GEOTECHNICAL STUDY
Proposed Three Single-Family Residences
35 Loma Vista Drive
Burlingame, California
for
MR. ALEX FLOCAS
NO. 06-197/7728-01
July 21, 2017
Rev. 5/14/19

# Purcell, Rhoades & Associates

Geotechnical, Environmental, & Materials Testing

3496 Buskirk Avenue, Suite 100 Pleasant Hill, CA 94523 Tel (925) 932-1177 Fax(925) 932-2795

No. 06-197/7728-01 July 21, 2017 Rev. 5/14/19

Mr. Alex Flocas 25 Loma Vista Lane Burlingame, CA 94010

Subject:

**GEOTECHNICAL STUDY** 

Proposed Three Singe-Family Residences

35 Loma Vista Drive Burlingame, California

Dear Mr. Flocas:

As requested, we have performed a Geotechnical Study for the proposed three lots at 35 Loma Vista Drive, Burlingame, San Mateo County, California (see Figure 1). The accompanying report presents the results of our site review, document review, exploratory boring excavations, our conclusions, and recommendations. In our opinion, the site is suitable for the proposed construction of three, single-family residences, provided the recommendations in this report are incorporated into the design and followed during construction.

The conclusions and recommendations submitted here are subject to our review of site development plans, including grading and foundation plans, and structural calculations, and observation of site grading, and foundation excavations. We reserve the right to submit supplemental recommendations at any time during construction or site development.

If you have questions, please contact this office at your convenience.

716

Daniel J. Rhoades, PE

Principal

G.E. 716, Exp. 6/30/19

ida/F772801.1

Very truly yours,

PURCELL, RHOADES & ASSOC

Dean Affeldt, PG

Principal

CEG-1108, exp. 07-31-19

Nº 1108

TEACHED Engineering

GEOLOGIST

OF CALIF

No. 06-197/7728-01 July 21, 2017 Page i Rev. 5/14/19

# **TABLE OF CONTENTS**

INTRODUCTION Purpose Proposed Development Scope Site Location and Description	 1 1
SITE SETTING	 2
SITE EXPLORATION AND LABORATORY TESTING Site Exploration Laboratory Testing	 4
SUBSURFACE CONDITIONS  General  Groundwater	 5
DISCUSSION	 6
CONCLUSIONS	 7
RECOMMENDATIONS Geotechnical Hazards Seismic Parameters Grading Foundations Pier Foundation System Concrete Slab-On-Grade, Floors Miscellaneous Flatwork Retaining Walls Seismic Surcharge Utility Trenches Pavement Design Drainage Miscellaneous Plan Review Site Safety	8 9 11 . 12 . 13 . 13 . 16 . 17 . 17 . 18 . 19
Site Safety	 . 20

No. 06-197/7728-01 July 21, 2017 Page ii Rev. 5/14/19

REFERENCES	2	22
FIGURES  Figure 1 - Site Location Map  Figure 2 - Site Plan and Boring Locations  Figure 3 - Area Geologic Map  Figure 4 - Log of Exploratory Boring 1  Figure 5 - Log of Exploratory Boring 2  Figure 6 - Log of Exploratory Boring 3  Figure 7 - Log of Exploratory Boring 4  Figure 8 - Log of Exploratory Boring 5  Figure 9 - Log of Exploratory Boring 6		
Appendix A Grading Specifications		

No. 06-197/7728-01 July 21, 2017 Page 1 Rev. 5/14/19

# INTRODUCTION

# <u>Purpose</u>

The purpose of this study was to evaluate the soil and geologic characteristics relevant to the development of three single-family residences at the subject site. General foundation engineering design and geotechnical recommendations are provided based on the physical characteristics of the subsurface materials and the geotechnical limitations created by the site's surface features.

# **Proposed Development**

The proposed development will consist of the construction of three, wood-framed, single-family dwellings. At the time of preparation of this geotechnical study, a specific house layout and design had not been determined. Figure 2, Site Plan and Boring Locations presents the proposed lot layout and the proposed development area established by City set-back limits.

Grading is anticipated to develop the site, with access to all three homes from Skyline Boulevard. Please contact our office if the conditions of the project change. We may need to revise our recommendations if changes occur in the configuration of the structures, the type of construction, or the proposed loads.

#### Scope

The scope of work for the proposed development included the following: researching soil and geotechnical data, the logging of six exploratory borings, laboratory testing of relatively undisturbed samples of soil and rock encountered in the borings, analyzing the soil data compiled during the exploration, and reporting our findings and recommendations. This study did not include assessments for environmental concerns, toxic substances or soil or groundwater contamination and is limited to the

No. 06-197/7728-01 July 21, 2017 Page 2 Rev. 5/14/19

immediate vicinity of the location of the planned structures. If additional

recommendations are required, please contact this office.

Site Location and Description

The site area is located between Loma Vista Drive on the west and Skyline Boulevard

on the east, with a descending slope below the private drive section of Loma Vista

Drive. The northern-most lot's upper slope is slightly steeper than 2:1 horizontal to

vertical (H:V), with the middle slope area on the order of approximately 3:1, H:V, and

the lower slope area generally flat (see Figure 2). It appears from the site plan that the

structures will be constructed partly upon the slope and partly on the flat section of the

property.

The site is currently vacant, with trees on the sloping ground and native grasses on the

flat area. A shallow, rough graded ditch that provides surface drainage through the site

is located along the eastern limit of the site (see Figure 2). It was noted during a site

review after recent rains that water ponds at the flat portion of the northern lot.

SITE SETTING

General Geologic Setting

The geologic structure of the Bay Area is complex and has been molded by numerous

mountain building events. This geologic structure is characterized by extensive folding,

faulting, and fracturing of variable intensity. The folds and faults trend northwesterly

and comprise the pronounced northwest tending ridge-valley system. The oldest

geologic formations in the Bay Area are probably of Jurassic age, 138-205 million years

ago, (Kith, et al. 1988). These formations have been subjected to repeated episodes

of deformation. By comparison, the youngest formations (Quaternary age - last 2

million years) have been only mildly flexed.

According to Brabb, Graymer, and Jones (1998), the site area is mapped as underlain by greenstone of the Franciscan Complex (see Figure 3, Area Geologic Map). This unit is regionally described by Brabb et al, as including dark-green to red, altered basaltic rocks, including flows, pillow lavas, breccias, tuff breccias, tuffs, and minor related intrusive rocks.

The U.S. Geological Survey Professional Paper entitled, "Relative Slope Stability and Land-Use Planning (1979), indicates that the site area is in a zone listed as, "Category 3", "Generally Stable to Marginally Stable", in "Areas of greater than 15% slope that are not underlain by landslide deposits or bedrock units susceptible to landsliding."

#### **Seismic Considerations**

The subject site lies within the San Francisco Bay Area, a region of high seismic activity. The probability is very high for a major earthquake to occur in the Bay Area within the economic lifetime of the proposed structures. Several active and potentially active faults occur in the region. The following active faults are listed with their distance from the site, and their respective moment magnitude earthquake.

<u>Fault</u>	<u>Distance, miles</u>	Moment Magnitude
San Andreas	1/4	8.0
Monte Vista-Shannon	12-1/2	6.7
San Gregorio	6-1/2	7.4
Hayward	18	7.3
Calaveras	26-1/2	6.9

The Serra fault, a series of southwesterly dipping thrust faults are located approximately 1850 feet northeast of the site (Brabb and Olson, 1986). The Serra fault has been shown to displace Pleistocene age materials, but has not been unequivocally

No. 06-197/7728-01

July 21, 2017

Page 4 Rev. 5/14/19

proven to displace Holocene age material, and is not zoned by the California Geologic

Survey as being potentially active.

The regional site area would be susceptible to ground shaking and ground failure

during a major earthquake on the San Andreas, Monte Vista-Shannon, San Gregorio

and Hayward, and Calaveras faults. The seismic risk to a structure depends on the

distance from the epicenter; the characteristics of the earthquake; the geologic,

groundwater, and soil conditions underlying the structure and its vicinity; and the nature

of the construction. A regional U.S. Geological Survey study of slope stability during

earthquakes in San Mateo County indicated that the site area would have a, "Very Low"

susceptibility to ground failure during an earthquake (Wieczoreck, and others, 1985).

Ground shaking at the site is likely to occur during the life of the project. Ground

acceleration values to be considered in design are provided in the Seismic Parameters

section of the Recommendations.

Liquefaction Potential

Liquefaction occurs when loose, saturated, granular deposits change from a solid to a

liquid state due to increased pore pressure during cyclic seismic loading. Our site

review and exploratory borings did not indicate the presence of any loose sand deposits

that would be subject to the affects of liquefaction.

SITE EXPLORATION AND LABORATORY TESTING

Site Exploration

Field exploration of the site, conducted on June 6, 2017, consisted of the drilling of six

exploratory borings using a truck-mounted B-24 (Borings 1 through 4), and a portable,

Minute-Man type drill rig (Borings 5 and 6). All borings were terminated within dense

bedrock, with the maximum depth explored approximately 23 feet below existing grade.

No. 06-197/7728-01 July 21, 2017 Page 5

Rev. 5/14/19

Please see Figure 2, Site Plan and Boring Locations for the location of all test borings.

The logs of the exploratory borings are presented as Figures 4 through 9.

Relatively undisturbed soil samples for laboratory testing were recovered in a 2.5-inch outside diameter (OD) California sampler or a 2-inch OD split spoon sampler driven by repeated blows of either a 140-pound hammer (Borings 1 through 4), or a 70-pound slide hammer free-falling 30-inches per blow. The number of blows applied to advance the sampler was recorded for each 6 inches of penetration and then converted to Standard Penetration Test values and recorded on the Exploratory Boring Logs

(Figures 4 through 9).

**Laboratory Testing** 

Laboratory testing was conducted on selected borehole samples to obtain data on dry density, moisture content, Atterberg Limits, and unconfined compressive strength. Test results are shown on the Exploratory Boring Logs (Figures 4 through 9).

SUBSURFACE CONDITIONS

General

The borings encountered surficial materials of stiff to very stiff clayey silt, and silty clay, and loose to medium dense silty sand, underlain by a dense to very dense bedrock of welded tuff breccia that has the consistency similar to that of a dense fractured sandstone. The borings on the hill slope portion of the site (Borings 2, , 5, and 6) encountered weathered bedrock material on the order of 3 to 5 feet below existing grade. Borings on the flatter portion of the site (Borings 1, and 3) encountered weathered bedrock material on the order of 19 to 21 feet below existing grade. Boring 4 was located within the northern-most lot at the transition from hillside to the flat area and encountered weathered bedrock materials at a depth of approximately 10 feet below existing grade.

Page 6

Rev. 5/14/19

Laboratory tests indicated the surface soil has a Liquid Limit of 39 and a Plasticity Index

of 16. This would indicate a low to moderate expansive condition with varying moisture

content. Using the statistical methods of Attom and Barakat (2000), the average

anticipated uplift pressure against a grade berm or footing during a wetting cycle may

be on the order of 1,500 pound per square foot (psf).

Groundwater

Free water was encountered in Borings 1 and 3 at an approximate depth of 19 and 20

feet below grade, respectively. The remaining borings did not extend to a depth that

would be anticipated to encounter groundwater. Due to the nature of the subsurface

materials encountered, zones of limited, perched groundwater may be seasonally

encountered within the matrix of the bedrock unit. Water levels will vary due to climatic

conditions, and the works of man.

DISCUSSION

The exploratory borings indicate that the site is underlain by moderately expansive

surficial materials, with an underlying dense to very dense, weathered and fractured

volcanic tuff breccia bedrock unit that has a consistency similar to that of a fractured

sandstone. Due to the chaotic nature of the Franciscan Complex, bedrock types and

consistency can vary within short distances, and depth.

Site development will require grading, and will likely include the construction of retaining

walls. Since the house footprint will likely be placed partially upon the slope and

partially upon the flat area of the site, a pier and grade beam foundation system is

recommended to provide a uniform bearing area and reduce the potential for excessive

differential foundation movement. Groundwater may be encountered in piers drilled in

the flat areas.

Page 7

Rev. 5/14/19

Surface drainage controls will be necessary for site development. Ponding was noted

at the northern lot limits after a rain period, and drainage improvements will be needed

at this location.

The site is near the active San Andreas fault and will be subject to very strong to violent

ground shaking in the event of a near-source maximum moment earthquake event.

**CONCLUSIONS** 

The following conclusions are based on the results of our study for the proposed

development.

1. It is our opinion that proposed construction is feasible from a geotechnical

viewpoint provided the recommendations contained in this report are followed.

2. Site observations and published information indicate that portions of the shallow

soil veneer may be characterized as moderately expansive. The weathered

bedrock unit is a mix of silty sand with blebs of silty clay with fractured rock

fragments. Due to potential localized variations in underlying bedrock type, soil

and bedrock materials of higher expansion potential, are possible at this site.

3. The hazard of seismic shaking is common to the geographic area; therefore, very

strong to violent seismic ground shaking should be expected to occur within the

economic life of the proposed structures. The potential for structural damage as

a result of ground shaking depends on the structural design of the structures.

4. It is our opinion that a low liquefaction hazard exists at the project site.

5. It is our opinion that the proposed single-family, wood-framed structures may be

supported on a pier and grade beam foundation system

No. 06-197/7728-01 July 21, 2017 Page 8 Rev. 5/14/19

- Based upon our review of published information and site reconnaissance, it is our opinion that there is presently no indication of landslides that would be an impact to the proposed construction.
- 7. It is our opinion that construction of this proposed structures, if constructed in accordance with the recommendations provided herein, will not result in an adverse impact to the soils, slope stability and drainage of the project site area.

# **RECOMMENDATIONS**

# **Geotechnical Hazards**

Risk of geotechnical hazards will always exist due to uncertainties of geologic conditions and the unpredictability of seismic activity in the Bay Area. However, in our opinion, based on available data, there are no indications of geotechnical hazards that would preclude use of the site for the proposed development. The proposed structures should be designed to meet current *California Building Code* (CBC) requirements to limit potential damage from ground shaking.

A representative of this office must perform a Plan Review of construction plans and structural calculations to confirm that the recommendations to be provided in the Geotechnical Study are considered in the design and construction of the project.

During construction, a representative of this office must observe grading operations, and foundation excavations, and to perform field density compaction testing to verify confirm that the geotechnical aspects of the construction was performed in accordance with the recommendations of the Geotechnical Study. PRA reserves the right to provide supplemental recommendations at any time during site planning and construction.

No. 06-197/7728-01 July 21, 2017 Page 9 Rev. 5/14/19

#### **Seismic Parameters**

The following seismic shaking criteria is provided for consideration by the Project Structural Engineer in the foundation design of the proposed development. The nearest known seismic source is the San Andreas fault (Type A), at a distance of approximately 0.4 km. Using the U. S. Geological Survey interactive website for acceleration parameters, we recommend the following near-source seismic values:

# SEISMIC CRITERIA VALUE

Site Class	С
S <sub>s</sub> Short Period 0.2-second Spectral Acceleration	2.603g
S <sub>1</sub> 1.0 Second Spectral Acceleration	1.250g
Site Coefficient F <sub>a</sub>	1.0
Site Coefficient F <sub>v</sub>	1.3
Max. Short Period Spectral Response Acceleration	
$SM_s = F_a \times S_s$	2.603g
Max. Spectral Response Acceleration 1-second period	
$SM_1 = F_v \times S_1$	1.625g
Damped Design Spectral Response - Short Period	
$SD_s = 2/3 \times SM_s$	1.735g
Damped Design Spectral Response - 1-second Period	
$SD_1 = 2/3 \times SM_1$	1.083g

# **Grading**

No grading plans were submitted to this office for consideration, however, we expect site development will require moderate grading for site development. The foundation and driveway will need to be stripped of vegetation and scarified to receive any fill. The organic material must be removed, and the loose soils subexcavated to firm material acceptable to the Geotechnical Engineer and then compacted per the recommendations provided below and in Appendix A to design finish grade.

Page 10

Rev. 5/14/19

Preliminary grading plans must be reviewed by our office in order to provide written

supplemental recommendations as needed for grading permit application and prior to

starting the grading operations.

All grading must conform to the specific recommendations of this report. However,

because of the potential for variability in encountered subsurface conditions on a

property, all conditions which may become exposed during grading cannot be foreseen

at this time. Therefore, it is recommended that site preparation and grading operations

must be performed under the observations of Purcell, Rhoades & Associates so that

actual conditions can be evaluated in the field as the job progresses. The Geotechnical

Engineer must be notified at least 48 hours prior to commencement of any grading

operations so that arrangements can be made to provide observation and testing

services.

Due to the variability of bedrock types in the site area, all cut slopes must be evaluated

by an Engineering Geologist from this office during grading. If necessary, supplemental

slope mitigation recommendations would be provided depending upon the material and

structural features (e.g., bedding, joints, and fractures) exposed by the cut slopes.

For compaction specifications, the upper 18 inches of subgrade below driveway

sections, and fill placed within keyways should be moisture conditioned to 3 to 5

percent over the optimum moisture content and compacted to a minimum of 95 percent

relative compaction in accordance with ASTM D1557. All other areas of fill should be

placed at a minimum of 3 to 5 percent over the optimum moisture content and a

minimum of 90 percent relative compaction, except the top 24 inches of material

underlying concrete flatwork or concrete slabs where expansive soils may be present.

At these locations, the subgrade should be moisture conditioned to a minimum of 5

percent over the optimum moisture content and the compaction should range from 85

percent to a maximum of 90 percent. On-site soil generated by site grading may be

No. 06-197/7728-01 July 21, 2017 Page 11 Rev. 5/14/19

used as fill provided that the soil is free of deleterious and organic materials and that it has been approved for use as fill by the Geotechnical Engineer. Samples of any proposed import fill planned for use on this project should be submitted to the Geotechnical Engineer for approval and appropriate testing no less than four working days before the expected delivery to the job site. See also Appendix A for Recommended Grading Specifications for implementation in the development of this site.

## **Foundations**

Any proposed dwelling must be supported upon a rigid foundation system that is supported upon piers with a grid of interlocking structural grade beams. The foundation contractor should be informed of the anticipated nature of the underlying bedrock, in order to provide the appropriate excavation method to achieve design depth. It is anticipated that the residence will be constructed using typical wood framing in conjunction with wood diaphragms in order to distribute seismic and wind shear to the foundation system. Structural loads for this type of construction are expected to be low to moderate.

The following geotechnical design criteria should be implemented at the discretion of the Structural Engineer based upon his review and design in conformance with current industry standards and the Geotechnical recommendations of this Geotechnical Study.

# Pier Foundation System

Pier Size

Minimum diameter 18 inches with vertical forces acting in both directions using a skin friction value of 750 psf. Piers must have a minimum of 6 feet into non-yielding bedrock material as determined by the Geotechnical Engineer or his representative

No. 06-197/7728-01 July 21, 2017 Page 12 Rev. 5/14/19

Passive Value 400 pcf-efw acting over 1-1/2 pier diameters, initiating at

a depth of 4 feet below surface grade.

Active Value 55 pcf-efw acting over twice the pier diameter to a depth

of 4 feet below surface grade.

To reduce the potential for settlement, we recommend that the pier excavations be cleaned of slough and loose material prior to placing steel reinforcement and concrete. Grade beams should be embedded a minimum of 6-inches below surface grade and designed to resist an uplift pressure of 1,500 psf.

A representative from our firm must be present to observe the pier drilling excavation to confirm the uniformity and the competence of the materials and embedment into acceptable non-yielding material.

#### Concrete Slab-On-Grade, Floors

We recommend that the minimum slab-on-grade floor thickness for the garage be 5-inches, underlain by 6 inches of capillary break material. The capillary break material can consist of 6 inches of 3/4-inch uniform graded rock, or 2 inches of sand, a 10 mil visqueen and 4 inches of 3/4-inch capillary break rock material. Reinforcement should be as directed by the Structural Engineer with the minimum reinforcement of No. 4 reinforcing bars spaced at 18-inches on-center in a grid pattern, or with an alternate reinforcement system as required by the Project Structural Engineer. The slabs shall be floated to allow for soil expansion and contraction. The reinforcement should be supported by concrete dobies to support the steel prior to the concrete placement in order to position the steel for the greatest efficiency in minimizing the cracking of the slab. The moisture retarder membrane, if used, should be placed in accordance with the manufacturer's specifications. Any punctures or damage to the membrane that may occur must be repaired in accordance with the manufacturer's specifications. Some moisture transmission should be expected where a membrane vapor retarder is

Page 13

Rev. 5/14/19

not utilized. Prior to membrane placement, the soil subgrade must be moisture

conditioned as approved by the Geotechnical Engineer.

Crack control joints should be located as directed by the Structural Engineer. The

subgrade in the slab area must be moisture conditioned by extended sprinkling prior

to placement of the concrete.

Recommendations presented in the American Concrete Institute should be complied

with for all concrete placement and curing operations. Improper curing techniques

and/or excessive slump (water-cement ratio) could cause excessive shrinkage,

cracking, or curling.

Miscellaneous Flatwork

Concrete slab-on-grade access facilities should consist of a minimum 5 inch slab

reinforced with no. 4 bar, 18 inches on-center, underlain by a 4 inch cushion of granular

materials A deepened edge around the slab exterior 6 inches into the subgrade is

recommended to prevent storm water from entering the granular subbase materials.

The owners must be advised that, due to the expansive nature of the site's surface

materials, some vertical displacement of exterior flatwork, sidewalks, driveways, and

pavements should be anticipated. Proper site drainage, maintenance and controlling

landscape irrigation is recommended to reduce the amount of vertical displacement that

may occur.

Retaining Walls

The following recommendations are for a retaining wall founded on piers extended into

the bedrock encountered during our subsurface investigation. The retaining wall

should be designed for a fully-drained condition. Table 1 presents our design criteria

No. 06-197/7728-01 July 21, 2017 Page 14 Rev. 5/14/19

recommendations for up to a maximum 8-foot high retaining wall. Design pressures are expressed as equivalent fluid pressures.

# TABLE 1 RETAINING WALL DESIGN CRITERIA

Lateral Pressures:	Active Pressure	Passive Pressure*
Gradient of Backfill	(pcf)	(pcf)
2:1 (maximum or less	55	See concrete pier lateral loads for
		minimum depth and loading condition

Walls restrained at the top should be designed with a 100 psf uniform lateral surcharge load in addition to the lateral earth pressures given above. Any wall structurally connected at the top to the structure should be considered a restrained wall.

The design criteria are applicable for walls which have fully-drained conditions and are no greater than 8 feet in height. To provide fully-drained conditions, a gravel drainage system should be constructed behind the walls and have a minimum width of 12 inches. We recommend that the drainage system commence behind and at the bottom of the retaining structure's heel and extend up the retaining wall to 1 foot below grade. The drainage system should consist of Cal Trans Class 2 permeable material drain rock and approved by our geotechnical engineer or the engineer's representative. A 4-inch diameter, perforated rigid drainpipe should be installed at the bottom of the drainage system with holes facing down. The pipe should be sloped at a minimum of 2 percent and discharged to a suitable drainage facility away from all structural improvements.

Page 15 Rev. 5/14/19

For backfill behind retaining structures, the zone between the structure's drainage

system and the limits of excavation may be backfilled with on-site soil; however,

granular material is recommended for lower lateral earth pressures. Should on-site

soils be used in the zone between the structure's drainage system and the limits of

excavation, the backfill materials should be compacted to 90 percent of the maximum

dry density at 2 to 4 percent above optimum moisture content as determined by

American Society of Testing Materials (ASTM) D1557 test methods. Over-compaction

behind retaining structures tends to increase the lateral pressure against the structures

and, therefore, should be avoided.

Any retaining walls must be designed for a fully-drained condition. Structural retaining

walls must be supported upon piers similar in design for the house piers. The retaining

wall design must be performed by the project Structural Engineer.

In general, all retaining walls must be free draining with a 4-inch diameter perforated

pipe (SDR 35 or equivalent) placed upon 1-inch of CalTrans Class II permeable drain

rock at the base of the wall and a minimum of 6 inches below any cold joint or where

potential seepage through the wall would be objectionable. The trench and pipe should

be sloped a minimum of 1 percent and discharged into a suitable outlet, with clean outs

at the start and every 100 foot of drain line. A 12-inch wide minimum section of

CalTrans permeable material should then be backfilled to within 1 foot of the surface

then capped with compacted clay material up to the finish surface.

To reduce the potential for moisture transmission through the retaining wall, where the

retaining wall is used as part of a building or where moisture transmission would be

objectionable, it is recommended that the appropriate face be hot-mopped in

accordance with the manufacturer's specifications and an impermeable membrane be

placed over the hot-mopped surface to protect the surface from damage during drain

rock placement. It is important that the surface drainage controls also be installed to

Page 16

Rev. 5/14/19

reduce the potential for moisture transmission. Where retaining walls form part of the

building, deflection calculations or allowance for wall movement should be included in

the final planning for the structure.

Seismic Surcharge

For the purpose of providing a seismic surcharge to be considered in the design of the

retaining walls in excess of 6 feet in height at this site, the methodology proposed by

Seed and Whitman (1970), provides a simplified dynamic lateral force component for

yielding walls as:

 $\Delta P_{AE} \sim (\frac{1}{2}) (3/4) k_h \gamma H^2 = (3/8) k_h \gamma H^2$ 

It has been recommended that kh be taken as equal to the site acceleration that is

consistent with the design motions of  $k_h = S_{DS}/2.5$ , where  $S_{DS}$  is the design, 5-percent-

damped, spectral response acceleration parameter at short periods (i.e., period of 0.2

seconds). The unit weight of soil (γ) should be assumed as 120 pcf. Seed and

Whitman recommended that the resultant dynamic thrust be applied at 0.6H above the

base of the wall (i.e., similar to an inverted triangular pressure distribution.

Therefore, the wall design includes the active soil lateral pressure values as provided

in this report, with the resultant acting at a distance of H/3 from the base of the wall;

and the seismic surcharge value, as discussed above, with the resultant acting at a

distance of (0.6\*H) from the base of the wall. This assumes a fully drained condition.

Any superimposed loads other than retained earth, shall be considered as surcharges.

Loads applied within a horizontal distance equal to wall stem height, measured from the

back face of the wall shall be considered as a surcharge.

No. 06-197/7728-01

July 21, 2017

Page 17 Rev. 5/14/19

**Utility Trenches** 

Utility trenches that parallel the sides of the buildings should be placed so that they do

not extend below a line sloped down and away at a slope of 2H:1V (horizontal to

vertical) from the bottom outside edge of the perimeter foundations.

All trenches should be backfilled with native materials compacted uniformly to a

minimum 90% relative compaction, or as specified by local codes. If local building

codes require use of sand as the trench backfill, all utility trenches entering the building

should be provided with an impervious seal of either cohesive soil or lean concrete

where the trench passes under the building perimeter. The impervious plug should

extend 4 feet into, and out of, the building perimeter. Jetting of trench backfill is not

recommended as it may result in an unsatisfactory degree of compaction.

Utility trench safety is the responsibility of the underground utility contractor. It is their

responsibility to ensure that all Cal/OSHA regulations regarding site safety and trench

stability are adhered to during trenching, placement of utilities and placement of

compacted trench backfill. The contractor's designated Competent Person must

monitor the soil conditions as required by Cal/OSHA.

Pavement Design

It is our understanding that it is intended to use concrete pavers to construct a common

courtyard at the middle lot leading off Skyline Boulevard that will service the respective

individual private driveways. Pavers are typically constructed using a sequence of

materials recommended by the manufacturer. It is recommended that the sequence

of materials be placed upon a subbase that is prepared by subexcavating

approximately 18 inches, scarifying the base and recompacting the base and

replacement fill that is moisture-conditioned to between 3 and 5 percent over optimum

moisture content and compacted to minimum 95 percent relative compaction. It is

Page 18

Rev. 5/14/19

recommended that this office receive a description of the respective thickness and

material types that will comprise the paver system.

We recommend that the owners be advised that some vertical displacement of exterior

flatwork, sidewalks, pavers, driveways, and pavements be anticipated. We also

recommend pre-soaking of all exterior flatwork areas be performed to the satisfaction

of the Geotechnical Engineer or his representative prior to the placement of concrete

or other covers.

**Drainage** 

Surface waters must not be allowed to pond or saturate soils adjacent to the building

foundations. To preclude this, it will be necessary to direct all water collected from roof

down spout into tightlines that will direct the collected drainage away from the building

foundation and into suitable discharge points.

We recommend that a minimum slope gradient of 5 percent down and away from the

structure perimeters be applied to the finished subgrade (including topsoil) for a

distance of at least 5 feet. A drainage swale or positive slope must be provided on the

uphill side of the structures in order to remove surface water from the pad areas to an

acceptable discharge point or storm drain inlet.

Undrained planted areas located immediately adjacent to the structures must be

avoided. If vegetation must be planted adjacent to a structure, plants that require very

little moisture should be used. The drip line of all trees should fall at least 10 feet from

the perimeter of any foundation element. Sprinkler heads should not be placed where

they would saturate the foundation soil; a drip irrigation system is preferred. No

flatwork should be used adjacent to the foundation where a trapped water condition

could occur. The use of drop-inlets in such areas are necessary to control the

discharge of irrigation or storm water at these locations.

Page 19

Rev. 5/14/19

Surface waters must not be allowed to pond or saturate soils adjacent to the

foundation. To preclude this, it will be necessary to direct all water away from the

foundation and into suitable storm water control systems. We recommend that a

positive slope gradient of 3 to 5 percent down and away from the structure perimeter

be applied to the finished subgrade (including topsoil) for a distance of at least 5 feet.

Miscellaneous

Our site review did not reveal the presence of buried items such as leaching fields, and

storage tanks, etc. in the proposed site area. It is possible, however, that such items

may be present. If such buried items are encountered during excavations of

foundations, our firm should be notified immediately to provide recommendations for

proper procedures. Also, this study did not include investigations for toxic substances

or groundwater contamination of any type, the potential for corrosive soils, or soils with

reactivity to concrete. If such conditions are encountered during site development,

additional studies will be required.

Plan Review

Before submitting design drawings and construction documents to the appropriate local

agency for approval, copies of the documents must be reviewed by our firm to ensure

that the recommendations in this report have been effectively incorporated, and to

provide supplemental recommendations, where needed.

Site Safety

All excavations and site work must comply with applicable local, state, and federal

safety regulations. Construction site safety is the responsibility of the contractor, who

shall be solely responsible for the means, methods, and sequencing of construction

operations. Our services and recommendations for site safety are advisory and not

supervisory.

Page 20 Rev. 5/14/19

**Construction Observations** 

A representative of this firm must be present during grading operations and foundation

excavation to observe that the work performed is in conformance with specifications

and recommendations provided here. Records will be maintained of our site visits and

test results.

At the completion of grading, and foundation excavation, we will submit a summary of

our observations along with any necessary supplemental recommendations.

To assure that our personnel are at the site when needed, we require that you notify

us at least 2 working days before the task begins.

No. 06-197/7728-01 July 21, 2017 Page 21

Rev. 5/14/19

**LIMITATIONS** 

This report has been prepared for the exclusive use of Alex Flocas and his consultants

for specific application to the proposed development. If changes occur in the nature,

design location, or configuration of the proposed development, the conclusions and

recommendations contained here shall not be considered valid. Changes must be

reviewed by our firm.

The analysis, opinions, conclusions and recommendations submitted in this report are

based in part on the referenced materials, site visit and evaluation, and subsurface

exploration. The nature and extent of variation among exploratory test borings may not

become evident until construction. If variations appear, it will be necessary to re-

evaluate or revise recommendations made in this report.

The recommendations in this report are contingent on conducting an adequate testing

and monitoring program during construction of the proposed development. Unless the

construction monitoring and testing program is provided by or coordinated with our firm,

Purcell, Rhoades & Associates, inc. will not be held responsible for compliance with

design recommendations presented in this report and other supplemental reports

submitted as part of this report.

Our services have been provided in accordance with generally accepted geotechnical

engineering practices. No warranties are made, express or implied, as to the


professional opinions or advice provided. Recommendations contained in this report

are valid for a period of 2 years; after 2 years they must be reviewed by this firm to


determine whether or not they still apply.


#### **REFERENCES**

- Attom, M. F., and Barakat, S., 2000, Investigation of Three Methods for Evaluating Swelling Pressure of Soils: Environmental & Engineering Geoscience, V. VI, No. 3, August 2000, pp. 293-299.
- Brabb, E. E., Graymer, R. W., and Jones, D. L., 1998, Geology of the Onshore Part of San Mateo County, California: A Digital Database: U.S.G.S. Open File 98-137.
- Brabb, E. E., and Olson, J. A., 1986, Map Showing Faults and Earthquake Epicenters in San Mateo County, California: U. S. G. S. Misc. Investigations Series Map I-1257-F.
- Borcherdt, R.D., 1975, "Studies for Seismic Zonation of the San Francisco Bay Region", U.S.G.S. Professional Paper 941-A.
- Brown, R.D., Jr., 1970, "Faults that are Historically Active or That Show Evidence of Geologically Young Surface Displacement": U.S.G.S. Misc. Field Studies Map-331.
- California Dept. Conservation Division of Mines and Geology, February 1998, "Maps of Known Active Fault Near-Source Zones in California and Adjacent Portions of Nevada": International Conference of Building Officials.
- California Geological Survey, 2003, "The Revised 2002 California Probabilistic Seismic Hazards Maps.
- CalTrans, 2012, Fault Database.
- Nilsen, T.H., Wright, R.H., Vlasic, T.C., and Spangle, W.E., 1979, "Relative Slope Stability and Land-Use Planning in the San Francisco Bay Region, California", U.S.G.S. Professional Paper 944.
- Ploessel, M.R. and Slosson, J.E., 1974, Repeatable High Ground Accelerations From Earthquakes Important Design Criteria: California Geology, September.
- U. S. Geological Survey, 2003, Seismic Design for Buildings (interactive web site).
- Wieczoreck, G. F., Wilson, R. C., and Harp, E. L., 1985, Map Showing Slope Stability During Earthquakes in San Mateo County, California: U. S. G. S. Misc. Investigation Series Map I-1257-E.



NOTES SOURCE:	DATE JULY 2017  JOB NO. 7728-01	Purcell, Rhoades & Associates Consultants in the Applied Earth Sciences	
TOPOZONE,	DWG NO. F772801.FIG 1	SITE LOCATION MAP	FIGURE NO.
MONTARA MOUNTAIN QUADRANGLE	DRAWN IDA	35 LOMA VISTA DRIVE	1
	CHK'D DJR	BURLINGAME, CALIFORNIA	
0	APP'D DJR	CLIENT ALEX FLOCAS	REV NO





# Key

af artificial fill
Qtm Merced Formation, sandstone, siltstone, and claystone
Kjf Franciscan Complex
fs sandstone

fg greenstone fsr sheared rock - melange sp Serpentinite

NOTES	DATE JULY 2017 JOB NO. F7728-01	— Purcell, Rhoades & Associates Consultants in the Applied Earth Sciences	
SOURCE: BRABB, E. E., GRAYMER, R. W., AND	DWG NO. F772801.FIG 3	AREA GEOLOGY MAP	FIGURE NO.
JONE, D. L.	DRAWN IDA	35 LOMA VISTA DRIVE	3
	CHK'D DJR	BURLINGAME, CALIFORNIA	
	APP'D DJR	CLIENT ALEX FLOCAS	REV. NO.

#### **EXPLORATORY BORING LOG** CLIENT: Mr. Alex Flocas PAGE 1 OF 1 LOGGED BY: IDA DATE DRILLED: 06/06/17 PROJECT NO.: 7728-01 BORING NO. BORING ELEV.: E.G. DRILL RIG: NORTH STAR DRILLING B-1 BORING DIAM.: 4 INCHES WEIGHT OF HAMMER: 140-POUND DROP: 30 INCHES **FIELD** DESCRIPTION LABORATORY USCS LETTER SYMBOL CONSISTENC SAMPLE NO. BLOWS / FT. DEPTH (FT.) PLASTICITY INDEX (%) MATERIAL DESCRIPTION AND REMARKS SAMPLE DECORATIVE BARK COVER LL: 39 Pl: 16 PP: 1.5 ĊĹ 21 STIFF 109 B1-1 10 CLAYEY SILT, dark brown, moist B1-2 15 TRACE OF FINE CLAYEY SAND WITH SOME 1/8-INCH PEBBLES B1-3 27 CLAYEY SILT, light brown, moist CŁ 104 22 2600 PP: 4.0 - VERY STIFF DRILLING AT 16 FEET 18-INITIAL WATER AT 19 FEET DENSE B1-4 39 RX 19 PP: 4.5 TUFF BRECCIA, greenish brown, sheared, wel - INCREASING RESISTANCE; VERY DENSE VERY DENSE TUFF BRECCIA, greenish brown, sheared, near refusal, wel B1-5 50/6 SPT TD BORING TERMINATED AT APPROXIMATELY 23 FEET. GROUNDWATER ENCOUNTERED AT 19 FEET HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE 32 FIGURE NO. **EXPLORATORY BORING LOG B-1** Purcell, Rhoades & Associates 35 Loma Vista Drive 4 Burlingame, CA Consultants in the Applied Earth Sciences **ALEX FLOCAS**

# **EXPLORATORY BORING LOG** CLIENT: Mr. Alex Flocas LOGGED BY: IDA DATE DRILLED: 06/06/17 PAGE 1 OF 1 PROJECT NO.: 7728-01 BORING NO. DRILL RIG: NORTH STAR DRILLING BORING ELEV.: E.G. B-2 BORING DIAM .: 4 INCHES WEIGHT OF HAMMER: 140-POUND DROP: 30 INCHES **FIELD** DESCRIPTION LABORATORY POCKET PENETROMETER, TSF USCS LETTER SYMBOL CONSISTENCY DRY DENSITY (PCF) SAMPLE NO. BLOWS / FT. PLASTICITY INDEX (%) MATERIAL DESCRIPTION AND REMARKS SAMPLE CLAYEY SILT, reddish brown, dry LOOSE SILTY SAND, motiled yellow and reddish brown, dry 95 16 B2-1 VERY DENSE PP: 4.5+ B2-2 54 WEATHERED TUFF BRECCIA, light yellow brown, sheared 117 14 2000 RX 10 11 SPT 12 VERY DENSE WEATHERED TUFF BRECCIA, light yellow brown, sheared, dry ЯX BORING TERMINATED AT APPROXIMATELY 10-1/2-FEET. NO GROUNDWATER ENCOUNTERED AT TIME OF DRILLING HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE 28 30 32 FIGURE NO. **EXPLORATORY BORING LOG B-2** Purcell, Rhoades & Associates 35 Loma Vista Drive 5 Burlingame, CA Consultants in the Applied Earth Sciences **ALEX FLOCAS**

#### **EXPLORATORY BORING LOG** CLIENT: Mr. Alex Flocas PAGE 1 OF 1 LOGGED BY: IDA DATE DRILLED: 06/06/17 PROJECT NO.: 7728-01 BORING NO. BORING ELEV.: E.G. DRILL RIG: NORTH STAR DRILLING **B-3** BORING DIAM .: 4 INCHES WEIGHT OF HAMMER: 140-POUND DROP: 30 INCHES **FIELD** LABORATORY DESCRIPTION USCS LETTER SYMBOL MOISTURE CONTENT (%) CONSISTENCY DRY DENSITY (PCF) DEPTH (FT.) SAMPLE NO. BLOWS / FT. PLASTICITY INDEX (%) MATERIAL DESCRIPTION AND REMARKS PERCENT PASSING NO. 200 SAMPLE PP: 4.0 SM MEDIUM DENSE 11 B3-1 CLAYEY SILTY SAND, with rock fragments, reddish brown, moist DRILLING HARD AT 6 FEET PP: 4.5 10,500 SILTY CLAY, reddish brown with SANDSTONE fragments, light yellow brown, moist 110 19 VERY CL 10\_ 12 13 SILTY CLAY, reddish brown mixed with sheared sendstone fragments PP: 4.5 18-CL VERY STIFF B3-4 23 PP: 4.5 RХ SILTY CLAY, reddish brown with increasing TUFF BRECCIA fragment volume, sheared INCREASING RESISTANCE; VERY DENSE INITIAL WATER AT 22 FEET 23 B3-5 VERY DENSE PP: 4.5 TUFF BRECCIA, fractured with some reddishbrown sitty clay, water on barrel 37 RX BORING TERMINATED AT APPROXIMATELY 23-1/2-FEET, GROUNDWATER ENCOUNTERED AT 22 FEET HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE 29 30 31<u>-</u> 32 FIGURE NO. **EXPLORATORY BORING LOG B-3** Purcell, Rhoades & Associates 35 Loma Vista Drive 6 Burlingame, CA Consultants in the Applied Earth Sciences **ALEX FLOCAS**

# **EXPLORATORY BORING LOG** LOGGED BY: IDA PAGE 1 OF 1 DATE DRILLED: 06/06/17

DRILL RIG: NORTH STAR DRILLING

CLIENT: Mr. Alex Flocas

PROJECT NO.: 7728-01

WEIGHT OF HAMMER: 140-POUND DROP: 30 INCHES

Consultants in the Applied Earth Sciences

**ALEX FLOCAS** 

BORING NO.

BORING ELEV.; E.G.

BORING DIAM.: 4 INCHES

**B-4** 

FI	IELI	D		DESCRIPTION				LABORATORY					
DEPTH (FT.)	SAMPLE	SAMPLE NO.	BLOWS/FT.	MATERIAL DESCRIPTION AND REMARKS	VONEIGHERING	CONSISTENCY	USCS LETTER SYMBOL	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	PERCENT PASSING NO. 200	PLASTICITY INDEX (%)	UNCONFINED COMPRESSIVE STRENGHT (PSF)	POCKET PENETROMETER, TSF
		B4-1	9	CLAYEY SILT, reddish brown with some rock fragments, moist	ST	TIFF	<b>C</b> L	107	22			3,200	PP: 3.5
0 1 2 3	25	B4-2	55	TUFF BRECCIA, light brown, moist	VEN	₹Y \\$£	RX						PP: 4.5
4 5 5 TI		B4-3	50/5	BORING TERMINATED AT APPROXIMATELY 23-1/2-FEET.	VE	RY NSE	RX						PP: 4.5
8 1 9 1 20 1 21 1 22 1				BORING TERMINATED AT APPROXIMATELY 23-1/2-FEET, NO GROUNDWATER ENCOUNTERED AT THE TIME OF DRILLING HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE									
3-13-13-13-13-13-13-13-13-13-13-13-13-13				·						***************************************			
28   29   20   20   20   20   20   20   20										**************************************			
3									RE NC 7				

# **EXPLORATORY BORING LOG** CLIENT: Mr. Alex Flocas PAGE 1 OF 1 LOGGED BY: IDA DATE DRILLED: 06/06/17 PROJECT NO.: 7728-01 BORING NO. BORING ELEV.: E.G. DRILL RIG: NORTH STAR DRILLING - MINUTE-MAN B-5 BORING DIAM,: 4 INCHES WEIGHT OF HAMMER: 70-POUND DROP: 30 INCHES LABORATORY FIELD DESCRIPTION USCS LETTER SYMBOL CONSISTENCY DEPTH (FT.) SAMPLE NO. BLOWS / FT. PLASTICITY INDEX (%) MATERIAL DESCRIPTION AND REMARKS SAMPLE PP: 4.5+ CL STIFF B5-1 16 CLAYEY SILT, light brown, moist - --- INCREASING RESISTANCE PP: 4.5+ DENSE 5,200 RX 109 21 B5-2 40 TUFF BRECCIA, weathered light brown, with some sandy clay, fractured, sheared, moist ΤĐ 8 BORING TERMINATED AT APPROXIMATELY 7-1/2 - FEET. NO GROUNDWATER ENCOUNTERED AT TIME OF DRILLING HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE 10 26-28 29 30-31– FIGURE NO. **EXPLORATORY BORING LOG B-5** Purcell, Rhoades & Associates 35 Loma Vista Drive 8 Burlingame, CA Consultants in the Applied Earth Sciences **ALEX FLOCAS**

# **EXPLORATORY BORING LOG** CLIENT: Mr. Alex Flocas LOGGED BY: IDA PAGE 1 OF 1 DATE DRILLED: 06/06/17 PROJECT NO.: 7728-01 BORING NO. DRILL RIG: NORTH STAR DRILLING - MINUTE-MAN BORING ELEV.: E.G. B-6 WEIGHT OF HAMMER: 70-POUND DROP: 30 INCHES BORING DIAM .: 4 INCHES FIELD DESCRIPTION LABORATORY CONSISTENCY USCS LETTER SYMBOL DRY DENSITY (PCF) DEPTH (FT.) PLASTICITY INDEX (%) MATERIAL DESCRIPTION AND REMARKS PERCENT PASSING NO. 200 CLAYEY SILTY SAND, dark brown, moist ST#FF CLAYEY SILT, light brown with sandslone fragments, moist CL VERY B6-1 TUFF BRECCIA, weathered light brown, fractured, moist RXPP: 4.5+ BORING TERMINATED AT APPROXIMATELY 4 FEET. NO GROUNDWATER ENCOUNTERED AT TIME OF DRILLING HOLE BACKFILLED WITH GROUT CUTTINGS DISPOSED ON-SITE 15 30 32 **EXPLORATORY BORING LOG B-6** FIGURE NO Purcell, Rhoades & Associates 35 Loma Vista Drive Burlingame, CA 9 Consultants in the Applied Earth Sciences ALEX FLOCAS

# **APPENDIX A**

# RECOMMENDED GRADING SPECIFICATIONS

PROPOSED THREE SINGLE FAMILY RESIDENCES
35 LOMA VISTA DRIVE
BURLINGAME, CALIFORNIA
PROJECT NO. 06-197/7728-01

No. 06-197/7728-01 July 21, 2017 Appendix A, Page 1 Rev. 5/14/19

#### APPENDIX A

#### RECOMMENDED GRADING SPECIFICATIONS

# PROPOSED THREE SINGLE FAMILY RESIDENCES 35 LOMA VISTA DRIVE BURLINGAME, CALIFORNIA for MR. ALEX FLOCAS PROJECT NO. 06-197/7728-01

## 1. General

- 1.1 These Recommended Grading Specifications (called "Specifications" here) provide general guidelines for soil engineering aspects of grading for the subject development. The Geotechnical Engineer from Purcell, Rhoades & Associates should be consulted prior to any site work connected with grading. Please refer to the following report(s) for other grading recommendations supporting these Specifications.
- 1. Purcell, Rhoades & Associates, dated 7/21/17 (rev. 5/14/19), Geotechnical Study, Proposed Three Single-Family Residences, 35 Loma Vista Drive, Burlingame, CA: Job No. 06-197/7728-01.
- 1.2 These Specifications include the following:
  - clearing, stripping, grubbing, and preparing areas to be filled
  - selecting materials for fill
    - placing, spreading, and compacting fill
    - completing subsidiary work necessary to conform to lines, grades, and slopes shown on accepted plans
    - protecting the soil in slab and foundation areas from drying out between grading and construction
- 1.3 Tests and observations shall be made by a representative from Purcell, Rhoades& Associates during the grading so that we can confirm that grading was

No. 06-197/7728-01 July 21, 2017 Appendix A, Page 2 Rev. 5/14/19

- performed according to these Specifications. Such confirmation in a Final grading report is often required to obtain a building permit.
- 1.4 Purcell, Rhoades & Associates shall be notified at least 2 working days prior to placement of fill so arrangements for testing and observation may be made.
- 1.5 Grading or placement of fill done without the presence of a representative of Purcell, Rhoades & Associates or without prior coordination between Purcell, Rhoades & Associates and the grading contractor shall be at the contractor's risk; Purcell, Rhoades & Associates will accept no responsibility for such work.

# 2. Testing

- 2.1 The American Society for Testing and Materials (ASTM) Test Procedure D 1557-78 shall be the standard test to define maximum densities for all compaction of fill. All densities shall be expressed as relative compaction in terms of the maximum dry density obtained in the laboratory by the foregoing standard procedure.
- 2.2 Field density tests shall be performed according to ASTM Test Procedures D 2922-81 and D 3017-88. The locations and number of field density tests shall be selected by the Geotechnical Engineer or the Engineer's Representative.

# 3. Clearing, Stripping, Grubbing, and Preparing of Areas to Be Filled

- 3.1 Trees, roots, vegetation, and organic surficial soil shall be removed from structural areas unless specified otherwise by Purcell, Rhoades & Associates. The depth of organic surficial soil to be removed will be recommended by the Geotechnical Engineer or the Engineer's Representative but, in general, will probably vary from about 2 to 4 inches.
- 3.2 Strippings are defined as surface vegetation and organic surficial soil. Strippings may not be used in fill unless specifically authorized and observed by the Geotechnical Engineer or the Engineer's Representative. Stripping may be stockpiled for landscaping use, with the approval of the landscape architect.
- 3.3 Soil deemed soft or unsuitable by the Geotechnical Engineer or the Engineer's Representative shall be removed. Loose fills and surface soil sloughs shall also be excavated.
- 3.4 Underground structures such as old foundations, abandoned pipelines, septic tanks, and leach fields shall be removed from the site.

No. 06-197/7728-01 July 21, 2017 Appendix A, Page 3 Rev. 5/14/19

- 3.5 The final stripping and excavation shall be approved by the Geotechnical Engineer or the Engineer's Representative before further grading is started.
- 3.6 The original ground on which the fill, foundation or slabs are to be placed shall be plowed or scarified at least 8 inches and until the surface is free from ruts, hummocks or uneven features which would tend to prevent compaction. The contractor shall observe the following guidelines:
  - Where the slope ratio of the original ground is steeper than 5:1 (horizontal to vertical), the bank shall be stepped or benched.
  - At the toe of the side slope fills, the base key shall be at least 12 feet in width, cut into firm, natural ground and sloped back into the hillside at a gradient of at least 2 percent.
  - Subsequent keys or benches shall be 10 feet wide and placed no more than 4 feet in vertical height from the previous key or bench unless otherwise recommended by the Geotechnical Engineer or the Engineer's Representative.
- 3.7 The native subgrade soil to receive fill shall be moisture-conditioned and compacted to the requirements specified in the referenced report and below:

Minimum relative compaction:

90 percent

Minimum moisture content:

3 percent over optimum

Special considerations:

85-90 percent compaction in designated expansive soil at 5 percent over optimum moisture condition.

# 4. Selecting Fill

- 4.1 The Geotechnical Engineer or the Engineer's Representative shall evaluate suitability of materials for compacted fills. The material shall be a soil or soil-rock mixture, free of organic matter or other deleterious substances. Within 3 feet of finished grade, the compacted fill shall contain no rocks or lumps over 6 inches in diameter and none that are more than 15 percent larger than 2-1/2 inches. Rocks greater than 6 inches in diameter shall be placed in deep fills as approved by the Geotechnical Engineer or the Engineer's Representative so that they are not nested and so compaction may be achieved around them.
- 4.2 If imported materials are needed, they must be approved by the Geotechnical Engineer or the Engineer's Representative prior to transporting the fill to the project. Unless otherwise exempted by the Geotechnical Engineer, they should meet the following requirements:
  - 1. The plasticity index shall not exceed 15.

2. No rocks shall exceed 6 inches in diameter.

# 5. Placing, Spreading, and Compacting Fill

- 5.1 The fill shall be placed in uniform lifts of not more than 8 inches in uncompacted thickness. Each layer shall be spread evenly and shall be thoroughly blade mixed during spreading to obtain uniformity of material. Before compaction begins, the fill shall be brought to a water content (as directed by the Geotechnical Engineer or the Engineer's Representative) that will permit proper compaction by either (1) aerating the material if it is too wet or (2) spraying the material with water if it is too dry.
- 5.2 After each layer has been placed, mixed, and spread evenly, it shall be compacted as specified in the referenced report and below:

Minimum relative compaction: 90 percent

Minimum moisture content: 3 percent over optimum

See Section 3.7 for expansive soil criteria

- 5.3 The contractor shall use appropriate equipment to compact the fill to the specified density. Compacting shall be performed while the fill is within the specified range of moisture content. Each layer shall be compacted over its entire area, and the compacting equipment shall make enough passes to achieve the required density.
- 5.4 Fill placed on slopes shall be compacted by means of suitable equipment. Benching of the slopes should be done in increments of 3 to 5 feet in height until the fill is brought to its specified height or as determined by the Geotechnical Engineer or the Engineer's Representative.
- 5.5 When sheepsfoot rollers are used for compaction, the density tests shall be taken in the compacted material below the surface disturbed by the roller. When these tests indicate that the density of any layer of fill, or portion thereof, is below the required density, it shall be reworked until the required compaction has been obtained.
- 5.6 Soil shall not be placed or compacted during periods of rain or on ground which is not drained of water. Soil which has been moistened by rain or other cause shall not be compacted until the moisture content is within the limits specified in the referenced report. Prior approval by the Geotechnical Engineer or the Engineer's Representative shall be obtained before continuing grading.

# 6. Backfilling Trenches

6.1 Geologic exploratory trenches (or other depressions), if any, within the proposed building or pavement areas, shall be re-excavated and backfilled to meet the requirements for compacted fill, as specified above.

6.2 The utility trenches extending under the perimeter foundation and concrete slabson-grade may require backfilling or plugging with impermeable soils at the building line with a 3-foot wide impermeable segment of compacted fill. Requirements will be specified during trench backfilling. Ponding or jetting of trench backfill is not recommended.

# 7. Removing Subsurface Pipes

- 7.1 The Geotechnical Engineer or Engineer's Representative shall designate the methods of removal of subsurface pipes. Depending upon depth and location, one of the following methods shall be specified:
  - The pipe shall be removed, and the trench shall be filled and compacted according to applicable requirements for compacting native soil (Section 3) or fill (Section 5).
  - The pipe shall be crushed in the trench, and the trench shall be filled and compacted according to applicable portions of Sections 3 and 5.
  - The ends of the pipes shall be capped with concrete to prevent entrance of water. The length of the cap shall be at least 5 feet.
- 7.2 Any wells encountered on the site shall be filled, buried and capped according to the requirements of the local regulatory agency. The final elevation of the top of the well casing shall be a minimum of 36 inches below any adjacent grade at the completion of grading or filling. Under no circumstances should structural foundations be placed over the capped wells.

## 8. **Grading Slopes**

- 8.1 Slopes shall be graded at gradients no steeper than 2:1 (horizontal to vertical) for fill and cut, except as noted in the referenced report.
- 8.2 After the slopes have been graded, they shall be track-rolled, and provisions shall be made for planting the slopes for erosion control. Drainage facilities shall be constructed to prevent water from flowing over slopes. No slope shall be left to stand through a winter season without erosion control.

## 9. <u>Installing Subdrains</u>

9.1 For subdrains, the contractor shall provide and install perforated pipe Standard Designation Ratio (SDR) 23.5 or equivalent approved by the Geotechnical Engineer or the Engineer's Representative and filter material for subdrains as shown on the plans or as directed by the Purcell, Rhoades & Associates. The following restrictions apply:

No. 06-197/7728-01 July 21, 2017 Appendix A, Page 6 Rev. 5/14/19

- 9.1.1 Clay drain tile, concrete drain tile and perforated clay pipe shall not be permitted. Use no wyes, tees, or other joints of these materials.
- 9.1.2 Porous concrete pipe, perforated asbestos-cement pipe, bituminous fiber or pipe of other materials shall be permitted only on written authorization of the Geotechnical Engineer.
- 9.1.3 The contractor shall use ½ by 3/4 inch drain rock wrapped within a filter fabric approved by our Geotechnical Engineer, unless otherwise permitted by written authorization from the Geotechnical Engineer.
- 9.1.4 Unless recommended otherwise by the Geotechnical Engineer or the Engineer's Representative, the contractor shall use pipes not less than 4 inches in diameter for lateral drains up to 50 feet in length. Use pipes of not less than 6 inches in diameter for lateral drains greater than 50 feet in length. Larger minimum pipe diameters may be specified by the Geotechnical Engineer or the Engineer's Representative during construction.

# 10. Unusual Conditions

10.1 If unusual conditions occur during grading, the Geotechnical Engineer shall be immediately notified for recommendations.