REQUEST FOR INFORMATION FOR COUNTY OF SAN MATEO

POTENTIAL BIDDERS FOR THE ALPINE ROAD TRAIL IMPROVEMENTS PROJECT

TOTAL PROJECT APPROXIMATELY 1.84 MILES IN LENGTH WITH APPURTENANT WORK THERETO IN SAN MATEO COUNTY

COUNTY PROJECT NO. P23P1 PROJECT FILE NO. E4905

THE COUNTY OF SAN MATEO DEPARTMENT OF PUBLIC WORKS HAS PROVIDED RESPONSES (R) TO THE QUESTIONS BELOW

- Q1. We currently use an exclusion fence with funnels (E-Fence) made by ERTEC. Is this the type of (Temporary Type ESA) fence intended for exclusion?
- R1. Yes. The Temporary Type ESA fence is intended for wildlife exclusion. County staff will review the ESA submittal to determine if it is acceptable after the project has been awarded.
- Q2. Request for log material suppliers for bid items Nos. 44 thru 46 or Section 72-2 in the Project Specifications.
- R2. Big Creek Lumber(BCL) in Davenport, CA has redwood forests that they harvest from. BCL or any other supplier may potentially provide the approved species (page 102 of Project Specifications) or equivalent to the County for review and approval.

Updated February 13, 2017:

Additional potential suppliers are listed below:

•	<u> </u>		
Company	Contact	Location	Contact info
Parmeter Logging and			
Excavation		Cazadero	707 632 5610
Bohan and Canelis			
General Engineering	Nick	Cazadero	707 632 5708; <u>nick@bcgeinc.com</u>
Felta Redwoods		Healdsburg	707 431 3812
Falk Forestry Services		Stewarts Point	707 367 0312; <u>falkforestry@gmail.com</u>
	Steve Butler	Boulder Creek	831 338 0249
County of Santa Cruz	Kristen Kittleson		831 454 3154; <u>ENV033@co.santa-cruz.ca.us</u>
Soquel Forest	Colin Noyes		831 475 8643; colin.noyes@fire.ca.gov

- Q3. On Sheet C-7.1 or Sheet 24 of 43, the Storm Drain Pipe Profile calls out 16LF of 18" CMP, but the bid item is for RCP. Is there a typo on the plans or bid schedule?
- R3. The storm drain pipe callout "18" CMP" on Sheet C-7.1 is a typo it should be labeled "18" RCP." Bid item No.34 on the bid schedule is shown correctly. See Addendum No. 2 for correction.

- Q4. Request to confirm quantity for volume of rock/soil mix placed on the logs under the Vegetated Soil Lifts.
- R4. Quantity for Light Class Rock import quantity for 471 tons is confirmed to be correct. The remaining 50% of the mix will be from onsite material and as approved by the Engineer. See Addendum No. 2 for clarification.

Updated as of February 13, 2017 at 4:45 P.M. F:\Users\design\ldd\E4905000\RFI\Alpine_Con_RFI.doc