

MCOUNTY OF SAN MATEO

STATE OF CALIFORNIA

**CONTRACT DOCUMENTS
AND
SPECIFICATIONS**

GAZOS CREEK ROAD REPAIR PROJECT

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**


**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO:155545 FIPS NO: 081-99081-00**

APPROVED: _____ May 7 _____, 2021



JAMES C. PORTER
(R.C.E. No. 48056)
Director of Public Works



Department of Public Works
San Mateo County
555 County Center, 5th Floor
Redwood City, California 94063

TABLE OF CONTENTS

NOTICE TO CONTRACTORS

Bid Opening Date
 Engineer's Estimate
 General Bidder's Information

SPECIAL PROVISIONS

<u>Section</u>	
1.	Definitions
2.	Bidding
2-1.	Plans and Specifications
2-1.015.	Federal Lobbying Restrictions
3.	Contract Award and Execution
4.	Description of Work
5.	Control of Work
5-1.	Differing Site Conditions
5-2.	Repair of Equipment
5-3.	Cooperation
5-4.	Permits and Licenses
5-5.	Project Appearance
5-6.	Preservation of Property
5-7.	Air Pollution Control
5-8.	Obstructions
5-9.	Sound Control
5-10.	Public Convenience
5-11.	Disposal of Material Outside the Highway Right Of Way
5-13.	Subcontracting
6.	Control of Materials
6-1.	Certificates of Compliance
6-2.	Materials Testing
7.	Legal Relations and Responsibility
7-0.10	Federal Forms, Posters and Data Required of Contractor During Construction
7-0.11	Required Listing of Proposed Subcontractors
7-0.12	Labor Nondiscrimination
7-0.13	Prevailing Wage
7-0.14	Contracting with Small and Minority Business, Women's Business Enterprises, and Labor Surplus Area Firms
7-0.15	Good faith Effort
7-0.16	Subcontracting
7-0.17	Prompt Progress Payment to Subcontractors
7-0.18	Prompt Payment of Funds Withheld to Subcontractors

TABLE OF CONTENTS (Continued)

SPECIAL PROVISIONS (Continued)

Section

7-1.	Equal Employment Opportunity Program for Minority Employment
7-2.	Prevailing Wages
7-2a.	Payroll Records
7-2b.	Contractor Employee Jury Service
7-3.	Highway Construction Equipment
7-4.	Public Safety
7-5.	Disposal of Material Outside the Highway Right of Way
8.	Progress of Work and Time of Completion
8-1.	Time of Completion
8-2.	Liquidated Damages
8-3.	Progress Schedule
9.	Measurement and Payment
9-1.	Force Account Work
9-2.	Payments to Contractor
9-3.	Payments Withheld from Contractor
9-4.	Stop Notices
9-5.	Construction Claims
11.	Mobilization
11-2.	Staging Area Restoration
12.	Maintaining Traffic
13.	Water Pollution Control
14.	Construction Waste Management
14-1.	Diversion Goals
14-2.	References and Resources
14-3.	Waste Management Plan and Daily Transport Report
14-4.	Waste Management Plan Implementation
15.	Existing Highway Facilities
37.	Microsurfacing
39.	Asphalt Concrete
39-1.	Compaction Testing
39-3.	Pavement Repair (Type A, 3/4" Max-Med Grading)
39-4.	Asphaltic Emulsion (Tack Coat)

Note: Gaps in Section numbering, above, indicate that the Section is either blank or does not apply.

FEDERAL REQUIREMENTS for FEDERAL-AID CONSTRUCTION PROJECTS

FR-1	Federal Forms, Posters and Data Required of Contractor During Construction
FR-2 to FR-10	Part 200- Uniform Administration Requirements, Cost Principals, and Audit Requirements for Federal Awards – Section 200.317 through 200-326 and Appendix II
FR-10 to FR-12	Equal Opportunity Employment
FR-12 to FR-13	Contract Work Hours and Safety Standards
FR-13	Compliance with the Clean Air Act and the Federal Water Pollution Control Act
FR-14 to FR-15	Suspension and Debarment
FR-15	Byrd Anti-Lobbying Amendment
FR-15	Affirmative Procurement of EPA-designated Items in Service and Construction Contracts
FR-16	DHS Seal, Logo, Flags
FR-16	Compliance with Federal Law, Regulations and Executive Orders
FR-16	No Obligation by Federal Government
FR-16	Program Fraud and False or Fraudulent Statements or Related Acts
FR-16	Contracting with Small and Minority Business, Women’s Business Enterprise, and Labor Surplus Area Firms
FR-17	Cost Analysis
FR-18	Federal Wage Rates (North County)
FR-19	Appendix E, Title VI Assurances in Contracts

APPENDICES

APPENDIX A

County of San Mateo Waste Management Plan Form
Waste Management Daily Transport Report

APPENDIX B

Sample “Payment Bond” Form
Sample “Performance Bond” Form

APPENDIX C

Daily Personnel and Equipment Log

APPENDIX D

Construction Claims: Public Contract Code Sections 9204 and 20104 et seq.

APPENDIX E

Vicinity and Location Maps and Typical Details

PROPOSAL

Contractor's Check-Off List

Name and Address of Bidder

Contractor Declaration Statement

Bid Schedules

Bidder's Bond

Signature of Bidder

Subcontractors

San Mateo County Equal Employment Opportunity Program

Equal Benefits Compliance Ordinance No. 04026

(Title 2, Chapter 2.84, San Mateo County Ordinance Code)

Equal Benefits Compliance Declaration Form

Contractor Employee Jury Service Ordinance No. 04269

(Title 2, Chapter 2.85, San Mateo County Ordinance Code)

Contractor Employee Jury Service Compliance Declaration Form

Non-Collusion Declaration Form

Certification Regarding Lobbying

Public Contract Code Section 10285.1 Statement

Public Contract Code Section 10162 Questionnaire

Public Contract Section 10232 Statement

Non-Collusion Affidavit (Federal Requirement)

Debarment and Suspension Certification (Title 49, Code of Federal Regulations, Part 29)

Non-Lobbying Certification for Federal-Aid Contracts

Disclosure of Lobbying Activities

Certification of Bidder's Qualification and Experience

AGREEMENT

Signature Sheet

**COUNTY OF SAN MATEO
STATE OF CALIFORNIA**

NOTICE TO CONTRACTORS

NOTICE IS HEREBY GIVEN, that

Sealed bids will be received **either by mail** to the office of the County Manager/Clerk of the Board of Supervisors, **or hand-delivered within one (1) hour prior to the bid opening to the main public entrance** of the Hall of Justice and Records, 400 County Center, Redwood City, California 94063, until the hour of

2:30 p.m., Wednesday, June 2, 2021

which **all bids (mailed in or hand-delivered)** will then be transmitted to the **main public entrance** of the Hall of Justice and Records at **400 County Center, Redwood City**, where the bids will be publicly opened and read aloud for the following project in accordance with the specifications therefore and to which special reference is made as follows:

GAZOS CREEK ROAD REPAIR PROJECT

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO:155545 FIPS NO: 081-99081-00**

Bids are required for the entire work described herein.

Bidders are further advised of the following:

1. **Contractor should be placed on a Plan Holders List for bidding. To be placed on the Plan Holders List, the Contractor shall either:**
 - a. **Complete and sign the Plan Holder's Affidavit by using the link below and you will receive a separate link for downloading an electronic copy of the Specifications:**
<https://publicworks.smcgov.org/GazosCreekRdPlanHoldersAffidavitForm>

- b. Complete and sign the Plan Holder’s Affidavit and return to the County by PDF via email to jrawley@smcgov.org, zazzari@smcgov.org, and pw_surveying@smcgov.org

The Contractor is advised that the table (Plan Holder’s Affidavit) should be received by the County no later than three (3) working days prior to bid opening date.

Plan Holder’s Affidavit	
Project Title	Gazos Creek Road Repair Project
Project No.	YY003
Project Engineer:	Joshua P. Rawley
Project Manager:	Zack Azzari
Bid Open Date and Time:	2:30 p.m., Wednesday, June 2, 2021
Company Name:	_____
Mailing Address:	_____
Phone Number:	_____ Fax Number: _____
E-mail Address:	_____
(Name and Title of Authorized Representative of Bidder)	
(Signature of Authorized Representative of Bidder)	

- 2. The Plan Holders List will be posted to the County of San Mateo’s Public Works website two (2) working days prior to the bid open date.
- 3. Questions regarding the Contract Documents concerning items such as discrepancies, conflicts, omissions, doubts as to meanings, or regarding scope of bid items shall be referred to the Engineer. Inquiries must be received in writing via email, to jrawley@smcgov.org, and zazzari@smcgov.org, not less than five (5) working days prior to bid opening. Inquiries will be answered in writing via email response if written clarification is warranted, in the opinion of the Engineer, then inquiries and responses will be posted to the Project’s page on the County of San Mateo’s Public Works website. It will be the Contractor’s sole responsibility to ensure that they receive responses, *if any*. The County will not be

- responsible for oral clarifications.
4. It will be the Contractor's sole responsibility to ensure that they have received addendums, *if any*, which will be posted to the County of San Mateo's Public Works website on the same day issued. Said addendums will also be sent to all current plan holders and made available during purchase of Specifications.
 5. The Contractor's attention is directed to the importance of complying with the provisions of Section 7-0.10, "Federal Forms, Posters and Data Required of Contractor During Construction."

ENGINEER'S ESTIMATE**GAZOS CREEK ROAD REPAIR PROJECT**

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO:155545 FIPS NO: 081-99081-00**

Item No.	Section No.	Estimated Quantity	Unit of Measure	Item Description
1	11	1	LS	Mobilization
2	11-2	1	LS	Staging Area Restoration
3	12	1	LS	Maintaining Traffic
4	13	1	LS	Water Pollution Control
5	14	1	LS	Construction Waste Management
6	37	48,000	SY	Microsurfacing
7	39-3	200	SY	Pavement Repair (Type A, 3/4" Max-Med Grading)

(Note: Gaps in section numbering, above, indicate the Section is blank or does not apply.)

Engineer's Estimate of Costs: \$ 550,000.00

(Note: Gaps in section numbering, above, indicate the Section is blank or does not apply.)

The foregoing quantities are approximate only, being given as a basis for the comparison of bids, and the County of San Mateo does not, expressly or by implication, agree that the actual amount of work will correspond herewith, but reserves the right to increase or decrease the amount of any class or portion of the work, or to omit any portion of the work, as may be deemed necessary or expedient by the Engineer.

Payment to the Contractor for materials furnished and work completed shall be made by the County in accordance with Section 9 of the "Special Provisions" portion of these Contract Documents. Pursuant to Section 22300 of the Public Contract Code, Contractor may, upon his request and at Contractor's expense, substitute equivalent securities for any moneys retained from such payment for the fulfillment of the Contract.

Pursuant to Section 1773 of the California Labor Code, prevailing wage rates in the County have been established by the California Department of Industrial Relations, and copies are available in the office of the Director of Public Works. Said prevailing wage rates shall be made available to any interested party on request, and the successful Bidder shall post a copy of the wage rates at the job site. The Contractor's attention is directed to Section 7-1.02K(2), "Wages," of the Standard Specifications and the Federal Requirements section of these Special Provisions. More specifically, reference is made to section FR-18, "Federal Wage Rates (North County)".

Additionally:

- a. **When applicable, both Contractor and Subcontractor(s) hereby agree to pay not less than prevailing rates of wages and be responsible for compliance with all the provisions of the California Labor Code, Article 2- Wages, Chapter 1, Part 7, Division 2, Section 1770 et seq and Section 1810 et seq. A copy of the prevailing wage scale established by the Department of Industrial Relations is on file in the office of the Director of Public Works, and available at www.dir.ca.gov/DLSR or by phone at 415-703-4774. California Labor Code Section 1776(a) requires each contractor and subcontractor keep accurate payroll records of trades workers on all public works projects and to submit copies of certified payroll records upon request.**
- b. **Pursuant to State Senate Bill SB 854 (Stat. 2014, chapter 28), effective January 1, 2015:**

- i. No contractor or subcontractor may be listed on a bid proposal for a public works project (submitted on or after March 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5 [with limited exceptions from this requirement for bid purposes only under Labor Code section 1771.1(a)].**
- ii. No contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.**
- iii. This project is subject to compliance monitoring and enforcement by the Department of Industrial Relations.**

Attention is directed to the Federal minimum wage rate requirements in the Contract documents for this Project. If there is a difference between the minimum wage rates predetermined by the Secretary of Labor and the general prevailing wage rates determined by the Director of the California Department of Industrial Relations for similar classifications of labor, the Contractor and subcontractors shall pay not less than the higher wage rate. The Department will not accept lower State wage rates not specifically included in the Federal minimum wage determinations. This includes "helper" (or other classifications based on hours of experience) or any other classification not appearing in the Federal wage determinations. Where Federal wage determinations do not contain the State wage rate determination otherwise available for use by the Contractor and subcontractors, the Contractor and subcontractors shall pay not less than the Federal minimum wage rate, which most closely approximates the duties of the employees in question.

Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the hotline provided below to report these activities. Reference is made to Section 2-1.50, "Bid Rigging," of the Standard Specifications, which states: "The U.S. Department of Transportation (DOT) provides a toll-free hotline service to report bid rigging activities. Use the hotline to report bid rigging, bidder collusion, or other fraudulent activities. The hotline number is (800)-424-9071. The service is available 24 hours 7 days a week and is confidential and anonymous. The hotline is part of the DOT's effort to identify and investigate highway construction

contract fraud and abuse and is operated under the direction of the DOT Inspector General.”

Wage rates for overtime shall be paid at not less than one and one-half (1-1/2) times the above rates. Wage rates for Sundays and holidays shall be paid at not less than two (2) times the above rates.

The holidays upon which such rates shall be paid shall be all holidays recognized in the collective bargaining agreement applicable to the particular craft, classification, or type of worker employed on the Project.

It is the policy of the County that Contractors on public projects employ their workers and craftsmen from the local labor market whenever possible. "Local Labor Market" is defined as the labor market within the geographical confines of the County of San Mateo, State of California. Consistent with this policy, the Contractor is requested to employ craftsmen and other workers from the local labor market whenever possible to do so.

Each bidder shall submit with the bid, Certificates of Compliance and Intent on a form provided in the "Proposal" section of these Contract Documents, a certificate that bidder is in compliance with the provisions of the Equal Employment Opportunity Requirement of Executive Order 11246, Title VII of the Civil Rights Act of 1964, the California Fair Employment and Housing Act and any other federal, State and local laws and regulations relating to equal employment opportunity. With the execution of said certificates, bidder also agrees that bidder will maintain or develop and implement, during the course of the work concerned, a program of hiring and employment, conducted without regard to race, religion, color, national origin, ancestry, sexual orientation, or sex of the applicants. With this certification, bidder shall submit any and all information that may be required by the County in connection with the particular project.

Each bidder is hereby notified of Section 9204 and Section 20104 et seq. of the Public Contract Code as those Sections (attached hereto as Appendix D) relate to resolution of construction claims, and to Section 3186 of the Civil Code, as amended January 1, 1999 with regard to stop notices and public entity's rights to retain monies in order to provide for that entity's reasonable cost of litigation. The bidder is further notified that all provisions of Section 9204 and Section 20104 et seq. of the Public Contract Code and Section 3186 of the Civil Code, as outlined above shall be

considered as incorporated into and become an integral part of these specifications.

Questions relating to equal employment should be directed to the San Mateo County Department of Public Works, Equal Employment Opportunity Program, 555 County Center, 5th Floor, Redwood City, CA 94063-1665, telephone (650) 363-4100.

Specifications and forms of Proposal and Contract may be seen and obtained at the office of the Director of Public Works, 555 County Center, Redwood City, California, 94063-1665. Plans and specifications may be obtained for a:

NON-REFUNDABLE FEE OF \$ 30.00 PER SET

Additional technical questions should be directed to the office of the Director of Public Works, 555 County Center, Redwood City, California, 94063-1665, telephone (650) 363-4100.

The Contractor shall possess either a Class A License or a combination of Class C licenses that are applicable for the majority of the work at the time this contract is awarded. No Contract will be awarded to a Bidder who is not licensed as required by laws of the State of California.


The County of San Mateo reserves the right to reject any or all bids and/or waive any informalities or irregularities in any bid received.

Bidders may not withdraw their bid for a period of **FORTY-FIVE (45) DAYS** after the date set from the opening thereof.

BY ORDER OF THE
BOARD OF SUPERVISORS
COUNTY OF SAN MATEO

DATE: May 7, 2021

**Michael Callagy, County Manager/
Clerk of the Board of Supervisors**



PUBLIC ENTRANCE
(SECURITY CHECK POINT)

SAN MATEO COUNTY GOVERNMENT CENTER

NOTE:

Receipt of Bids in the Office of the County Manager/Clerk of the Board of Supervisors, Hall of Justice.
Refer to project Notice to Contractors for Time, Date or alternate location.

F:\USERS\DESIGN\SPEC\BOILERPLATES\S55_BIDOPEN3.DWG

COUNTY OF SAN MATEO

STATE OF CALIFORNIA

**SPECIAL PROVISIONS
FOR**

GAZOS CREEK ROAD REPAIR PROJECT

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO:155545 FIPS NO: 081-99081-00**

DATE: May 7 , 2021

SECTION 1.**DEFINITIONS OF TERMS TO BE USED IN THE SPECIAL PROVISIONS,
NOTICE TO CONTRACTORS, PROPOSAL, AGREEMENT OR
OTHER CONTRACT DOCUMENTS**

Except as specifically stated herein, the definitions contained in the Standard Specifications of the State of California, Department of Transportation, as set forth per Section 2-1, "Plans and Specifications," of these Special Provisions and hereafter referred to as "Standard Specifications," shall be applicable with the understanding that where said definitions specifically refer to the State of California, a department or division of the State or an official, officer or employee of the State, said definition shall be interpreted to refer to the County of San Mateo, the Department of Public Works, or other appropriate department, division, official, officer or employee of the County of San Mateo.

Definition 7-1.02L, "Public Contract Code," of the Standard Specifications shall not be interpreted to include the provisions of Article 7.1 of Division 2, Part 2, Chapter 1 of the Public Contract Code.

END OF SECTION

SECTION 2. BIDDING

The Bidder's attention is directed to all the provisions of Section 2, "Bidding," of the Standard Specifications and these Special Provisions. The County will accept a Bidder's Bond in the form issued by an admitted surety insurer in lieu of the sample forms provided herein in Appendix B of these Special Provisions. The County will not be responsible for any oral interpretations to Bidders with respect to any of the work embraced herein.

The contractor, sub-recipient or subcontractor shall not discriminate on the basis of race, color, sex, or national origin in the performance of this contract. The contractor shall carry out applicable requirements of Title 49 CFR (Code of Federal Regulations) part 26, "Participation by Disadvantaged Business Enterprises in Department of Transportation Financial Assistance Programs," in the award and administration of US DOT assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy, as the recipient deems appropriate. Each subcontract signed by the bidder must include this assurance.

Failure of the bidder to fulfill the requirements of the Special Provisions for submittals required to be furnished after bid opening, including but not limited to escrowed bid documents, where applicable, may subject the bidder to a determination of the bidder's responsibility in the event it is the apparent low bidder on a future public works contracts.

All proposals must be made upon the blank form contained herein.

2-1. Plans and Specifications

Subject to the exceptions stated herein, the work embraced herein shall be done in accordance with the Standard Plans and Specifications as adopted by the County of San Mateo insofar as the same may apply, and in accordance with the following Special Provisions.

As set forth in **Resolution No. 077277** of the Board of Supervisors of the County of San Mateo, adopted **February 11, 2020**, which approved the use of the 2018 Standard Plans and Standard Specifications, of the State of California, Department of Transportation as the Standard Plans and Standard Specifications

of the County of San Mateo, State of California.

2-1.015. Federal Lobbying Restrictions

Title 31, Subtitle II, Chapter 13, Subchapter III, Section 1352, of the United States Code prohibits Federal funds from being expended by the recipient or any lower tier sub-recipient of a Federal-aid contract to pay for any person for influencing or attempting to influence a Federal agency or Congress in connection with the awarding of any Federal-aid contract, the making of any Federal grant or loan, or the entering into of any cooperative agreement.

If any funds other than Federal funds have been paid for the same purposes in connection with this Federal-aid contract, the recipient shall submit an executed certification and, if required, submit a completed disclosure form as part of the bid documents.

Certification for Federal-aid contracts regarding payment of funds to lobby Congress or a Federal agency is required. Included in the Proposal is Standard Form LLL, "Disclosure of Lobbying Activities," with instructions for completing. Signing the Proposal shall constitute both signature of Standard Form LLL and said Certification.

The above referenced certification and disclosure of lobbying activities shall be included in each subcontract and any lower-tier contracts exceeding \$100,000. All disclosure forms shall be forwarded from tier to tier until received by the Engineer.

The Contractor, subcontractors and any lower-tier contractors shall file a disclosure form at the end of each calendar quarter in which there occurs any event that requires disclosure or that materially affects the accuracy of the information contained in any disclosure form previously filed by the Contractor, subcontractors and any lower-tier contractors. An event that materially affects the accuracy of the information reported includes:

- (1) A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or
- (2) A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or

- (3) A change in the officer(s), employees(s), or Member(s) contacted to influence or attempt to influence a covered Federal Action.

END OF SECTION

SECTION 3. CONTRACT AWARD AND EXECUTION

The bidder's attention is directed to the provisions in Section 3, "Contract Award and Execution," of the Standard Specifications and these Special Provisions for the requirements and conditions concerning award and execution of contracts.

However, the following supersedes the second paragraph in Section 3-1.04, "Contract Award," of the Standard Specifications:

"The award of contract, if awarded, will be made to the lowest responsible bidder within **SIXTY (60) DAYS** after the opening of the proposals. If the lowest responsible bidder refuses or fails to execute the contract, the County may award the contract to the second lowest responsible bidder. If the second lowest responsible bidder refuses or fails to execute the contract, the County may award the contract to the third responsible bidder. The period of time after that specified above within which the award of the contract may be made shall be subject to extension for such further period as may be agreed upon, in writing, between the County and the bidder concerned."

Bidders who wish to lodge a protest for consideration as to the bidding process or the award of a contract to the lowest responsible bidder must do so as follows:

- (1) Protests based upon alleged improprieties in a solicitation, which are apparent prior to bid opening, shall be filed **two (2) business days** prior to bid opening.
- (2) Protests other than those covered by paragraph 1, above, shall be filed no later than **ten (10) calendar days** after the bid opening.
- (3) All protests shall be delivered to:

Director of Public Works
County of San Mateo
555 County Center, 5th Floor
Redwood City, CA 94063

Untimely protests, which do not meet the deadline requirements specified above, will not be accepted or considered.

Bid protests must be submitted in writing to the addressee and address listed above. Bid protests must at a minimum include the following:

- Project Name
- Project File Number
- A complete statement describing the basis for the bid protest, which includes

- a detailed statement of all legal and factual grounds for the protest
- Documentation supporting the protestor's grounds for the protest
- The type of relief requested and the legal basis for such relief

If a valid protest is filed timely, the Department will investigate the bid protest. The protested bidder shall have **three (3) business days** to respond to the Department and to provide any information requested by the Department. The Department shall respond to the protesting party, stating its findings. The Department Director shall make a recommendation to the San Mateo County Board of Supervisors regarding the bid protest.

Bid protests are to be delivered to the following address: 555 County Center, 5th Floor Redwood City, CA 94063.

The award of the contract, if it is awarded, will be to the lowest responsible bidder whose proposal complies with all the requirements prescribed.

The contract shall be executed by the successful bidder and shall be returned, together with the contract bonds, to the County so that it is received within ten (10) days, not including Saturdays, Sundays and legal holidays, after the bidder has received the contract for execution. Failure to do so shall be just cause for forfeiture of the proposal guaranty. The executed contract documents shall be delivered to the following address: 555 County Center, 5th Floor Redwood City, CA 94063.

Paragraph 1 of Section 3-1.02, "Contract Bonds," of the Standard Specifications is amended to read:

"The Contractor shall provide, at the time of the execution of the Agreement or Contract for work, at his own expense, a surety bond in an amount equal to at least one hundred percent (100%) of the contract price as security for the faithful performance of said agreement. Contractor shall also provide, at the time of the execution of the agreement or contract for work, and at his own expense, a separate surety bond in the amount equal to at least one hundred percent (100%) of the contract price as security for the payment of all persons performing and furnishing materials in connection with said agreement. Sureties on each of said bonds shall be satisfactory to County Counsel."

"Reference is made to **Appendix B** of these Special Provisions for a sample of both a "Payment Bond" and "Performance Bond" that have been approved as to form by County Counsel."

A successful bidder certified as a Minority and Women's Business Enterprises (DBE) should describe the work it has committed to performing with its own forces as well as any other work that it has committed to be performed by DBE subcontractors,

suppliers and trucking companies.

The Contractor shall provide written confirmation from each DBE that the DBE is participating in the contract. A copy of a DBE's quote will serve as written confirmation that the DBE is participating in the contract. If a DBE is participating as a joint venture partner, the successful bidder is encouraged to submit a copy of the joint venture agreement.

END OF SECTION

SECTION 4.
DESCRIPTION OF WORK

The work to be done shall include but not be limited to the installation of pavement repairs and microsurfacing on Gazos Creek Road located south of the Pescadero Area. The road spans approximately 3.3 miles easterly from the intersection of Cloverdale Road. All road work will take place within the footprint of existing road limits.

END OF SECTION

SECTION 5. CONTROL OF WORK

Attention is directed to the provisions of Section 5, "Control of Work," of the Standard Specifications, except as herein provided, and to Section 2-1, "Plans and Specifications," of these Special Provisions.

5-1. Differing Site Conditions

This section shall be used in lieu of Section 4-1.06, "Differing Site Conditions," of the Standard Specifications. Section 4-1.06 of the Standard Specifications shall not apply.

Contractor's Notification

Contractor shall promptly notify the Engineer if either of the following conditions are found:

1. Physical conditions differing materially from either of the following:
 - Contract documents
 - Job site examination
2. Physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the work provided for in the contract.

Contractor shall include details explaining the information relied on and the material differences discovered.

If Contractor fails to notify the Engineer promptly, the differing site condition claim is waived, for the period between discovery of the differing site condition and notification to the Engineer.

If Contractor disturbs the site after discovery and before the Engineer's investigation, Contractor waives the differing site condition claim.

Engineer's Investigation and Decision

Upon Contractor's notification, Engineer shall investigate job site conditions and:

1. Notify Contractor whether to resume affected work
2. Decide whether the condition differs materially and is cause for an adjustment of time, payment, or both

Contractor may protest the Engineer's decision.

5-2. Repair of Equipment

The work of installing, assembling, repairing or reconditioning, or other work of any nature on machinery, equipment or tools used in or upon the work shall be considered a part of the work to be performed under the contract and any laborers, workers or mechanics working on the machinery, equipment or tools, unless employed by bona fide commercial repair shops, garages, blacksmith shops or machine shops, which have been established and operating on a commercial basis for a period of at least 2 months prior to the award of the contract, shall be subject to all the requirements relating to labor set forth in these specifications and in the special provisions.

5-3. Cooperation

Attention is directed to Sections 5-1.20, "Coordination with Other Entities," and 5-1.36, "Property and Facility Preservation," of the Standard Specifications, and to these Special Provisions. The utility companies may be rearranging their facilities within the project area and it is expected that they will cooperate with the Contractor to the end that the work may be handled in an efficient manner.

The Contractor shall contact USA North811 (USA) service alert a minimum of forty-eight (48) hours in advance of any excavation or trenching work. USA may be contacted either on-line at usanorth811.org or by phone by dialing (800) 642-2444 or 811.

5-4. Permits and Licenses

Attention is directed to Section 5-1.20B, "Permits, Licenses, Agreements, and Certifications," of the Standard Specifications and these Special Provisions.

The Contractor shall have at least two employees trained in confined space entry regulations CAL/OSHA Confined Space Regulations, Title 8 CCR GISO 5156, 5157, and 5158 at the site whenever there are open trenches or underground work going on. It is understood that all fall protection, retrieval and atmospheric monitoring equipment shall be furnished and maintained by the Contractor at the Contractor's expense. This shall include but not be limited to cost associated with compliance with Confined Space Entry Regulations at the expense of the Contractor.

5-5. Project Appearance

The Contractor shall maintain a neat appearance to the work. Full

compensation for conforming to the provisions in this section, not otherwise provided for, shall be considered as included in the unit prices paid for the various Contract items of work involved, and no additional compensation will be allowed therefore.

5-6. Preservation of Property

The Contractor's attention is directed to Section 5-1.36, "Property and Facility Preservation," of the Standard Specifications.

5-7. Air Pollution Control

Air pollution control shall conform to the provisions of Section 14-9.02, "Air Pollution Control," of the Standard Specifications.

5-8. Obstructions

Attention is directed to the provisions in Sections 5-1.36D, "Nonhighway Facilities," 15, "Existing Facilities," and 51-1.03E(9), "Utility Facilities," of the Standard Specifications.

5-9. Sound Control

Sound control shall conform to the provisions in Section 14-8.02, "Noise Control," of the Standard Specifications.

5-10. Public Convenience

Public Convenience shall conform to the provisions in Section 7-1.03, "Public Convenience," of the Standard Specifications and to these Special Provisions.

5-11. Disposal of Material Outside the Highway Right of Way

Disposal of Material Outside the Highway Right Of Way shall conform to the provisions of Sections 5-1.20B(4), "Contractor-Property Owner Agreement," and 14-10, "Solid Waste Disposal and Recycling," of the Standard Specifications, and Section 10, "Construction Waste Management," of these Special Provisions. The Contractor's attention is further directed to Appendix "A", "Construction Waste Management Plan," of these Special Provisions.

5-12. Blank

5-13. Subcontracting

Attention is directed to the provisions in Section 7-0.16, "Subcontracting," of these Special Provisions and Section 5-1.13, "Subcontracting," of the Standard Specifications.

END OF SECTION

SECTION 6.

CONTROL OF MATERIALS

Attention is directed to Section 6, "Control of Materials," of the Standard Specifications and these Special Provisions.

The Contractor shall furnish all materials required to complete the work under this Contract.

The County uses a Quality Assurance Plan (QAP) to provide assurance that the materials incorporated into construction projects are in conformance with the contract specifications. Contractor may examine records and reports of tests performed by the County if they are available on the job site. Contractor shall schedule work to allow time for the testing requirements in the QAP.

6-1. Certificates of Compliance

Certificates of Compliance, conforming to the provisions in Section 6-2.03C, "Certificates of Compliance," of the Standard Specifications shall be furnished for all manufactured products, unless otherwise waived by the Engineer.

6-2. Materials Testing

The Contractor shall, at no additional expense to the County, furnish certificates of inspection or laboratory reports from a reputable testing or inspection agency as to compliance with the specifications and composition, durability and performance in accordance with the Special Provisions or Standard Specifications. Test reports on any material must be submitted and approved by the Engineer before incorporating that material in the work.

Any costs to the County for testing materials which fail testing requirements may be deducted from any progress payment due to the Contractor when, in the opinion of the Engineer, such failure results from the Contractor's lack of diligence in pursuing quality control efforts related to but not limited to material selection and installation. In the event that a test fails, any testing after the first shall be at the Contractor's expense.

END OF SECTION

SECTION 7.

LEGAL RELATIONS AND RESPONSIBILITY

Attention is directed to the provisions of Section 7, "Legal Relations and Responsibility to the Public," of the Standard Specifications, these Special Provisions, and to the provisions of paragraph VIII, "Insurance," of the Agreement (AG) portion of the Contract Documents for insurance requirements and the provisions related to Novel Coronavirus Disease 2019 (COVID-19) in the Proposal (PR) and Sections XVI, "COVID-19" and XXII, "Electronic Signature," of the Agreement (AG) portions of the Contract Documents.

7-0.10. Federal Forms, Posters and Data Required of Contractor During Construction

The Contractor is advised that there are Federal posters required to be posted at the job site and forms required to be submitted during construction. Reference is made to the "Federal Requirements for Federal-Aid Construction Projects" section of these Special Provisions for a listing of the most-commonly required forms.

The Contractor is further advised that, should Contractor fail to post the required posters at the job site or provide the Federal forms in a timely manner without due cause, as determined by the Engineer, the Engineer shall have the option, at his discretion, to either withhold the progress payment or issue a stop work order until such forms have been submitted to the Engineer.

7-0.11. Required Listing of Proposed Subcontractors

All proposed subcontractors shall be listed by the Contractor in conformance with Section 2-1.10, "Subcontractor List," of the Standard Specifications.

Each proposal shall have listed therein the name and address of each subcontractor to whom the bidder proposed to subcontract portions of the work in an amount in excess of one-half of one percent (0.5%) of his total bid or \$10,000, whichever is greater, in accordance with the Subletting and Subcontracting Fair Practices Act, commencing with Section 4100 of the Public Contract Code. The bidder's attention is directed to other provisions of said Act related to the imposition of penalties for a failure to observe its provisions by using unauthorized subcontractors or by making unauthorized substitutions.

A sheet for listing the subcontractors, as required herein, is included in the Proposal.

7-0.12.Labor Nondiscrimination

The Contractor is advised that the State Standard Specifications shall apply if and where any conflicts between," this Section 7-0.12, "Labor Nondiscrimination," and Section 7-1, "Equal Employment Program for Minority Employment," of these Special Provisions and the State Standard Specifications exist.

Attention is directed to the following Notice that is required by Chapter 5 of Division 4 of Title 2, California Code of Regulations:

**NOTICE OF REQUIREMENT FOR
NONDISCRIMINATION PROGRAM
(GOV. CODE, SECTION 12990)**

Your attention is called to the "Nondiscrimination Clause", set forth in Section 7-1.01A(4), "Labor Nondiscrimination," of the Standard Specifications, which is applicable to all non-exempt State contracts and subcontracts, and to the "Standard California Nondiscrimination Construction Contract Specifications" set forth therein. The Specifications are applicable to all nonexempt State construction contracts and subcontracts of \$5,000 or more.

7-0.13.Prevailing Wage

Attention is directed to Section 7-1.02K(2), "Wages," of the Standard Specifications.

In accordance with the provisions of Section 1770 of the Labor Code, the Board of Supervisors of the County of San Mateo has ascertained the prevailing rate of wages applicable to the work to be done, which prevailing wage rates have been established as indicated in the Notice to Contractors and are incorporated herein by reference.

7-0.14.Contracting with small and Minority Business, Women's Business Enterprises, and Labor Surplus Area Firms

The Contractor must take all necessary affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible.

Affirmative steps must include:

- (1) Placing qualified small and minority businesses and women's business enterprises on solicitation lists;
- (2) Assuring that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources;
- (3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's business enterprises;
- (4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises;
- (5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce.

7-0.15. Good Faith Effort

MBE / WBE REQUIREMENTS

The County intends to seek reimbursement of its costs incurred in connection with this project from FEMA. Accordingly, the CONTRACTOR shall make every effort to procure DBE through the "Good Faith Effort" process as required in 2 CFR 200.321. Failure to perform the "Good Faith Effort" process and submit the forms listed below with the bid shall be cause for a bid to be rejected as nonresponsive and/or be considered as a material breach of the contract.

PRIME CONTRACTOR RESPONSIBILITIES All recipients of this grant funding, as well as their prime contractors and subcontractors, must take all affirmative steps to assure that minority firms, women's business enterprises, and labor surplus area firms are used when possible make every effort to solicit bids from eligible DBEs. This information must be documented and reported.

"GOOD FAITH" EFFORT PROCESS Any public or private entity receiving federal funds must demonstrate that efforts were made to attract MBE/WBEs. The process to attract MBE/WBEs is referred to as the "Good Faith" effort. This effort requires the recipient, prime contractor and any subcontractors to take the steps listed below to assure that MBE/WBEs are used whenever possible as sources

of supplies, construction, equipment, or services. If a CONTRACTOR fails to take the steps outlined below shall cause the bid to be rejected as non-responsive and/or be deemed a material breach of the contract.

- A. Place qualified small and minority businesses and women's business enterprises on solicitation lists;
- B. Assure that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources;
- C. Divide total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority business, and women's business enterprises;
- D. Establish delivery schedules, where the requirement permits, which encourage participation by small and minority business, and women's business enterprises; and
- E. Use the services and assistance of the Small Business Administration, and the Minority Business Development Agency of the Department of Commerce.
- F. If subcontracts are to be let, Contractor shall take the affirmative steps listed in 2 CFR 200.321.

7-0.16. Subcontracting

No subcontract releases the Contractor from the contract or relieves the Contractor of their responsibility for a subcontractor's work.

If the Contractor violates Pub Cont Code § 4100 et seq., the County of San Mateo may exercise the remedies provided under Pub Cont Code § 4110. The County of San Mateo may refer the violation to the Contractors State License Board as provided under Pub Cont Code § 4111.

The provisions in the third paragraph of Section 5-1.13, "Subcontracting," of the Standard Specifications, that the Contractor shall perform with the Contractor's own organization contract work amounting to not less than 50 percent of the original contract price, is not changed by the Federal Aid requirement specified under "Required Contract Provisions Federal-Aid Construction Contracts" that the Contractor perform not less than 30 percent of the original contract work with the Contractor's own organization.

Each subcontract must comply with the contract.

Each subcontractor must have an active and valid State contractor's license with a classification appropriate for the work to be performed (Bus & Prof Code, § 7000 et seq.).

Submit copies of subcontracts upon request by the Engineer.

Before subcontracted work starts, submit a Subcontracting Request form.

Attention is directed to the provisions in Section 8-1.01, "Subcontracting," and these Special Provisions. Pursuant to the provisions in Section 1777.1 of the Labor Code, the Labor Commissioner publishes and distributes a list of contractors ineligible to perform work as a subcontractor on a public works project. The contractor shall not use a debarred contractor. This list of debarred contractors is available from the Department of Industrial Relations web site at: <http://www.dir.ca.gov/DLSE/Debar.html>

Upon request by the Engineer, immediately remove and not again use a subcontractor who fails to prosecute the work satisfactorily.

7-0.17. Prompt Progress Payment to Subcontractors

A prime contractor or subcontractor shall pay any subcontractor not later than 7 days of receipt of each progress payment in accordance with the provision in Section 7108.5 of the California Business and Professions Code concerning prompt payment to subcontractors. The 7 days is applicable unless a longer period is agreed to in writing. Any delay or postponement of payment over 30 days may take place only for good cause as determined by the County and with the County's prior written approval. Any violation of Section 7108.5 shall subject the violating contractor or subcontractor to the penalties, sanctions and other remedies of that section. This requirement shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the prime contractor or subcontractor in the event of a dispute involving late payment or nonpayment by the prime contractor, deficient subcontract performance, or noncompliance by a subcontractor.

The Contractor's attention is directed to Section 9-2, "Payments to Contractor," of these Special Provisions for the provisions applicable to payments to be made to the prime contractor.

7-0.18. Prompt Payment of Funds Withheld to Subcontractors

Section 9-1.16, "Progress Payments," of the Standard Specifications shall not apply.

The County shall hold retainage from the prime contractor and shall make prompt and regular incremental acceptances of portions, as determined by the County, of the contract work, and pay retainage to the prime contractor based on these acceptances. The prime contractor or subcontractor shall return all monies withheld in retention from a subcontractor within 30 days after receiving payment for work satisfactorily completed and accepted, including incremental acceptances of portions of the contract work by the County. Federal Law (49CFR26.29) requires that any delay or postponement of payment over the 30 days may take place only for good cause and with the County's prior written approval. Any violation of this provision shall subject the violating prime contractor or subcontractor to the penalties, sanctions and other remedies specified in Section 7108.5 of the California Business and Professions Code. These requirements shall not be construed to limit or impair any contractual, administrative, or judicial remedies otherwise available to the prime contractor or subcontractor in the event of a dispute involving late payment or non-payment by the prime contractor, deficient subcontract performance, or noncompliance by a subcontractor. This provision applies to both DBE and non-DBE prime contractors and subcontractors.

The Contractor's attention is directed to Section 9-3, "Payments Withheld from Contractor," of these Special Provisions for the provisions applicable to payments that may be withheld from the prime contractor.

7-1. Equal Employment Opportunity Program for Minority Employment

It is the intent of the Board of Supervisors of the County of San Mateo to prohibit and eliminate employment discrimination and to further the opportunities for minority persons to be gainfully employed in the performance of County construction contracts. Award of a contract to a low bidder will not be made until such bidder has complied with the provisions of Section 2.50.040 of Title 2, Chapter 2.50, as amended, of the San Mateo County Ordinance Code and with these guidelines.

7-1.1. Definitions

EQUAL EMPLOYMENT OPPORTUNITY PROGRAM: An Equal

Employment Opportunity Program (EEOP) is a set of specific and result oriented procedures to which a Contractor commits himself in order to achieve equal employment opportunity.

COMPLIANCE OFFICER: The Compliance Officer (CO) means the County official designated by the County Manager to represent him in the administration of these guidelines and in the enforcement of the provisions of Sections 2.50.040 and 2.50.050 of Title 2, Chapter 2.50.

7-1.2. Certifications of Compliance and Intent

Every bidder will submit with his bid, as required by Section 2.50.050 of Title 2, Chapter 2.50, a Certification of Compliance with the laws prohibiting discrimination and a Certification of Intent to implement an equal employment opportunity program on the form furnished in the Proposal section of these Specifications.

7-1.3. Equal Employment Opportunity Program

In addition to furnishing the Certifications of Compliance and Intent, each bidder will submit his equal employment opportunity program with his bid proposal. The EEOP shall contain the following information:

- A. Analysis of current work force
 - (1) Total number of employees;
 - (2) Numerical racial breakdown of employees by job classification;
 - (3) Information on apprentices.

These figures will provide the base by which the low bidder's EEOP will be evaluated. Factors to be considered both in the original statistics and in any plans for future employment will include the percentage of minority population in San Mateo County, the availability of minority construction workers and the present minority representation in the various construction trades.

- B. The affirmative actions the bidder has taken and will take to ensure equal employment opportunity. These shall include:
 - (1) Recruiting and hiring minority persons. If non-union personnel are employed, this would involve employment advertising through sources serving the minority population. These include local minority newspapers, referral agencies, high schools, vocational

schools and community groups. Specific information on these sources may be obtained from the Compliance Officer. Union employees will be recruited in accordance with applicable labor agreements. The bidder will seek to have included or will reaffirm clauses in all labor agreements prohibiting discrimination based on race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex. It is also suggested that bidders assist in admitting minority workers who are over the traditional apprenticeship entry age to the various craft training programs.

- (2) Providing adequate opportunity for the upgrading or further training of all employees to insure equal opportunity in advancement and promotion. This might include a counseling service, information and assistance with night classes, or special career-directed program information.
- (3) Appointing an Equal Employment Opportunity Coordinator, full time or as an additional duty. This person will have the responsibility of administering an active program, informing company personnel and union representatives of company policy, and advising all subcontractors of their obligation to this program.
- (4) Establishing or maintaining an apprenticeship/training program designed to ensure hiring of additional minority employees in the journeyman and skilled classes. Each bidder is urged to support or develop and implement an Apprenticeship Program for his trade.
- (5) Selecting minority subcontractors or subcontractors who are known for their ongoing programs of apprenticeship for minorities. This includes advising minority Contractor associations of opportunities for subcontracts. Joint ventures with minority sub-contractors are encouraged.

C. The EEOP should state any previous experience the bidder has had with similar plans and the results of that effort. Current affirmative action plans should be described in detail.

7-1.4. Equal Employment Opportunity Program Evaluation

A. The Compliance Officer (**CO**) will review the EEOP submitted by

the low bidder in order to determine whether the program submitted complies with the provisions of Section 2.50.040 of Title 2, Chapter 2.50, as amended, of the San Mateo County Ordinance Code, and these guidelines. If deficiencies are indicated, CO may request additional information from the bidder or suggest appropriate remedies. The CO will be available to answer questions relative to the guidelines and to advise those seeking assistance of other sources. CO will not be responsible for the service or lack of service rendered by the consultant recommended, nor will the CO develop an EEOP or serve as a recruiter for any bidder.

The low bidder may withdraw his EEOP for revision after consultation with the CO; however, the revised program must be resubmitted by a date not later than fifteen (15) calendar days after the opening of bids.

- B. All subcontractors listed in the low bidder's proposal shall be required to file completed Certificates of Compliance and Intent and their EEOP with the Bidder for submission to the County. The EEOP of each subcontractor will be evaluated by criteria established for the low bidder's EEOP.
- C. The CO, upon conclusion of the EEOP review, will report his findings and recommendation to the Director of Public Works. The CO will keep acceptable EEOP's on file for six (6) months. During this time period, if the bidder or subcontractors bid for other County contracts, they may refer to the EEOP on file and state any changes, but will not be required, unless specifically requested, to re-file their program.

7-1.5. Inclusion of EEOP and Certificates

Upon award of the Contract by the Board of Supervisors, the EEOP and certifications for the bidder and all subcontractors, which have been approved and accepted by the County, will become an integral part of the Contract and subject to the provisions thereof.

7-1.6. Compliance of Contractor

- A. The Contractor will post, in conspicuous places available to employees and applicants for employment, notices, provided by the County, stating that the Contractor is obliged to comply with the provisions

of these guidelines and the provisions of Section 2.050.040 of Title 2, Chapter 2.50, as amended, of the San Mateo County Ordinance Code. These notices will also be sent to all unions, employee organizations and other recruiting sources providing employees to the Contractor.

- B. All announcements of job openings will include the statement, "An Equal Opportunity Employer."
- C. The Contractor will make written progress reports on a form provided by the County to illustrate the effectiveness of his EEOP at intervals established by the County.
- D. The **CO** will monitor the Contractor's EEOP until completion of the Contract and will report non-compliance of the Contractor in adhering to his EEOP to the Director of Public Works.
- E. The Contractor will permit, during Contractor's normal business hours and at Contractor's place of business, access by the County to his records of employment, employment advertisements, application forms and other data and records pertaining to Contractor's employment practices, for the purpose of determining whether Contractor is complying with the non-discrimination and equal employment opportunity rules of the County.

7-1.7. Compliance of Subcontractor

All subcontractors listed by the bidder are subject to all the provisions of these guidelines and the provisions of Section 2.050.040 of Title 2, Chapter 2.50, as amended, of the San Mateo County Ordinance Code.

7-1.8. Penalties for Non-Compliance

The penalties for non-compliance are listed in Title 2, Chapter 2.50, Section 2.50.050, which states:

- a. "Every public works contract shall provide that a contractor who, within the time specified in the contract, does not submit an equal employment plan and make the certifications required in this chapter shall be in breach of the contract."
- b. "If, after an award is made, the contractor is found by the County or by a Federal or State agency empowered to make such findings to be in substantial or material violation of the Fair Employment Practices Act of the State of California, the Equal Employment Opportunity Requirement of Executive Order 11246, title VII of the Civil Rights Act

of 1964, or of the provisions of this chapter or of the Board-established guidelines implementing them, he may be found to be in material breach of contract, and the County shall have the power to cancel the contract in whole or in part, or alternatively, to deduct for each working day during which the contractor is found to have been in such non-compliance, two percent (2%) of the total amount payable to the contractor.”

7-1.9. Waiver of Compliance

In the event that any of the requirements of Sections 2.050.040 and 2.050.050 of Title 2, Chapter 2.50, as amended, of the San Mateo County Ordinance Code, are found to result in an undue hardship upon a low bidder, bidder may submit evidence of hardship and a petition for waiver of such requirements to the Director of Public Works for recommendation to the Board of Supervisors. Such a waiver may only be granted by the Board and, if approved, shall become an integral part of the contract.

7-1.10 Employee Benefits

All Contractors with contracts with the County of \$5,000 or more shall comply with the provisions of Title 2, Chapter 2.84, as amended, of the San Mateo County Ordinance Code with respect to the provisions on employee benefits. As set forth in the ordinance, such contractors are prohibited from discriminating in the provisions of employee benefits between an employee with a domestic partner and an employee with a spouse. A copy of the Ordinance and Compliance form is attached to the Proposal Section of these Specifications.

In the event it is determined, by the County, that any portion of the County Ordinance Code regarding employee benefits conflict with Federal or State regulations, the Federal or State regulations shall take precedence over the County Ordinance Code.

7-1.11 Non-Discrimination

No person shall be excluded from participation in, denied benefits of, or be subject to discrimination under this Agreement on the basis of their race, color, religion, national origin, age, sex, sexual orientation, pregnancy, childbirth or related conditions, medical condition, mental or physical disability or veteran’s status. Contractor shall ensure full compliance with Federal, State and local laws, directives and executive orders regarding non-discrimination for all employees

and Subcontractors under this Agreement.

Violation of the non-discrimination provisions of this Agreement shall be considered a breach of this Agreement and subject the Contractor to penalties, to be determined by the County Manager, including but not limited to:

- i) termination of this Agreement;
- ii) disqualification of the Contractor from bidding on or being awarded a County contract for a period of up to 3 years;
- iii) liquidated damages of \$2,500 per violation;
- iv) imposition of other appropriate contractual and civil remedies and sanctions, as determined by the County Manager.

To effectuate the provisions of this paragraph, the County Manager shall have the authority to:

- i) examine Contractor's employment records with respect to compliance with this paragraph;
- ii) set off all or any portion of the amount described in this paragraph against amounts due to Contractor under the Contract or any other Contract between Contractor and County.

Contractor shall report to the County Manager the filing by any person in any court of any complaint of discrimination or the filing by any person of any and all charges with the Equal Employment Opportunity Commission, the Fair Employment and Housing Commission or any other entity charged with the investigation of allegations within thirty (30) days of such filing, provided that within such thirty (30) days such entity has not notified Contractor that such charges are dismissed or otherwise unfounded. Such notification shall include the name of the complainant, a copy of such complaint and a description of the circumstance. Contractor shall provide County with a copy of its response to the Complaint when filed.

In the event it is determined, by the County, that any portion of these requirements regarding non-discrimination conflict with Federal or State regulations, the Federal or State regulations shall take precedence over County requirements.

7-2. Prevailing Wages

The Contractor's attention is directed to Section 7-1.02K(2), "Wages," of

the Standard Specifications and the Federal Requirements section of these Special Provisions.

Contractor and Subcontractors hereby agree to pay not less than prevailing wage rates and be responsible for compliance with all the provisions of;

- a. Section 7-1.01A(2), “Prevailing Wage,” of the Standard Specifications and the Federal Requirements section of these Special Provisions. More specifically, reference is made to page FR-18, “Federal Wage Rates (North County)”;** or
- b. California Labor Code, Article 2-Wages, Chapter 1, Part 7, Division 2, Section 1770 et seq and Section 1810 et seq. A copy of the prevailing wage scale established by the Department of Industrial Relations is on file in the office of the Director of Public Works, and available at www.dir.ca.gov/DLSR or by phone at 415-703-4774. California Labor Code Section 1776(a) requires each contractor and subcontractor keep accurate payroll records of trades workers on all public works projects and to submit copies of certified payroll records upon request.**

The Contractor’s attention is further directed to the following requirements of State Senate Bill SB 854 (Stat. 2014, chapter 28), effective January 1, 2015:

- (1) No contractor or subcontractor may be listed on a bid proposal for a public works project (submitted on or after March 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5 [with limited exceptions from this requirement for bid purposes only under Labor Code section 1771.1(a)].**
- (2) No contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.**

(3) This project is subject to compliance monitoring and enforcement by the Department of Industrial Relations.

7-2a. Payroll Records

Reference is made to Section 7-1.02K(3), "Certified Payroll Records (Labor Code § 1776)," of the Standard Specifications. In particular, the Contractor's attention is directed 'to the last paragraph, which is amended to read:

"If by the 10th working day after the 25th of the month, the Contractor has not submitted satisfactory payrolls for all work performed during the monthly period ending on or before the 25th of that month, the Department may withhold an amount equal to ten percent (10%) of the estimated value of the work performed (exclusive of Mobilization) from that month's estimate, except that this withholding shall not exceed \$10,000 nor be less than \$1,000. Withholdings for failure to submit satisfactory payrolls shall be additional to all other withholdings or retentions provided for in the contract. The withholding for failure to submit payrolls for any monthly period will be released for payment on the monthly estimate for partial payments next following the date that all the satisfactory payrolls for which the withholding was made are submitted."

The Contractor is advised that Contractor shall submit either Contractor's Daily Dispatch Report at the start of each working day OR a Daily Personnel and Equipment Log (included as Appendix C of these Special Provisions) to the Engineer by the start of the first working day subsequent to the performance of the work, or Contractor may incur task-specific liquidated damages in the amount of \$500 per calendar day for every day hence until submittal is made.

The Contractor is further advised that, pursuant to State Senate Bill SB 854 (Stat. 2014, chapter 28), effective January 1, 2015, all contractors and subcontractors working on a contract for public work on a public works project (awarded on or after April 1, 2015) must furnish electronic certified payroll records to the Labor Commissioner.

7-2b. Contractor Employee Jury Service

All Contractors with contracts with the County of \$100,000 or more shall

comply with the provisions of Title 2, Chapter 2.85, as amended, of the San Mateo County Ordinance Code, with respect to provision of jury duty pay to employees and have and adhere to a written policy that provides that its employees shall receive from the Contractor, on an annual basis, no less than five (5) days of regular pay for actual jury service in San Mateo County. The policy may provide that employees deposit any fees received for such jury service with the Contractor or that the Contractor deduct from the employees' regular pay the fees received for jury service. A copy of the Ordinance and a Compliance Form is attached to the Proposal Section of these Specifications.

Award of a Contract to a low bidder will not be made until such bidder has certified compliance with the provisions of Title 2, Chapter 2.85, as amended, of the San Mateo County Ordinance Code.

7-3. Highway Construction Equipment

Attention is directed to Section 7-1.02O, "Vehicle Code," of the Standard Specifications and these Special Provisions.

Pursuant to the authority contained in Section 591 of the Vehicle Code, the County has determined that, within such areas as are within the limits of the project and are open to public traffic, the Contractor shall comply with all the requirements set forth in Divisions 11, 12, 13, 14 and 15 of the Vehicle Code. Attention is directed to the statement in Section 591 that this section shall not relieve him or any person from the duty of exercising due care. The Contractor shall take all necessary precautions for safe operation of his equipment and the protection of the public from injury and damage from such equipment.

7-4. Public Safety

Public Safety shall conform to the provisions in Section 7-1.04, "Public Safety," of the Standard Specifications and to these Special Provisions.

Full compensation for conforming to the requirements of this section shall be considered as included in the unit prices paid for the various Contract items of work, and no additional compensation will be allowed, therefore.

7-5. Disposal of Material Outside the Highway Right of Way

Disposal of Material Outside the Highway Right Of Way shall conform to Section 14, "Construction Waste Management," of these Special

Provisions. The Contractor's attention is further directed to Appendix "A", "Construction Waste Management Plan," of these Special Provisions.

END OF SECTION

SECTION 8.
PROGRESS OF WORK AND TIME OF COMPLETION

Attention is directed to the provisions of Section 8, "Prosecution and Progress," of the Standard Specifications, except as herein provided.

8-1. Time of Completion

The Contractor shall begin work within **TEN (10) CALENDAR DAYS** after receiving Notice to Proceed from the Department of Public Works, and shall diligently prosecute the same to completion before the expiration of

FIFTEEN (15) WORKING DAYS

from the date of said beginning, as described above.

The Contractor is advised that punch list items are required to be completed before the expiration of the working days stated above.

The Contractor may request, in writing, for an extension of working days, which request shall state the reason for said request and the number of additional working days. The Engineer will consider said request and respond, in writing, stating either the number of additional working days approved or the reason for denying the request.

8-2. Liquidated Damages

Attention is directed to Sections 8-1.04, "Start of Job Site Activities," 8-1.05, "Time," and 8-1.10, "Liquidated Damages," of the Standard Specifications. The Contractor shall pay to the County of San Mateo the sum of Five Hundred Dollars (\$500.00) per calendar day for every calendar day delay over and above the number of working days prescribed above for finishing the work.

The Contractor is advised that task-based liquidated damages may be enforced in conformance with the following bid item-specific Special Provisions:

(1) Section 7-2a, "Payroll Records"

8-3. Progress Schedule

The Contractor is advised that an initial/baseline project schedule and subsequent schedule updates is required for the work included under this

Contract, and such schedules shall be in accordance with these Special Provisions.

The provisions of Section 8-1.02, "Schedule," of the Standard Specifications are superseded by the following:

"The Contractor shall submit a baseline project schedule to the Engineer within **five (5) working days** after receipt of the Notice to Proceed from the Department of Public Works. This baseline schedule and any subsequent schedule updates shall show:

- (1) Completion of all work within the specified contract time;
- (2) The proposed order of work; and
- (3) Projected starting and completion times for major phases of the work, for the total project, including dates for ordering materials and for substantial completion of the project. Reference is made to Section 8-1, "Time of Completion," of these Special Provisions."

The Contractor is advised that:

- (1) **Contractor shall notify the Engineer a minimum of twenty-four (24) hours prior to cancellation of any scheduled work. Should the Contractor fail to provide such notice, the cost for any travel time and mileage incurred by the Engineer will be deducted from the total amount due to the Contractor.**
- (2) **When requested, Contractor shall submit subsequent schedule updates within five (5) calendar days after receipt of written request from the Engineer. Failure to provide such subsequent schedule updates may be sufficient enough cause for the Engineer to issue a "Stop Notice," and work may not be allowed to proceed until such subsequent schedule update has been submitted and approved.**

The schedule shall be developed by a critical path method. The baseline progress schedule shall have as many activities as necessary, and as approved by the Engineer, to be sufficient to assure adequate planning of the project, and to permit monitoring and evaluation of progress and the analysis of time impacts. The Contractor shall provide sufficient material, equipment, and labor to meet the completion times in this schedule.

The baseline project schedule submitted shall meet in all respects the time

and order of work requirement of the contract. If the Contractor fails to define any element of work, activity or logic, and the error is discovered by either party, it shall be corrected by the Contractor at the next scheduled monthly update or revision.

The Engineer shall have **five (5) working days** to review and accept, reject or return a submitted schedule for revision. The Contractor shall not commence project work until after receipt of written approval of the preliminary project schedule from the Engineer.

The Contractor shall submit a revised progress schedule within **five (5) working days** when requested by the Engineer, or when there is significant change in the Contractor's operations that will affect the work schedule.

During the period of the Contract, on or before the first calendar day of each month, the Contractor shall submit to the Engineer a complete, updated progress schedule. Said updated schedules shall provide a complete analysis of work previously completed and work yet to be performed, including a status update of each salient component that is delayed or not on schedule, the impact such delays will have on each of the remaining salient features of the work (with revised completion dates), and a revised completion date for all of the project work. Updated schedules shall incorporate all current schedule information, actual progress, approved adjustments of time and proposed changes in sequence and logic.

The Engineer may require the Contractor to also submit, on a weekly basis, a schedule of work for the following workweek. The Engineer will determine the dates for submittal of weekly schedules.

If the Contractor or the Engineer considers that an approved or anticipated change will impact the contract progress, a schedule analysis and revised schedule supporting the proposed adjustment of time shall be submitted to the Engineer for review and approval.

If the Engineer deems that the baseline progress schedule, any necessary progress schedules and/or required supplemental schedules do not provide the information required in the Section and/or is unacceptable in size, appearance, neatness and legibility, progress payments will be withheld by the Engineer until a schedule containing the required information and/or with improved appearance

has been submitted by the Contractor and approved in writing by the Engineer.

The Engineer's written approval of any schedule shall not transfer any of the Contractor's responsibilities to the Engineer. The Contractor alone shall remain responsible for adjusting forces, equipment, and work schedules to ensure completion of the work within the time(s) specified in the contract. Full compensation for conforming to all of the provisions of this Section, "Progress Schedule," shall be considered as included in the unit prices paid for the various Contract items of the work, and no additional compensation will be allowed, therefore.

END OF SECTION

SECTION 9.
MEASUREMENT AND PAYMENT

9-1. Force Account Work

Attention is directed to the provisions of Section 9-1.04, "Force Account," of the Standard Specifications and these Special Provisions.

The first sentence of bullet item 2 under Section 9-1.04B, "Labor," of the Standard Specifications is amended to read:

"Labor surcharge percentage in *Labor Surcharge and Equipment Rental Rates* and *General Prevailing Wage Rates* current during the work paid at force account for:"

With respect to extra work, the Bidder's attention is directed to the provisions of Section 4-1.05, "Changes and Extra Work," of the Standard Specifications. No extra work or change shall be made, unless pursuant to a written contract change order from the Engineer. No claim for an addition to the Contract sum shall be valid unless so ordered.

9-2. Payments to Contractor

Payments shall be made according to the provisions of Section 9, "Payment," of the Standard Specifications and these Special Provisions. Attention is directed to Section 9-1.16, "Progress Payments," regarding progress or partial payments, and to Section 9-1.17, "Payment After Contract Acceptance," regarding final estimates and payments.

Section 9-1.16E(2), "Progress Withholds," of the Standard Specifications is superseded by the following:

The County of San Mateo shall retain five percent (5%) of such estimated value of the work done, and five percent (5%) of the value of materials so estimated to have been furnished and delivered and unused or furnished and stored as aforesaid as part security for the fulfillment of the Contract by the Contractor. In no event shall the County of San Mateo withhold less than five percent (5%) of the total Contract price until final completion and acceptance of the project.

The Contractor may, upon request and at the Contractor's own expense, substitute security for any money withheld to ensure performance of the Contract in accordance with Government Code Section 4590.

The filing of a Notice of Completion for the work herein provided shall not

constitute an acceptance by the County of latent defects in said work.

The Contractor's attention is directed to Section 7-0.21, "Prompt Progress Payment to Subcontractors," of these Special Provisions for the provisions applicable to payments to be made by a prime contractor or subcontractor to any subcontractor.

9-3. Payments Withheld from Contractor

The County may withhold sufficient monies from any sum otherwise due the Contractor, pursuant to this Agreement, to protect the County against loss on account of:

- A. Repair or replacement of street pavement or base, and/or culverts or other structures, on or near the work, damaged by reason of the Contractor's operations due to hauling materials or moving heavy equipment.
- B. Defective work not corrected.
- C. Claims filed or reasonable evidence indicating probable filing of claims.
- D. Failure of the Contractor to make payments properly to the subcontractors for material or labor.
- E. Reasonable doubt that the Contract can be completed for the balance then unpaid.
- F. Damage to another Contractor.
- G. Failure of the Contractor to provide water pollution control.
- H. Failure of the Contractor to submit satisfactory as-built drawings.

Payment of the amounts withheld shall be made upon the determination by the County that the withholding of such amounts is no longer necessary.

The Contractor's attention is directed to Section 7-0.18, "Prompt Payment of Funds Withheld to Subcontractors," of these Special Provisions for the provisions applicable to the return, by a prime contractor or subcontractor, of all monies withheld in retention from any subcontractor.

9-4. Stop Notices

Section 9-1.16E(4), "Stop Notice Withholds," of the Standard Specifications is superseded by the following:

"The County of San Mateo, by and through the Department of Public Works or other appropriate County office or officers, may at its option and at any time retain any amounts due the Contractor, sums sufficient to cover claims filed pursuant to Section 3179 et seq. of the

Civil Code.”

9-5. Construction Claims

Each Bidder is hereby notified of Section 9204 and Section 20104 et seq. of the Public Contract Code as those Sections (attached hereto as Appendix D) relate to the resolution of construction claims and to Section 3186 of the Civil Code, as amended January 1, 1999 with regard to stop notices and public entity's rights to retain monies in order to provide for that entity's reasonable cost of litigation. The Bidder is further notified that all provisions of Section 9204 and Section 20104 et seq. of the Public Contract Code and Section 3186 of the Civil Code, as outlined above, shall be considered as incorporated into and become an integral part of these Specifications.

END OF SECTION

SECTION 11. MOBILIZATION

Mobilization shall conform to the provisions in Section 9-1.16D, "Mobilization," of the Standard Specifications and to these Special Provisions.

11-1. Property Owner Primary Notification

The Contractor shall furnish all affected property owners and/or residents written notification that describes the proposed work. The notices shall include relevant dates and describe anticipated impacts to property owners during the work, including, but not limited to, a description of landscaping and improvements that may be affected and/or removed and a statement that the owners/residents have a right to salvage all such existing landscaping, improvements and/or materials that the Contractor may remove to facilitate construction within the right of way. The content, format and method of delivery of such notices shall be approved by the Engineer prior to distribution. The Contractor is advised that these notices shall not be placed in mailboxes, as it is a violation of Federal postal regulations.

Affected property owners and residents shall be considered all those who:

1. Front on or are contiguous to the Project limits.
2. Have ingress/egress route only from within the Project limits.
3. Have executed a Right-of-Entry Agreement with the Real Property Division, County of San Mateo.

The Contractor shall provide approved notification to all affected owners/residents a minimum of **TEN (10) CALENDAR DAYS** prior to the commencement of any Project site work. Failure to distribute notices shall be sufficient cause for the Engineer to suspend the work until such notices are distributed.

For additional property owner notification requirements, the Contractor's attention is directed to Section 12, "Maintaining Traffic," of these Special Provisions.

The Contract lump sum price paid for this item, "Mobilization," shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the applicable work specified in Section 9-1.16D, "Mobilization," of the

Standard Specifications, these Special Provisions and as directed by the Engineer.

11-2. Staging Area Restoration

A. Submittals

Prior to site mobilization, Contractor shall prepare and submit a site plan sketch for County review and approval indicating the layout of the Contractor Staging Area, including but not limited to:

1. Vehicular access ways, haul routes and on-site parking
2. Temporary barriers and enclosures
3. Storm water pollution prevention measures (see Sec.13)
4. Temporary restrooms
5. Trash Bins with covered lids

B. Requirements

It is recommended that the primary staging area be designated within the vicinity of the intersection at Gazos Creek Road and Cloverdale Road.

1. Contractor shall only use site areas designated in the County approved submittal location sketch.
2. Contractor Staging Area for the Project shall be clearly indicated by use of signage, delineators or other means acceptable to clearly identify the area.
3. **All existing conditions shall be documented (pictures, field notes, etc.) by the Contractor and the County to ensure that any damage to the existing habitat and/or property incurred during construction, shall be restored to its original condition by the Contractor to the satisfaction of the County. Liquidated damages shall be assessed in the event that any areas are damaged and/or not restored to original condition.**
4. All existing habitats shall be protected throughout construction without exception. Any negative impacts to the existing habitat during construction shall be the sole responsibility of the Contractor.
5. Contractor shall keep access to staging area and thoroughfares clear at all times. Contractor shall provide traffic and parking control signage. Refer to Section 12 for additional details.
6. Cleanliness: Contractor shall keep Staging Area clear of trash and debris and in neat order. Contractor shall be responsible for cleanliness and organizing the

area at no additional cost.

The Contract lump sum price paid for this item, "Staging Area Restoration," shall include full compensation for submitting a complete Staging Area submittal plan, for providing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in protecting, maintaining, and restoring all impacted areas to original condition to the full satisfaction of the County. No additional compensation shall be allowed therefore for this bid item.

END OF SECTION

SECTION 12.

MAINTAINING TRAFFIC

Attention is directed to Section 12-1, "Temporary Traffic Control, General," of the Standard Specifications, Sections 5-10, "Public Convenience" and 7-4, "Public Safety" of these Special Provisions, the Standard Plans, the Project Plans and the directions of the Engineer. Section 12-1.04, "Payment," of the Standard Specifications shall not apply. In connection with said sections, it is understood that all lights, signs, barricades, flaggers or other necessary devices shall be furnished and maintained by the Contractor at the Contractor's expense.

Contractor is advised that general roadway excavation shall not commence until authorized by the Engineer.

Property Owner Secondary Notification

The Contractor shall furnish all affected property owners and/or residents secondary written notification that describes the proposed work, including relevant dates; the Contractor's attention is directed to Section 11, "Mobilization," for primary notification requirements. The content, format and method of delivery of such secondary notices shall be approved by the Engineer prior to distribution.

Affected property owners and residents shall be considered all those who:


1. Front on or are contiguous to the Project limits.
2. Have ingress/egress route only from within the Project limits.
3. Have executed a Right-of-Entry Agreement with the Real Property Division, County of San Mateo.

The Contractor shall provide approved notification to all affected owners/residents a minimum of **FORTY-EIGHT (48) HOURS** prior to the commencement of any Project specific site work to allow residents to move their vehicles away from the work area. Failure to distribute notices shall be sufficient cause for the Engineer to suspend the work until such notices are distributed.

The Contractor shall furnish an overall Traffic Control Plan for all phases of work. The Plan shall be in accordance with 2018 Standard Plan T-13 unless these requirements are modified as directed by the Engineer. The Contractor shall submit the Traffic Control Plan within **FIVE (5) WORKING DAYS** after the pre-construction conference. The Engineer shall establish the time and place for said pre-construction

conference. Delays upon the part of the Contractor in submitting a Plan, in the format as outlined in these Special Provisions and as directed by the Engineer, shall not constitute a valid reason for time extensions should the Contract time elapse before completion of said project. The Contractor is further advised that consideration for adequate review time, as determined by the Engineer, shall be included in the work schedule.

The Traffic Control Plan shall include orange advisory signs (aluminum or plywood, or as approved by the Engineer), **3' x 6' minimum**, stating expected delays, including dates, times and affected streets. Wording of advisory signs shall be as follows:



Advisory sign shall be installed at the intersection of Cloverdale Road so that it can be read clearly by incoming traffic from Highway-1. Sign shall be set in place a minimum of **SEVEN (7) CALENDAR DAYS** prior to commencement of construction site work, unless otherwise directed by the Engineer. No construction site work shall commence prior to the Engineer's written approval of the Traffic Control Plan and installation of required signage.

The Contractor is advised that Gazos Creek Road shall be open by 5:00 P.M. at the end of the workday. Contractor shall also provide advisory signage advising of dates, times and recommended detour routes for road closures. Furthermore, the Contractor's attention is directed to Section 8-3, "Progress Schedule," of these Special Provisions.

Hand-written signs will not be permitted.

Proposals by the Contractor to close portions of roadways within the Project limits to through traffic during and/or outside of working hours shall be submitted, as a part of the Traffic Control Plan, to the Engineer for review. Acceptance of such proposals shall be entirely at the discretion of the Engineer. Should the Engineer reject the Contractor's road closure proposals, the Contractor shall be required to adhere to the provisions herein relating to passage of public traffic through the work and maintenance of traffic lanes through the work.

The Contractor may, at his option, submit an alternate work hour proposal to the Engineer for review. Acceptance of such proposal shall be entirely at the discretion of the Engineer, and any additional costs associated with alternate work hours proposed by the Contractor shall be borne solely by the Contractor, and no additional compensation will be allowed therefore. Should the Engineer reject the Contractor's alternate work hour proposal, the Contractor shall be required to adhere to the work schedule outlined herein.

When ordered by the Engineer, the Contractor shall furnish additional flaggers for the purpose of expediting the passage of public traffic through the work under one-way controls. The Contractor may also, at his option, utilize a pilot car. Traffic may be stopped in both directions only as specifically authorized by the Engineer.

If any component in the traffic control system is damaged, displaced or ceases to operate or function as specified, from any cause, during the progress of the work, the Contractor shall immediately repair or replace said component to its original condition and reinstall the component to its original location.

The provisions in this Special Provision will not relieve the Contractor from responsibility to provide additional devices or take such measures as may be necessary to comply with the provisions in Section 7-1.04, "Public Safety," of the Standard Specifications.

During paving operations, the Contractor shall furnish and place sufficient barricades and detour signs at all cross streets to protect new pavement surfaces. The duration of placement of said barricades shall be as approved by the Engineer.

Whenever the Contractor's operations create a condition hazardous to traffic or to the public, the Contractor shall take the necessary precautions and provide additional traffic control measures to protect those who must pass through the work. If the

Contractor shall appear to be neglectful or negligent in providing warning or protective measures, the Engineer may direct attention to the existence of a hazard, and require that additional barricades, flashers, warning and detour signs or lights be installed by the Contractor, or additional flaggers provided. Any action or lack of action by the Engineer as provided herein shall not relieve the Contractor from responsibility for public safety.

The Contract lump sum price paid for this item, "Maintaining Traffic," shall include full compensation for furnishing a complete Traffic Control Plan, for providing all labor (including flagging costs and pilot car), materials (including all stationary and portable signs, lights, traffic cones, and lane delineators), tools, equipment and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, moving to new locations, replacing, and disposing of the components of the traffic control system as shown on the Plans, the approved Traffic Control Plan, and the Standard Plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer, and no additional compensation shall be allowed, therefore.

END OF SECTION

SECTION 13.
WATER POLLUTION CONTROL

The provisions of Section 13, “Water Pollution,” of the Standard Specifications are superseded by these Special Provisions and the San Mateo Countywide Water Pollution Prevention Program (SMCWPPP). Information regarding this program is available at www.flowstobay.org.

The Contractor is advised that failure to fully comply with the provisions of this Section, and all requirements listed in the California Regional Water Quality Control Board San Francisco Bay Region Municipal Regional Stormwater National Pollutant Discharge Elimination System (NPDES) Permit Order No. R2-2015-0049 (MRP), and where applicable, the State Water Resources Control Board NPDES General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities Order No. 2010-0014-DWQ (Construction General Permit), and any resource agency permits obtained for the project, where applicable, except where amended in writing and signed by the Director of Public Works or his duly authorized representative, shall constitute substantial non-compliance with the requirements of the Clean Water Act, the NPDES permit program, and the Contract.

The County shall provide periodic site monitoring to ensure that the work complies with the requirements specified herein and in any resource agency permits. The County will provide the Contractor with copies of the completed monitoring reports. Should any work be found to be non-compliant, a follow up site monitoring visit will be conducted to ensure the items have been corrected. If deficiencies noted during a monitoring visit are not corrected before the follow up monitoring visit, the costs associated with additional follow up visits to correct the noted deficiencies shall be deducted from the final payment for all of the Contract work.

Construction sites are common sources of water pollution. Materials and wastes that blow or wash into a storm drain, gutter, or street have a direct impact on local creeks and wetlands, San Francisco Bay and the Pacific Ocean. The Contractor shall be responsible for any environmental damage caused by his operations and those of his subcontractors or employees.

Water pollution shall be defined as including the introduction of any material, including sediment, trash, or other debris, equipment or vehicles into any watercourse, including creeks, ponds, ditches, storm drain facilities, and any surfaces immediately tributary to those areas, except as specifically authorized by any resource agency permits. Water pollution controls are materials and measures that prevent the introduction of any material to any watercourse. Water pollution control materials and measures may consist of temporary silt fencing; straw mulch/straw logs; spill cleanup materials; pavement sweepers; sand bags or continuous berms; etc.

Water pollution controls shall be applied, maintained and removed by the Contractor as specified herein and as directed by the Engineer. For construction activities occurring between June 15 and September 15, sufficient quantities of applicable water pollution control materials shall be available at the work site prior to commencing any work. For construction activities occurring between September 15 and June 15, all applicable water pollution control measures shall be installed, and all applicable water pollution control materials shall be available at the work site, prior to commencing any work.

A. Water Pollution Control Program

Before starting any work on the project, the Contractor shall submit, for acceptance by the Engineer, a written program including Storm Water Pollution Prevention Plans (SWPPPs) and applicable plan drawings and details to control water pollution effectively during construction of the project. The program shall show the schedule for any erosion control work included in the contract and for all water pollution control measures that the Contractor proposes to take in connection with construction of the project to minimize the effects of the operations upon water resources. The Contractor shall not perform any clearing and grubbing or earthwork on the project, other than that specifically authorized in writing by the Engineer, until the program has been approved by the Engineer.

If the measures being taken by the Contractor are inadequate to control water pollution effectively, the Engineer may direct the Contractor to revise the operations and the water pollution control program. The directions will be in writing and will specify the items of work for which the Contractor's water pollution control measures are inadequate. No further work shall be performed on those items until the water pollution control measures are adequate and, if

also required, a revised water pollution control program has been approved. Attention is directed to “Contractor Response” of this Section for additional provisions relating to correction of the Contractor’s water pollution control program, and payment.

The Engineer will notify the Contractor of the acceptance or rejection of any submitted or revised water pollution control program within 5 working days.

The County will not be liable to the Contractor for failure to accept all or any portion of an originally submitted or revised water pollution control program, nor for any delays to the work due to the Contractor’s failure to submit an acceptable water pollution control program or failure to adhere to the provisions of an accepted water pollution control program.

B. Contractor Response

The Contractor is advised that they may be required to respond to the work site after hours and/or on weekends or holidays to mitigate potential water pollution, soil erosion or sedimentation and/or to repair damaged water pollution controls. Failure to respond within four (4) hours of notification by the Department of Public Works shall constitute substantial non-compliance with these Special Provisions.

Should the County Road Maintenance Division be required to provide any after-hours, weekend or holiday repairs to the Contractor’s water pollution controls due to the Contractor’s failure to respond, all costs associated with providing that response, including overtime wages, equipment and material costs, shall be deducted from the Contractor’s final payment. The Contractor shall also be fully responsible for any fines, penalties or mitigations imposed by any regulatory agency caused by his failure to respond, regardless if the County Road Maintenance Division attempts any repairs or pollution prevention work in his absence.

C. Excavation and Grading

The Contractor shall not commence any excavation, backfilling, grading or stockpiling operations until water pollution control materials have been delivered to the work site. The Contractor shall certify, in writing, that the quantity of water pollution control materials at the site is sufficient to protect against water pollution caused by the work, and shall specify the type of material and intended use in

said written certification.

Excavation and grading activities shall be scheduled for dry weather periods. Excavation and grading activities shall not be allowed to commence or continue during periods of rainfall or runoff.

The Contractor may elect to perform excavation or grading activities immediately prior to periods of forecasted rain if he certifies in writing to the Engineer that the site will be completely secured against erosion and/or water pollution at the conclusion of the workday and prior to any rainfall. The work site shall be considered as completely secured against erosion and/or water pollution during or prior to forecast periods of rain if the turbidity of runoff from the site does not exceed the turbidity of runoff from adjacent, undisturbed sites by more than 50 NTUs (Nephelometric Turbidity Units). Should the turbidity of runoff from the work site exceed this limit, the Contractor shall be required to immediately place additional erosion and/or water pollution controls at his expense as directed by the Engineer, and shall be subject to any administrative fines or penalties associated with water quality or permit violations, and no additional compensation will be allowed therefore.

D. General Housekeeping

The Contractor shall control the amount of runoff entering upon disturbed construction and staging areas, particularly during excavation, to reduce the amount of water pollution controls required. Temporary diversion berms and/or sandbags may be employed to divert runoff from entering upon construction and staging areas as approved by the Engineer.

Paved surfaces shall be broom-swept as necessary to prevent water pollution. Water spray system of the sweeper units shall be used as appropriate to reduce dust generation. If pavement flushing is necessary, silt ponds or other techniques to trap sediment and other pollutants shall be required.

Dumpsters shall be covered, maintained, and checked frequently for leaks. It is recommended that dumpsters be lined with plastic to prevent leakage of liquids. At no time will the Contractor be permitted to wash dumpsters at the site.

The Contractor shall place trashcans and recycling receptacles around the site for use by his forces. Trashcans and recycling receptacles shall be kept covered and shall be emptied at appropriate intervals to reduce litter at the site.

All wastes shall be disposed of properly outside the highway right of way in accordance with Section 5-11, "Disposal of Material Outside the Highway Right of Way," and Section 14, "Construction Waste Management," of these Special Provisions.

The Contractor shall maintain portable toilets in good working order and wastes shall be disposed of properly. The Contractor shall check toilets frequently for leaks, and repair or replace any toilets found to be leaking. Portable toilets shall be protected against tipping by ground anchors, bollards, or any other suitable means as approved by the Engineer.

E. Stockpiles

All soil and/or rock stockpiles shall be protected against wind, rainfall and runoff at all times. Plastic sheeting may be used to cover soils, including aggregate base, and shall be securely anchored by sandbags or other suitable means. At no time will any stockpiled materials be allowed to erode into any watercourse or onto any roadway or other tributary surface.

F. Vehicle Maintenance

The Contractor shall designate a completely contained area of the construction site, well away from watercourses and tributary areas, for auto and equipment parking, refueling, and routine vehicle and equipment maintenance. The Contractor shall require the use of drip pans or drop cloths to catch drips and spills if any vehicle or equipment fluids (e.g. motor oil, radiator coolant, etc.) must be drained on site. Diesel oil shall not be used to lubricate or clean equipment or parts. All spent fluids shall be stored in separate containers, and recycled whenever possible, or disposed of as hazardous waste.

Spills or leaks shall be immediately contained and cleaned up by the Contractor, all at his expense, and shall be reported to the Engineer immediately after containment.

All vehicles and equipment shall be maintained in good repair. The Contractor shall inspect frequently for and immediately repair any leaks. The Contractor shall perform major maintenance, repair jobs, and vehicle and equipment washing off site.

G. Spill Prevention and Response

Fluid spills shall not be hosed down. The Contractor shall use dry cleanup

methods (absorbent materials, cat litter, and/or rags) whenever possible. If water must be used, the Contractor will be required to collect the water and spilled fluids and dispose of it as hazardous waste. Spilled fluids shall not be allowed to soak into the ground or enter into any watercourse.

Spilled dry materials shall be swept up immediately. The Contractor shall not wash down or bury any dry spills. Spills on dirt areas shall be removed by digging up and properly disposing of contaminated soil. The Contractor shall report significant spills to the Engineer immediately.

H. Tire Washing

Should the Contractor's equipment be tracking soil onto a public road, the Engineer shall require a tire-washing swale at the exit from the construction site and/or staging areas. The Engineer shall also require that soil be removed from the traveled way by whatever means necessary to prevent water pollution.

I. Roadwork and Paving

The Contractor shall avoid creating excess dust when breaking and/or removing asphalt or concrete. Broken asphalt and/or concrete pieces shall be completely removed from the site as soon as possible, or shall be stored in a separate, secure stockpile protected against from wind, rainfall and runoff. Material derived from roadway work shall not be allowed to enter any watercourse, or tributary area.

Slurry resulting from sawcutting operations shall be shoveled or vacuumed and completely removed from the site. The Contractor shall not be permitted to sweep or flush any sawcutting debris or slurry into any watercourse, or tributary area.

J. Concrete and Mortar

Except as approved by the Engineer for temporary concrete washouts for concrete mixers or trucks, the Contractor shall ensure that concrete and mortar are contained within the lines and grades shown on the Plans and not allowed to leave the construction site. Any excess concrete, mortar and/or mix water placed or spilled beyond the limits of concrete construction as shown on the Plans shall be immediately collected, removed and disposed of properly.

Location of temporary concrete washouts for concrete mixers or trucks

shall be as approved, in writing, by the Engineer. Should the Contractor allow washing out of concrete mixers or trucks prior to receiving said written approval, Contractor may be required to clean up the unapproved washout area to the satisfaction of the Engineer and/or relocate temporary concrete washouts, all at the Contractor's sole expense, and no additional compensation will be allowed therefore.

Dry sacks of cement shall be protected against wind, rainfall and runoff. Opened sacks of cement shall be secured and protected from spilling.

K. Training

Contractor shall ensure that all persons responsible for preparing, amending and implementing SWPPPs be appropriately trained in accordance with the requirements of the Construction General Permit and these Special Provisions. The Contractor shall provide documentation of all training for persons responsible for implementing these requirements upon request by the Engineer.

When required, the County will provide introductory training to the Contractor, his employees and subcontractors at the job site before work commences for any project with resource agency permits. The training will provide background information on sensitive species, permit requirements and site-specific water quality issues. When not required, the County is available to provide such training at the Contractor's request.

The Contract lump sum price paid for this item, "Water Pollution Control," shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work required by these Special Provisions for Water Pollution Control, including submittal of a written program and working drawings, in a form approved by the Engineer, as specified in these Special Provisions, the Standard Specifications and as directed by the Engineer, and no additional compensation will be allowed therefore.

END OF SECTION

SECTION 14. CONSTRUCTION WASTE MANAGEMENT

The County has established that this Project shall minimize the creation of construction and demolition waste on the job site. Factors that contribute to waste such as over packaging, improper storage, ordering error, poor planning, breakage, mishandling, and contamination, shall be minimized. For any waste that is generated, as many of the waste materials as economically feasible shall be reused, salvaged, or recycled. Waste disposal in landfills shall be minimized.

The contract lump sum price paid for this item, "Construction Waste Management," shall include full compensation for furnishing all labor, equipment and incidentals, including the provision of required documentation of proper materials disposal and the development of a Waste Management Plan, all as described herein, and no separate payment will be made therefore.

No partial payment will be made for this Contract item of work until all work required, as specified herein, is completed to the satisfaction of the County, and all necessary documentation provided.

14-1 Diversion Goals

One hundred percent (100%) of inert wastes, and at least fifty percent (50%) of the remaining construction and demolition debris shall be diverted from landfills.

Inert wastes, such as concrete, brick, rock, asphalt, and soil not intended for on-site use, shall be taken to a facility that will reuse or recycle them.

Other mixed construction & demolition (C&D) wastes shall be taken to a facility with a C&D sorting program, as listed in the Construction and Demolition Debris Recycling Guide referenced below, if additional recycling is needed in order to meet the requirements set forth in this Section. If debris box service is used, the debris boxes must be taken to a C&D sorting facility if materials are not separated on-site for recycling.

The Contractor has the option of separating on-site for recycling non-inert materials, such as cardboard, paper, wood, metals, green waste, new gypsum wallboard, tile, porcelain fixtures, and other easily recycled materials, and directing them to recycling facilities and taking the remaining mixed waste (but no

more than 50% by weight or yardage) to a facility for disposal. If waste is taken for disposal, documentation must be provided to show that 50% of C&D wastes (in addition to 100% of inert wastes) have been diverted.

14-2 References and Resources

A Construction and Demolition Guide (C&D Guide) is available online at <https://www.smcsustainability.org/waste-reduction/construction-demolition/>. For more information or resources, contact the County of San Mateo's Office of Sustainability by phone at (888) 442-2666 or by email at sustainability@smcgov.org. The Contractor's attention is directed to **Appendix A** for the County of San Mateo Waste Management Plan Form and the Waste Management Daily Transport Report.

14-3. Waste Management Plan and Daily Transport Report

The Contractor is required to complete a Waste Management Daily Transport Report, listing details of the material transported on that particular day, which is to be signed by both the Contractor's representative and the County inspector on the job site.

The Waste Management Plan shall be submitted to the Engineer, Department of Public Works, 555 County Center – 5th Floor, for approval within SEVEN (7) WORKING DAYS after the pre-construction conference.

The Waste Management Plan shall include a description of how the contractor will meet the requirements of this contract and shall include a list of disposal and recycling facilities where waste materials will be taken, a description of what will be taken to each facility (inert wastes, metals, wood, glass, plastics, mixed waste, etc.), a description of the means of transportation of recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and designated center, or whether mixed materials will be collected by a waste hauler and removed from the site), and an estimated amount (weight, yardage, etc.).

Approval will be granted if the plan shows:

- One hundred percent (100%) of inert wastes being reused or recycled AND at least fifty percent (50%) of C&D wastes being reused or recycled; OR

- All waste that is not separated on-site for recycling is sent to a mixed C& D sorting facility for recycling.

14-4. Waste Management Plan Implementation

A. Plan Distribution:

The contractor shall provide copies of the approved Waste Management Plan to the project superintendent and each subcontractor.

B. Instruction:

The contractor shall provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the Project.

C. Meetings:

The contractor shall conduct monthly Construction Waste Management meetings or at least one meeting for projects with length of less than twenty (20) working days. Meetings shall include subcontractors affected by the Waste Management Plan. At a minimum, waste management goals and issues shall be discussed at regularly scheduled project meetings.

D. Separation Facilities:

The contractor shall designate a specific area or areas to facilitate separation of materials for potential reuse, salvage, recycling, and return. Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid co-mingling of materials. Bins set within the County Right of Way shall be subject to approval by the County. All bins used shall be protected during non-working hours from offsite contamination.

E. Materials Handling Procedures:

Materials to be recycled shall be protected from contamination, and shall be handled, stored and transported in a manner that meets the requirements set by the designated facilities for acceptance.

F. Hazardous Wastes:

Hazardous wastes shall be separated, stored, and disposed of according to State and local regulations. Unless specified in other section, the County is not aware of any hazardous wastes within the project site.

Notify the Engineer if hazardous waste is encountered.

G. Reporting:

As a condition of final approval and retention release, submit documentation to the Engineer. Projects that establish monthly progress payments shall also require monthly reporting on the Waste Management Plan. Such reports shall be submitted prior to the monthly cutoff for progress payments and shall include, at a minimum, a summary of waste materials recycled, salvaged and disposed of for the Project. Submitted with this summary will be documentation (receipts/scale tickets, waybills) showing the quantities and types of materials diverted and disposed. The documentation shall coincide with the Waste Management Daily Transport Reports (in Appendix A) that were signed by both the Contractor and the County inspector. A Notice of Completion will not be filed for the project and retention released until all reports as required for the project are submitted and approved.

The above-mentioned summary and documentation shall contain the following information:

- (1) For each material recycled and salvaged from the Project, include the amount (in cubic yards or tons, or in the case of salvaged items, state quantities by number, type and size of items) and the destination (i.e., recycling facility, used building materials yard or other local users).
- (2) For each material landfilled or incinerated from the Project, include the amount (in cubic yards or tons) of material and the identity of the landfill, incinerator and/or transfer station. All projects are subject to inspection.
- (3) Documentation shall consist of photocopies of receipts and weight tags or other records of measurement or equivalent documentation from recycling companies, deconstruction contractors, and landfill and disposal companies. The contractor shall sign the completed Waste Management Plan to certify its accuracy as part of the documentation of compliance.

It is unlawful for any person to submit documentation to the County for an approved Waste Management Plan that that said person knows to contain any false statements, including but not limited to false statements regarding weight

and/or yardage of materials recycled or diverted, or to submit any false or fraudulent receipt or weight tag or other record of measurement.

END OF SECTION

SECTION 15.

EXISTING HIGHWAY FACILITIES

The work performed in connection with various existing highway facilities shall conform to the provisions in Section 15, "Existing Facilities", of the Standard Specifications, and Section 15, "Existing Highway Facilities," of these Special Provisions, and the directions of the Engineer.

The Contractor shall be responsible for providing, by any means necessary, reference points for existing highway facilities (such as water valves, vaults, manholes, monuments) such that said facilities can be located after the roadway has been microsurfaced by the Contractor. All tie-out points shall be removed upon completion of the work. If paint markings are used to locate facilities, the Contractor shall remove these markings by power washing or other method, as approved by the Engineer. The Contractor shall be required to clean any markings placed in association with this Project. The cost for removing said markings shall be fully borne by the Contractor, and no additional compensation will be allowed, therefore.

The Contractor shall call the USA North at (800) 642-2444 a minimum of two (2) working days in advance of any excavation work.

Full compensation for conforming to this provision shall be considered as included in the unit prices paid for the various Contract items of work, and no additional compensation will be allowed, therefore.

END OF SECTION

SECTION 37. MICROSURFACING

Microsurfacing is a mixture of polymer-modified asphalt emulsion, mineral aggregate, mineral filler, water, and other additives, properly proportioned, mixed and spread on a paved surface in accordance these specifications. The mix should be capable of being spread in variable thick cross-sections (wedges, ruts, scratch courses and surfaces), which, after curing and initial traffic consolidation, resists compaction throughout the entire design tolerance range of bitumen content and variable thickness to be encountered. The end product should maintain a skid-resistant surface (high wet friction coefficient) in variable thick sections throughout the service life of the microsurfacing. Within two (2) hours after placement, microsurfacing must be set enough to allow traffic without pilot cars. Protect the microsurfacing from damage until it has set and will not adhere or be picked up by vehicle tires. Microsurfacing must not exhibit distress from traffic such as bleeding, raveling, separation or other distresses.

A. Emulsified Asphalt

General - The emulsified asphalt shall be homogenous and shall be a quick- traffic, polymer-modified cationic asphalt emulsion conforming to the requirements of Section 94 "Asphaltic Emulsions" of the State Standard Specifications and respected revisions.

The polymer material shall be milled or blended into the asphalt or emulsifier solution prior to the emulsification process. The laboratory performing the mix design shall determine the minimum amount and type of polymer modifier. The minimum amount required will be based on asphalt weight content and will be certified by the emulsion supplier. In general, a three percent (3%) polymer solids, based on asphalt weight, is considered minimum.

Quality Tests – For a microsurfacing emulsion, the authorized laboratory must perform quality control sampling and testing at the specified frequency and location for the quality characteristics shown in the following table:

Microsurfacing Emulsion			
Quality characteristic	Test method	Minimum sampling and testing frequency	Sampling location
Tests on emulsion:			
Saybolt Furol Viscosity, at 25°C (Saybolt Furol seconds)	AASHTO T 59	Minimum 1 per day per delivery truck	Delivery truck
Storage stability, 1 day (max, %) ^a			
Sieve test (max, %)			
Residue by evaporation (min, %)	California Test 331	Minimum 1 per day per delivery truck	Delivery truck
Tests on residue from evaporation test:			
Penetration at 25 °C	AASHTO T 49	Minimum 1 per day per delivery truck	Delivery truck
Softening point (min, °C)	AASHTO T 53		
^a Storage stability test will be run if the storage exceeds 48 hours			

Department Acceptance - For micro-surfacing emulsions, acceptance is based on the Department's sampling and testing for compliance with the requirements shown in the following table:

Microsurfacing Emulsion Acceptance Criteria		
Quality characteristic	Test method	Requirement
Tests on emulsion:		
Saybolt Furol Viscosity at 25°C (Saybolt Furol seconds)	AASHTO T 59	15–90
Sieve test (%)	AASHTO T 59	0.30
Storage stability, 1 day (max, %)	AASHTO T 59	0–1
Settlement ^a , 5 days (max, %)	ASTM D244	5
Residue by evaporation (min, %)	California Test 331	62
Tests on residue by evaporation:		
Penetration at 25°C	AASHTO T 49	40–90
Softening point (min, °C)	AASHTO T 53	57
^a Settlement test on emulsion is not required if used within 48 hours of shipment.		

Each load of emulsified asphalt shall be accompanied with a Certificate of Analysis/Compliance to assure that it is the same as that used in the mix design.

B. Aggregate

General - The mineral aggregate shall be Type II. The aggregate shall be a

manufactured crushed stone such as granite, slag, limestone, chat, or other high-quality aggregate, or combination thereof. The material shall be free from vegetable matter and other deleterious substance. All aggregate shall be free of caked lumps and oversize particles. The aggregate, prior to the addition of emulsion shall conform to the requirements of this section. If aggregates are blended each component aggregate shall meet the sand equivalency and abrasion resistance requirements of these specifications when tested in conformance with the respective California Tests. **Application rate shall be Eighteen (18) pounds of aggregate per square yard and rate shall not vary by more than 10% maximum.**

Quality Tests - When tested according to the following tests, the aggregate (excluding mineral filler) should meet these requirements:

Aggregate Acceptance Criteria		
Quality characteristic	Test method	Requirement
Los Angeles Rattler loss (max, %) At 500 revolutions	California Test 211 ^a	35
Percent of crushed particles (min, %)	California Test 205	95
Durability (min)	California Test 229	65
Sand equivalent (min) Type II	California Test 217	65
^a California Test 211 must be performed on the aggregate before crushing. The aggregate supplier must certify that the crushed aggregate being used on the project is manufactured from the source aggregate complying with the LA rattler requirements.		

If the results of the Sand Equivalent test for aggregate do not meet the specified requirement, the microsurfacing represented by the test shall be removed.

Grading - The aggregate shall be Type II and the percentage composition by mass of the aggregate (including mineral filler) shall conform to the following grading requirements when tested in conformance with California Test 202:

Sieve Size	Type II Percent Passing	Stockpile Tolerance +/-
3/8	100	
#4	94-100	5%
#8	65-90	5%
#16	40-70	5%
#30	25-50	5%
#200	5-15	2%

The job mix (target) gradation shall be within the gradation band. After the target gradation has been submitted (this should be the gradation that the mix design is based on), then the percent passing each sieve shall not vary by more than the stockpile tolerance shown in the above table for each individual sieve, and still remain within the gradation band. If the results of the aggregate grading do not meet the specified gradation, the microsurfacing represented by the test shall be removed.

Mineral Filler - If a mineral filler is used, it must be type I or type II Portland cement. A mineral filler used during mix design must be used during production.

Water - The water shall be potable and free of harmful soluble salts or reactive chemicals and any other contaminants. It shall be of such quality that the asphalt will not separate from the emulsion before the microsurfacing is in place on the pavement.

Additive - Additives may be added to the emulsion mix or any of the component materials to provide the control of the quick-traffic properties. They must be included as part of the mix design and be compatible with the other components of the mix.

C. Mix Design

General - At least 7 days before the work commences, the contractor shall submit an approved mix design covering the specific materials to be used on the project. This design will be performed by a laboratory, which has experience in designing microsurfacing. International Slurry Surfacing Association can provide a list of laboratories experienced in microsurfacing design. After the mix design has been

approved, no substitution will be permitted, unless approved by the Engineer. **Should the sample fail to meet the specifications, the County has the option to have the Contractor remove and replace the material that didn't meet the specifications or request a 4-year extended warranty for the material.**

Mix Design - The contractor shall submit for approval a complete mix design prepared and certified by a laboratory. Compatibility of the aggregate, polymer-modified emulsion, mineral filler, and other additives shall be verified by the mix design. The mix design shall be made with the same aggregate gradation that the contractor will provide on the project. The micro-surfacing mix design must have the material proportion limits shown in the following table:

Microsurfacing Mix Design Proportion Limits	
Material	Proportion limits
Micro-surfacing emulsion asphalt residual content (% of dry weight of aggregate)	5.5–10.5
Water and additives	As Required
Mineral filler (% of dry weight of aggregate)	0–3

The micro-surfacing mix design must comply with the requirements shown in the following table:

Microsurfacing Mix Design Requirements		
Quality characteristics	Test method^a	Requirement
Wet cohesion At 30 minutes (set) (min, kg-cm) At 60 minutes (traffic) (min, kg-cm)	Technical Bulletin 139	12 20
Excess asphalt (max, g/m ²)	Technical Bulletin 109	540
Wet stripping (min, %)	Technical Bulletin 114	90
Wet track abrasion loss 6-day soak (max,	Technical Bulletin 100	810

Displacement Lateral (max, %) Specific gravity after 1000 cycles of 57 kg (max)	Technical Bulletin 147A	5 2.10
Classification compatibility (min, grade points)	Technical Bulletin 144	(AAA, BAA) 11
Mix time at 25°C (min)	Technical Bulletin 113	Controllable to 120 seconds
^a Test methods are by the International Slurry Surfacing Association.		

The mixing test and set-time test should be checked at the highest temperatures expected during construction. The mix design should report the quantitative effects of moisture content on the unit weight of the aggregate (bulking effect). The report must clearly show the proportions of aggregate, mineral filler (minimum and maximum), water (minimum and maximum), additive usage, and polymer-modified asphalt emulsion based on the dry weight of the aggregate. All the component materials used in the mix design shall be representative of the materials proposed by the contractor to be used on the project. The percentages of each individual material proposed in the mix design shall be shown in the laboratory report. Individual materials shall be within the following limits:

Component Material	Limits
Residual Asphalt	5.5 to 10.5% by dry weight of aggregate
Mineral Filler	0.0 to 3% by dry weight of aggregate
Polymer-Based Modifier	Minimum of 3% solids based on bitumen weight content
Additives	As needed
Water	As required to produce proper mix consistency

The laboratory that performed the tests and designed the mixture shall sign the laboratory report. The report shall show the results of the tests on individual materials and shall compare their values to those required by these special provisions. The report shall clearly show the proportions of aggregate, filler (minimum and maximum), water (minimum and maximum), set control additive, and emulsion solids content (minimum and maximum) based on the dry mass of aggregate. The laboratory shall report the quantitative effects of moisture content on the unit mass of the aggregate (bulking effect) in conformance with the

requirements of ASTM Designation C 29M. Previous laboratory reports covering the same materials may be accepted provided the material test reports were completed within the previous 12 months. The mix design shall further show the recommended changes in mineral filler, water, and additive proportions for high temperature weather conditions by reporting proportions of materials required for 60 seconds of mix time with materials heated to 100°F. This 100°F mixing report will not be required for projects requiring nighttime application. The component materials used in the mix design shall be representative of the microsurfacing materials proposed by the Contractor for use on the project. Once the Engineer approves the mix design, no substitution of other material will be permitted unless the materials proposed for substitution are first tested and a laboratory report is submitted for the substituted design in conformance with the provisions of these special provisions. Substituted materials shall not be used until the Engineer has approved the mix design for those materials. The Contractor shall furnish an aggregate moisture determination from the stockpile prior to placing the microsurfacing and shall be retested if weather conditions have changed the aggregate moisture content appreciably. Aggregate moisture will be accounted for in determining the aggregate bitumen ratio to be used during placement. Portable acetylene moisture determination kits will be allowed for determining moisture contents. The completed mixture, after addition of water and set control agent, if used, shall be such that the microsurfacing mixture has proper workability. At the expiration of the road closure hours, in conformance with these specifications, the microsurfacing mixture shall be sufficiently cured to support unrestricted traffic.

Aggregate, mineral filler, emulsion, water, and additives, including the set-control agent, if used, shall be proportioned by volume utilizing the mix design approved by the Engineer. If more than one kind of aggregate is used, the correct amount of each kind of aggregate to produce the required grading shall be proportioned separately, prior to adding the other materials of the mixture, in a manner that will result in a uniform and homogeneous blend.

Rate of Application - The microsurfacing mixture shall be of the proper consistency at all times, so as to provide the application rate required by the surface condition. The average single application rate, as measured by the

contractor and witnessed by the Engineer, shall be 18 lb/yd² ±10%.

D. Equipment

General - All equipment, tools, and machines used in the performance of this work shall be maintained in satisfactory working condition at all times to ensure a high-quality product. The machine shall be specifically designed and manufactured to lay microsurfacing. Production and spreading of microsurfacing should follow the Material Plant Quality Program (MPQP), formerly California Test Method 109.

Auxiliary Equipment - The contractor as necessary to perform the work shall provide suitable surface preparation equipment, traffic control equipment, hand tools, and any other support and safety equipment.

E. Calibration

General - Each mixing unit to be used in the performance of the work shall be calibrated in the presence of the Engineer prior to construction. Previous calibration documentation covering the exact materials to be used may be acceptable, provided that no more than 60 days have lapsed. The documentation shall include an individual calibration of each material at various settings, which can be related to the machine metering devices. No machine will be allowed to work on the project until the calibration has been completed and/or accepted.

F. Weather Limitations

General - Only place microsurfacing if both the pavement and air temperatures are at least 50°F and rising. Do not place microsurfacing if rain is imminent or the air temperature is expected to be below 36° F within 24 hours after placement.

G. Surface Preparation

General - Immediately prior to applying the microsurfacing, the surface shall be cleared of all loose material, silt spots, vegetation, and other objectionable material. Any standard cleaning method will be acceptable. Water shall not be used for cleaning unless approved by the Engineer. Even then, no water will be allowed to enter the

storm drain system. Manholes, valve boxes, drop inlets and other service entrances shall be protected from the microsurfacing by a suitable method. The Engineer shall approve the surface preparation prior to surfacing. No dry aggregate either spilled from the lay-down machine or existing on the road, will be permitted.

Immediately preceding the seal application, the Contractor shall cover all grates, slotted manholes, and other appurtenances on and adjacent to the pavement that would allow the entry of the sealing materials; mask with roofing paper, all closed manhole covers, water and gas valve box covers, monuments, monument boxes, etc.; and remove all existing raised pavement markers, thermoplastic pavement markings. Drainage inlets shall be uncovered and cleaned to the satisfaction of the Engineer as soon as the seal sets. The other surface utilities shall be uncovered and cleaned the following day after completion of the slurry seal at each location. If they are not uncovered within this time frame, no additional seal shall be placed until they are uncovered. Gutters, curbs, sidewalks, driveways, shoulders and other structures adjacent to the pavement to be microsealed shall be cleaned of excess seal to the satisfaction of the Engineer. Asphalt pavement, concrete curb, gutter, sidewalk, and other concrete surface structures along existing County streets damaged by the Contractor's operations, including but not limited to walkways, lawns and other landscaping, fences, gates, driveways, walls and mailboxes shall be replaced in kind by the Contractor. Full compensation for protecting and repairing property as specified herein shall be considered as included in the price paid for other items of work, and no additional compensation will be allowed, therefore.

H. Application

General - A test strip shall be placed in conditions similar to those expected to be encountered during the project. The microsurfacing shall be of the desired consistency upon leaving the mixer. A sufficient amount of material shall be carried in all parts of the spreader at all times so that a complete coverage is obtained. Overloading of the spreader shall be avoided. No lumping, balling, or unmixed aggregate shall be permitted. No streaks, such as those caused by oversized aggregate, shall be left in the finished surface. If excess streaking develops, the job will be stopped until the contractor proves to the Engineer that the situation has been

corrected. Excessive streaking is defined as more than four drag marks greater than one-half ($\frac{1}{2}$) inch wide and four (4) inches long, or one inch (1) wide and three (3) inches long, in any 29.9 yd² (25 m²) area. No transverse ripples or longitudinal streaks of one-fourth ($\frac{1}{4}$) inch in depth (6.4 mm) will be permitted, when measured by placing a ten (10) foot (3m) straight edge over the surface.

Transverse and longitudinal joints must be:

1. Uniform
2. Straight
3. Neat in appearance
4. Without material buildup
5. Without uncovered areas

Transverse joints must be butt-type joints. Prevent double placement at transverse joints over previously placed microsurfacing.

Place longitudinal joints:

1. On centerlines, lane lines, edge lines, or shoulder lines
2. With overlaps not more than 4 inches

The maximum difference between the pavement surface and the bottom edge of a 12-foot straightedge placed perpendicular to the longitudinal joint must be 0.04 foot.

Mix Stability - The microsurfacing shall possess sufficient stability so that premature breaking of the material in the spreader box does not occur. The mixture shall be homogeneous during and following mixing and spreading. It shall be free of excess water or emulsion and free of segregation of the emulsion and aggregate fines from the coarser aggregate. Under no circumstances shall water be sprayed directly into the lay-down box while laying microsurfacing material.

Handwork - Areas, which cannot be reached with the mixing machine, shall be surfaced using hand squeegees to provide complete and uniform coverage. If necessary, the area to be hand worked shall be lightly dampened prior to mix placement. Care shall be exercised to leave no unsightly appearance from handwork. The same type of finish as applied by the spreader box shall be required.

Lines - Care shall be taken to ensure straight lines along curbs and shoulders. No runoff on these areas will be permitted. Lines at intersections will be kept straight to provide a good appearance. If necessary, a suitable material will be used to mask off the end of streets to provide straight lines. Edge lines shall not vary by more than ± 2 inches (± 50 mm) horizontal variance in any 96 feet (30m) of length.

Cleanup - All areas, such as man-ways, gutters, and intersections, shall have the microsurfacing mix removed as specified by the Engineer. The contractor shall, on a daily basis, remove any debris associated with the performance of the work.

Loose aggregate remaining after the microsurfacing has set shall be swept up and disposed of the day after it was placed. All streets shall be re-swept two weeks and again six weeks after the completion of the microsurfacing to remove any loose aggregate.

I. Testing

Test samples shall be extracted from the truck tank at mid load from a sampling tap. Before taking samples, draw and dispose of 1 gallon. In the presence of the Engineer, take two 1-quart wide mouth plastic containers for acceptance testing. Immediately after sampling, the contractor shall furnish and submit two 1-quart wide mouth plastic containers of micro-surfacing emulsion taken in the presence of the Engineer. Samples must be submitted in an insulated shipping container. Consistency and residual asphalt content tests shall be made on the samples and compared to the specifications. **Tests will be run by an authorized laboratory at the discretion of the Engineer at the expense of the County. If the test fails, the County has the option to have the Contractor remove and replace the material that didn't meet the specifications or request a 4-year extended warranty for the material. All subsequent testing of failing areas shall be at the expense of the Contractor.** When tests for an area indicate that the application is outside the specified limits, then one of the following remedies shall be applied unless approved otherwise by the Engineer, in writing:

1. A deduction shall be made at a cost of \$2.00 per square yard (SY) of microsurfacing

or

2. The area shall receive an additional microsurfacing seal at the Contractor's expense.

Microsurfacing shall be spread in the direction of traffic or in the opposite direction. Keep hand tools available to remove spillage.

Truck Tags shall be submitted by the Contractor prior to all payment. Full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all work involved in applying microsurfacing, including but not limited to obtaining an adequate water supply from others, cleaning and sweeping pavement surfaces, protection of existing improvements from asphaltic emulsion or microsurfacing stains, furnishing and applying microsurfacing mixture, and all labor, materials, tools, equipment and incidentals necessary for doing all work involved in microsurfacing Gazos Creek Road, complete in place, as shown on the Plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer, shall be considered as included in the Contract unit price paid per square yard for Microsurfacing and no additional compensation will be allowed, therefore.

END OF SECTION

SECTION 39.
ASPHALT CONCRETE (TYPE A)

Asphalt concrete shall be Type A and shall conform to the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications and these Special Provisions.

The Contractor shall be responsible for locating and reference marking all existing highway facilities (such as manholes, valves, and monuments) within the Project limits prior to any paving work.

Asphalt concrete to be used for pavement repairs, as marked in the field by the Engineer, shall be Type A, $\frac{3}{4}$ " Max-Med Grading.

The amount of asphalt binder to be mixed with the aggregate shall be between five percent (5%) and six percent (6%) by weight of dry aggregate. The exact amount of asphaltic binder to be mixed with the aggregate shall be as determined by the Engineer.

Areas to which asphaltic emulsion has been applied shall be closed to public traffic. Care shall be taken to avoid tracking asphaltic emulsion onto existing pavement surfaces beyond the limits of construction.

The Contractor will be responsible for any damage to existing curbs, gutters, sidewalks, and driveways. Any asphalt concrete or asphaltic emulsion stains occurring during the course of this Contract will be cleaned by sandblasting, or any other method satisfactory to the Engineer. The cost of repairing this damage shall be considered as included in the Contract unit price paid per square yard for the Contract item "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)" and no additional compensation will be allowed, therefore.

The Contractor is further advised that it will be his/her responsibility to ensure that the existing drainage patterns are maintained at all locations, as indicated on the Plans or as directed by the Engineer. Full compensation for furnishing all labor, tools, incidentals necessary for doing all work to hand rake said connections shall be considered as included in the Contract items, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," and no additional compensation will be allowed, therefore.

The cost of aggregate, asphalt binder, and liquid asphalt shall be included in the Contract unit price paid per square yard for the Contract item, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," and no additional compensation will be allowed, therefore.

39-1. Compaction Testing

New asphalt concrete (Type A, $\frac{3}{4}$ " Max-Med Grading) placed within the roadway for pavement repairs designated by the Engineer, may be tested for compaction, as directed by the Engineer.

Compacting shall be performed to achieve not less than ninety-five percent (95%) of the maximum theoretical density. The Contractor's attention is directed to Section 6-2, "Materials Testing," of these Special Provisions. Acceptance testing shall be performed using California Test Method (CT) 375, as directed by the Engineer.

For percent of maximum theoretical density, the Engineer determines a deduction for each test result outside the specifications in compliance with the "Reduced Payment Factors for Percentage of Maximum Theoretical Density" Table in Section 39-2.01A(4)(i)(ii) of the Standard Specifications. The County pays for Contractor's call for first test only and, if necessary, subsequent re-test only. Should the subsequent re-test fail, then all subsequent re-tests will be paid for by the Contractor until the desired compaction is reached, and no additional compensation will be allowed, therefore.

39-2. BLANK

39-3. Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)

Pavement repair shall conform to the applicable provisions of Sections 19-1.03C, "Grade Tolerance," and 19-2.03D, "Selected Material," of the Standard Specifications and these Special Provisions, the Plans, and the directions of the Engineer.

Asphalt concrete to be used for pavement repair shall be Type A, $\frac{3}{4}$ " Max-Med Grading. Material type and installation techniques shall conform to the provisions of Section 39, "Asphalt Concrete," of the Standard Specifications, except for payment, and Section 39, "Asphalt Concrete (Type A)," and this Section 39-3, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," of these Special Provisions, and shall be included in the Contract unit price paid per square yard for this item, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," and no separate payment will be allowed, therefore.

Pavement Repair shall consist of removing existing asphalt concrete surfacing and underlying base to a depth of four inches (4”), or 0.33-foot, below the existing grade, compacting the subgrade material, applying a tack coat of asphalt emulsion, and backfilling the resultant excavation with new asphalt concrete to match the existing grade at the locations marked in the field by the Engineer.

Specific areas of pavement repair shall be as marked in the field and as directed by the Engineer. Prior to construction, the Engineer will delineate the outside edges of pavement repair areas throughout the Project.

No excavation shall be left open during non-working hours unless specifically authorized, in writing, by the Engineer. Roadway areas from which surfacing and base material has been removed shall be backfilled to the level of the adjacent undisturbed paved surfaces and/or barricaded, as approved by the Engineer, prior to the time public traffic is allowed thereon.

The compacted lift thickness must not exceed 3 inches, as stipulated in the Standard Specifications, unless waived by the Engineer.

Placing asphalt concrete material shall be in conformance with the provisions of Section 39-2.01C(2), “Spreading and Compacting Equipment,” and Section 39-2.01C(3) “Surface Preparation” of the Standard Specifications.

Prior to placement of asphalt concrete, the outside edges of the pavement repair areas, as shown on the Plans and as directed by the Engineer, shall be cut to provide a clean, neat and uniform joint utilizing a method approved by the Engineer, and the base and vertical faces shall receive a tack coat of asphaltic emulsion (Type SS1) conforming to Section 39-4, “Asphaltic Emulsion (Tack Coat),” of these Special Provisions. The cost for furnishing and placing this asphaltic emulsion (tack coat) shall be considered as included in the Contract unit price paid for “Pavement Repair (Type A, ¾” Max-Med Grading),” and no separate payment will be allowed, therefore.

The Contractor will be required to take corrective steps, as directed by the Engineer, where the outer limits of pavement repair areas are not neat, clean and uniform, as determined by the Engineer. The cost of such corrective steps, including, but not limited to, over-excavation, prior to microsurfacing, shall be fully

borne by the Contractor, and no additional compensation will be allowed, therefore.

Excavated material shall become the property of the Contractor and shall be disposed of outside the highway right of way in accordance with the provisions of Section 5-11, "Disposal of Material outside the Highway Right of Way," of these Special Provisions.

The subgrade material to remain in place shall be graded to a plane, brought to optimum moisture content, and a relative compaction of not less than ninety percent (90%) shall be obtained for a minimum depth of one foot (1') below the grading plane. Areas of the grading plane that are low as a result of over-excavation shall be filled, at the Contractor's expense, with asphalt concrete.

Any damage, as a result of the Contractor's operations, to pavement and base material that is to remain shall be repaired, or removed and replaced, as directed by the Engineer, with new asphalt concrete by and at the sole expense of the Contractor, and no additional compensation will be allowed therefore. The Engineer shall be the sole judge of the adequacy of the completed remedial work.

The limits of pavement repair to be paid for shall be designated by the Engineer. The Contractor is advised that some of the narrower pavement repair areas may not accommodate equipment typically utilized for this operation, and that pavement repair work beyond that designated by the Engineer, even if permitted by the Engineer, shall not be considered as having been authorized by the Engineer and will not be paid for.

The Contract unit price paid per square yard for this item, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)", shall include full compensation for furnishing all labor, materials (including asphalt concrete, asphaltic emulsion), tools, equipment, and incidentals necessary for doing all work involved in repairing existing pavement, including, but not limited to, saw-cutting of existing asphalt concrete pavement, excavation, hauling, placing selected material, disposal of excavated material, including any petromat or other paving reinforcing fabric encountered outside of the right of way, subgrade preparation, placing and compacting new asphalt concrete, and fog seal, including sand for fog seal, as

shown on the Plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer, and no additional compensation will be allowed, therefore.

No adjustment to the Contract bid price will be made for any increase or decrease in the quantity of this item, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," required. The provisions in Section 9-1.06, "Changed Quantity Pay Adjustments," of the Standard Specifications shall not apply to this item of work.

39-4. Asphaltic Emulsion (Tack Coat)

Asphaltic Emulsion (Tack Coat) shall conform to the provisions of Section 39-2.01C(3)(f), "Tack Coat," and Section 94, "Asphaltic Emulsions," of the Standard Specifications, these Special Provisions, and the directions of the Engineer.

For Pavement Repair Areas - Asphaltic emulsion shall be applied as a tack coat and a fog seal to pavement repair areas as marked in the field, as indicated in these Special Provisions and as directed by the Engineer. Asphaltic Emulsion for pavement repair areas shall be Type SS1. The application rate of the fog seal coat to the surface of pavement repair areas shall be such that the asphaltic emulsion will be spread at a rate no greater than 0.10 gallons per square yard, or as directed by the Engineer. See Section 39-2.01C(3)(f) "Tack Coat" of the Standard Specifications for minimum application rates. The finished surface of the pavement repair areas that have been fog sealed shall be sanded with clean sand to absorb any free asphaltic emulsion. Reference is made to Section 39-3, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)," of these Special Provisions.

The areas to which asphaltic emulsion has been applied shall be closed to public traffic, as specified in these Special Provisions and as directed by the Engineer; and the Contractor shall avoid tracking asphaltic emulsion onto existing pavement surfaces beyond the limits of construction.

The Contractor will be responsible for any asphaltic emulsion stains occurring during the course of this Contract. Such stains will be cleaned by sandblasting, or any other method satisfactory to the Engineer. The cost of repairing this damage shall be considered as included in the unit prices paid for

the various Contract items of work, and no additional compensation will be allowed, therefore.

Full compensation for furnishing all labor, materials, tools, equipment and incidental necessary for doing all work involved in furnishing and applying asphaltic emulsion for asphalt concrete pavement repairs, fog seal including sand for fog seal as specified in the Standard Specifications, and these Special Provisions, as shown on the Plans, and as directed by the Engineer, included in the unit price paid for item, "Pavement Repair (Type A, $\frac{3}{4}$ " Max-Med Grading)", and no separate payment or additional compensation will be allowed, therefore.

END OF SECTION

**FEDERAL REQUIREMENTS
FOR
FEDERAL-AID CONSTRUCTION PROJECTS**

FR-1	Federal Forms, Posters and Data Required of Contractor During Construction
FR-2 to FR-10	Part 200- Uniform Administration Requirements, Cost Principals, and Audit Requirements for Federal Awards – Section 200.317 through 200-326 and Appendix II
FR-10 to FR-12	Equal Opportunity Employment
FR-12 to FR-13	Contract Work Hours and Safety Standards
FR-13	Compliance with the Clean Air Act and the Federal Water Pollution Control Act
FR-14 to FR-15	Suspension and Debarment
FR-15	Byrd Anti-Lobbying Amendment
FR-15	Affirmative Procurement of EPA-designated Items in Service and Construction Contracts
FR-16	DHS Seal, Logo, Flags
FR-16	Compliance with Federal Law, Regulations and Executive Orders
FR-16	No Obligation by Federal Government
FR-16	Program Fraud and False or Fraudulent Statements or Related Acts
FR-16	Contracting with Small and Minority Business, Women’s Business Enterprise, and Labor Surplus Area Firms
FR-17	Cost Analysis
FR-18	Federal Wage Rates (North County)
FR-19	Appendix E, Title VI Assurances in Contracts

**FEDERAL FORMS, POSTERS AND DATA
REQUIRED OF CONTRACTOR
DURING CONSTRUCTION**

Reference is made to Section 7-0.10, "Federal Forms Required To Be Submitted By Contractor," of these Special Provisions.

The Contractor will be required to submit a number of standard forms and information during construction in conformance with Federal requirements. The Contractor is reminded that, should Contractor fail to provide the Federal forms in a timely manner without due cause, as determined by the Engineer, the Engineer shall have the option, at his discretion, to either withhold the progress payment or issue a stop work order until such forms have been submitted to the Engineer.

Item	Comment
Certified Payrolls	Provided by Contractor, for self and Subcontractors.
Non-Performance Certifications	Provided by Contractor, for self and Subcontractors.
Daily Personnel and Equipment Log	Reference Appendix C.
Federal Posters	Download at: https://dot.ca.gov/programs/construction/labor-compliance/labor-compliance-posters <u>Posting Requirements:</u> <ul style="list-style-type: none"> - Must be at all active job sites during work, - Must be in plain view for work crew. - Must be in common area (i.e. break room, porta-potty) or, for mobile operations, mounted on a board and moved with crew.
Federal-Aid Construction Project Forms	Reference page FR-2 of this section for Federal Requirements for Federal-Aid Construction Projects.

Part 200- Uniform Administration Requirements, Cost Principals, and Audit Requirements for Federal Awards – Section 200.317 through 200.326 and Appendix II

Procurement Standards

§ 200.317 Procurements by states. When procuring property and services under a Federal award, a state must follow the same policies and procedures it uses for procurements from its non-Federal funds. The state will comply with § 200.322 Procurement of recovered *materials* and ensure that every purchase order or other contract includes any clauses required by section § 200.326 Contract provisions. All other non-Federal entities, including subrecipients of a state, will follow §§ 200.318 General procurement standards through 200.326 Contract provisions.

§ 200.318 General procurement standards. (a) The non-Federal entity must use its own documented procurement procedures which reflect applicable State and local laws and regulations, provided that the procurements conform to applicable Federal law and the standards identified in this section. (b) Non-Federal entities must maintain oversight to ensure that contractors perform in accordance with the terms, conditions, and specifications of their contracts or purchase orders. (c)(1) The non-Federal entity must maintain written standards of conduct covering conflicts of interest and governing the performance of its employees engaged in the selection, award and administration of contracts. No employee, officer, or agent must participate in the selection, award, or administration of a contract supported by a Federal award if he or she has a real or apparent conflict of interest. Such a conflict of interest would arise when the employee, officer, or agent, any member of his or her immediate family, his or her partner, or an organization which employs or is about to employ any of the parties indicated herein, has a financial or other interest in or a tangible personal benefit from a firm considered for a contract. The officers, employees, and agents of the non-Federal entity must neither solicit nor accept gratuities, favors, or anything of monetary value from contractors or parties to subcontracts. However, non-Federal entities may set standards for situations in which the financial interest is not substantial or the gift is an unsolicited item of nominal value. The standards of conduct must provide for disciplinary actions to be applied for violations of such standards by officers, employees, or agents of the non-Federal entity. (2) If the non-Federal entity has a parent, affiliate, or subsidiary organization that is not a state, local government, or Indian tribe, the non-Federal entity must also maintain written standards of conduct covering organizational conflicts of interest. Organizational conflicts of interest means that because of relationships with a parent company, affiliate, or subsidiary organization, the non-Federal entity is unable or appears to be unable to be impartial in conducting a procurement action involving a related organization. (d) The non-Federal entity's procedures must avoid acquisition of unnecessary or duplicative items. Consideration should be given to consolidating or breaking out procurements to obtain a more economical purchase. Where appropriate, an analysis will be made of lease versus purchase alternatives, and any other appropriate analysis to determine the most economical approach. (e) To foster greater economy and efficiency, and in accordance with efforts to promote cost-effective use of shared services across the Federal government, the non-Federal entity is encouraged to enter into state and local intergovernmental agreements or inter-entity agreements where appropriate for procurement or use of common or shared goods and services. (f)

The non-Federal entity is encouraged to use Federal excess and surplus property in lieu of purchasing new equipment and property whenever such use is feasible and reduces project costs.(g) The non-Federal entity is encouraged to use value engineering clauses in contracts for construction projects of sufficient size to offer reasonable opportunities for cost reductions. Value engineering

is a systematic and creative analysis of each contract item or task to ensure that its essential function is provided at the overall lower cost.(h) The non-Federal entity must award contracts only to responsible contractors possessing the ability to perform successfully under the terms and conditions of a proposed procurement. Consideration will be given to such matters as contractor integrity, compliance with public policy, record of past performance, and financial and technical resources.(i) The non-Federal entity must maintain records sufficient to detail the history of procurement. These records will include, but are not necessarily limited to the following: rationale for the method of procurement, selection of contract type, contractor selection or rejection, and the basis for the contract price.(j)(1) The non-Federal entity may use time and material type contracts only after a determination that no other contract is suitable and if the contract includes a ceiling price that the contractor exceeds at its own risk. Time and material type contract means a contract whose cost to a non-Federal entity is the sum of:(i) The actual cost of materials; and(ii) Direct labor hours charged at fixed hourly rates that reflect wages, general and administrative expenses, and profit.(2) Since this formula generates an open-ended contract price, a time-and-materials contract provides no positive profit incentive to the contractor for cost control or labor efficiency.

Therefore, each contract must set a ceiling price that the contractor exceeds at its own risk. Further, the non-Federal entity awarding such a contract must assert a high degree of oversight in order to obtain reasonable assurance that the contractor is using efficient methods and effective cost controls.(k) The non-Federal entity alone must be responsible, in accordance with good administrative practice and sound business judgment, for the settlement of all contractual and administrative issues arising out of procurements. These issues include, but are not limited to, source evaluation, protests, disputes, and claims. These standards do not relieve the non-Federal entity of any contractual responsibilities under its contracts. The Federal awarding agency will not substitute its judgment for that of the non-Federal entity unless the matter is primarily a Federal concern. Violations of law will be referred to the local, state, or Federal authority having proper jurisdiction.

§ 200.319 Competition. (a) All procurement transactions must be conducted in a manner providing full and open competition consistent with the standards of this section. In order to ensure objective contractor performance and eliminate unfair competitive advantage, contractors that develop or draft specifications, requirements, statements of work, and invitations for bids or requests for proposals must be excluded from competing for such procurements. Some of the situations considered to be restrictive of competition include but are not limited to:(1) Placing unreasonable requirements on firms in order for them to qualify to do business;(2) Requiring unnecessary experience and excessive bonding;(3) Noncompetitive pricing practices between firms or between affiliated companies;(4) Noncompetitive contracts to consultants that are on retainer contracts;(5) Organizational conflicts of interest;(6) Specifying only a “brand name” product instead of allowing “an equal” product to be offered and describing the performance or other relevant requirements of the procurement; and(7) Any arbitrary action in the procurement process.(b) The non-Federal entity must conduct

procurements in a manner that prohibits the use of statutorily or administratively imposed state or local geographical preferences in the evaluation of bids or proposals, except in those cases where applicable Federal statutes expressly mandate or encourage geographic preference. Nothing in this section preempts state licensing laws. When contracting for architectural and engineering (A/E) services, geographic location may be a selection criterion provided its application leaves an appropriate number of qualified firms, given the nature and size of the project, to compete for the contract.(c) The non-Federal entity must have written procedures for procurement transactions. These procedures must ensure that all solicitations:(1) Incorporate a clear and accurate description of the technical requirements for the material, product, or service to be procured. Such description must not, in competitive procurements, contain features which unduly restrict competition. The description may include a statement of the qualitative nature of the material, product or service to be procured and, when necessary, must set forth those minimum essential characteristics and standards to which it must conform if it is to satisfy its intended use. Detailed product specifications should be avoided if at all possible. When it is impractical or uneconomical to make a clear and accurate description of the technical requirements, a "brand name or equivalent" description may be used as a means to define the performance or other salient requirements of procurement. The specific features of the named brand which must be met by offers must be clearly stated; and(2) Identify all requirements which the offerors must fulfill and all other factors to be used in evaluating bids or proposals.(d) The non-Federal entity must ensure that all prequalified lists of persons, firms, or products which are used in acquiring goods and services are current and include enough qualified sources to ensure maximum open and free competition. Also, the non-Federal entity must not preclude potential bidders from qualifying during the solicitation period.

§ 200.320 Methods of procurement to be followed. The non-Federal entity must use one of the following methods of procurement.(a) Procurement by micro-purchases. Procurement by micro-purchase is the acquisition of supplies or services, the aggregate dollar amount of which does not exceed \$3,000 (or \$2,000 in the case of acquisitions for construction subject to the Davis-Bacon Act). To the extent practicable, the non-Federal entity must distribute micro-purchases equitably among qualified suppliers. Micro-purchases may be awarded without soliciting competitive quotations if the non-Federal entity considers the price to be reasonable.(b) Procurement by small purchase procedures. Small purchase procedures are those relatively simple and informal procurement methods for securing services, supplies, or other property that do not cost more than the Simplified Acquisition Threshold. If small purchase procedures are used, price or rate quotations must be obtained from an adequate number of qualified sources.(c) Procurement by sealed bids (formal advertising). Bids are publicly solicited and a firm fixed price contract (lump sum or unit price) is awarded to the responsible bidder whose bid, conforming with all the material terms and conditions of the invitation for bids, is the lowest in price. The sealed bid method is the preferred method for procuring construction, if the conditions in paragraph (c)(1) of this section apply.(1) In order for sealed bidding to be feasible, the following conditions should be present:(i) A complete, adequate, and realistic specification or purchase description is available;(ii) Two or more responsible bidders are willing and able to compete effectively for the business; and(iii) The procurement lends itself to a firm fixed price contract and the selection of the successful bidder can be made principally on the basis of price.(2) If

sealed bids are used, the following requirements apply:(i) The invitation for bids will be publicly advertised and bids must be solicited from an adequate number of known suppliers, providing them sufficient response time prior to the date set for opening the bids;(ii) The invitation for bids, which will include any specifications and pertinent attachments, must define the items or services in order for the bidder to properly respond;(iii) All bids will be publicly opened at the time and place prescribed in the invitation for bids;(iv) A firm fixed price contract award will be made in writing to the lowest responsive and responsible bidder. Where specified in bidding documents, factors such as discounts, transportation cost, and life cycle costs must be considered in determining which bid is lowest. Payment discounts will only be used to determine the low bid when prior experience indicates that such discounts are usually taken advantage of; and(v) Any or all bids may be rejected if there is a sound documented reason.(d) Procurement by competitive proposals. The technique of competitive proposals is normally conducted with more than one source submitting an offer, and either a fixed price or cost-reimbursement type contract is awarded. It is generally used when conditions are not appropriate for the use of sealed bids. If this method is used, the following requirements apply:(1) Requests for proposals must be publicized and identify all evaluation factors and their relative importance. Any response to publicized requests for proposals must be considered to the maximum extent practical;(2) Proposals must be solicited from an adequate number of qualified sources;(3) The non-Federal entity must have a written method for conducting technical evaluations of the proposals received and for selecting recipients;(4) Contracts must be awarded to the responsible firm whose proposal is most advantageous to the program, with price and other factors considered; and(5) The non-Federal entity may use competitive proposal procedures for qualifications-based procurement of architectural/engineering (A/E) professional services whereby competitors' qualifications are evaluated and the most qualified competitor is selected, subject to negotiation of fair and reasonable compensation. The method, where price is not used as a selection factor, can only be used in procurement of A/E professional services. It cannot be used to purchase other types of services though A/E firms are a potential source to perform the proposed effort.(e) [Reserved](f) Procurement by noncompetitive proposals. Procurement by noncompetitive proposals is procurement through solicitation of a proposal from only one source and may be used only when one or more of the following circumstances apply:(1) The item is available only from a single source;(2) The public exigency or emergency for the requirement will not permit a delay resulting from competitive solicitation;(3) The Federal awarding agency or pass-through entity expressly authorizes noncompetitive proposals in response to a written request from the non-Federal entity; or(4) After solicitation of a number of sources, competition is determined inadequate.

§ 200.321 Contracting with small and minority businesses, women's business enterprises, and labor surplus area firms. (a) The non-Federal entity must take all necessary affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible.(b) Affirmative steps must include:(1) Placing qualified small and minority businesses and women's business enterprises on solicitation lists;(2) Assuring that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources;(3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's

business enterprises;(4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises;(5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce; and(6) Requiring the prime contractor, if subcontracts are to be let, to take the affirmative steps listed in paragraphs (1) through (5) of this section.

§ 200.322 Procurement of recovered materials. A non-Federal entity that is a state agency or agency of a political subdivision of a state and its contractors must comply with section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act. The requirements of Section 6002 include procuring only items designated in guidelines of the Environmental Protection Agency (EPA) at 40 CFR part 247 that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition, where the purchase price of the item exceeds \$10,000 or the value of the quantity acquired by the preceding fiscal year exceeded \$10,000; procuring solid waste management services in a manner that maximizes energy and resource recovery; and establishing an affirmative procurement program for procurement of recovered materials identified in the EPA guidelines.

§ 200.323 Contract cost and price. (a) The non-Federal entity must perform a cost or price analysis in connection with every procurement action in excess of the Simplified Acquisition Threshold including contract modifications. The method and degree of analysis is dependent on the facts surrounding the particular procurement situation, but as a starting point, the non-Federal entity must make independent estimates before receiving bids or proposals.(b) The non-Federal entity must negotiate profit as a separate element of the price for each contract in which there is no price competition and in all cases where cost analysis is performed. To establish a fair and reasonable profit, consideration must be given to the complexity of the work to be performed, the risk borne by the contractor, the contractor's investment, the amount of subcontracting, the quality of its record of past performance, and industry profit rates in the surrounding geographical area for similar work.(c) Costs or prices based on estimated costs for contracts under the Federal award are allowable only to the extent that costs incurred or cost estimates included in negotiated prices would be allowable for the non-Federal entity under Subpart E—Cost Principles of this part. The non-Federal entity may reference its own cost principles that comply with the Federal cost principles.(d) The cost plus a percentage of cost and percentage of construction cost methods of contracting must not be used.

§ 200.324 Federal awarding agency or pass-through entity review. (a) The non-Federal entity must make available, upon request of the Federal awarding agency or pass-through entity, technical specifications on proposed procurements where the Federal awarding agency or pass-through entity believes such review is needed to ensure that the item or service specified is the one being proposed for acquisition. This review generally will take place prior to the time the specification is incorporated into a solicitation document. However, if the non-Federal entity desires to have the review accomplished after a solicitation has been developed, the Federal awarding agency or pass-through entity may still review the specifications, with such review usually limited to the technical aspects of the proposed purchase.(b) The non-Federal entity must make available upon request, for the Federal awarding agency or pass-through entity pre-procurement review, procurement documents, such as requests for proposals or

invitations for bids, or independent cost estimates, when:(1) The non-Federal entity's procurement procedures or operation fails to comply with the procurement standards in this part;(2) The procurement is expected to exceed the Simplified Acquisition Threshold and is to be awarded without competition or only one bid or offer is received in response to a solicitation;(3) The procurement, which is expected to exceed the Simplified Acquisition Threshold, specifies a “brand name” product;(4) The proposed contract is more than the Simplified Acquisition Threshold and is to be awarded to other than the apparent low bidder under a sealed bid procurement; or(5) A proposed contract modification changes the scope of a contract or increases the contract amount by more than the Simplified Acquisition Threshold.(c) The non-Federal entity is exempt from the pre-procurement review in paragraph (b) of this section if the Federal awarding agency or pass-through entity determines that its procurement systems comply with the standards of this part.(1) The non-Federal entity may request that its procurement system be reviewed by the Federal awarding agency or pass-through entity to determine whether its system meets these standards in order for its system to be certified. Generally, these reviews must occur where there is continuous high-dollar funding, and third party contracts are awarded on a regular basis;(2) The non-Federal entity may self-certify its procurement system. Such self-certification must not limit the Federal awarding agency's right to survey the system. Under a self-certification procedure, the Federal awarding agency may rely on written assurances from the non-Federal entity that it is complying with these standards. The non-Federal entity must cite specific policies, procedures, regulations, or standards as being in compliance with these requirements and have its system available for review.

§ 200.325 Bonding requirements. For construction or facility improvement contracts or subcontracts exceeding the Simplified Acquisition Threshold, the Federal awarding agency or pass-through entity may accept the bonding policy and requirements of the non-Federal entity provided that the Federal awarding agency or pass-through entity has made a determination that the Federal interest is adequately protected. If such a determination has not been made, the minimum requirements must be as follows:(a) A bid guarantee from each bidder equivalent to five percent of the bid price. The “bid guarantee” must consist of a firm commitment such as a bid bond, certified check, or other negotiable instrument accompanying a bid as assurance that the bidder will, upon acceptance of the bid, execute such contractual documents as may be required within the time specified.(b) A performance bond on the part of the contractor for 100 percent of the contract price. A “performance bond” is one executed in connection with a contract to secure fulfillment of all the contractor's obligations under such contract.(c) A payment bond on the part of the contractor for 100 percent of the contract price. A “payment bond” is one executed in connection with a contract to assure payment as required by law of all persons supplying labor and material in the execution of the work provided for in the contract.

§ 200.326 Contract provisions. The non-Federal entity's contracts must contain the applicable provisions described in Appendix II to Part 200—Contract Provisions for non-Federal Entity Contracts Under Federal Awards.

Pt. 200, App. II Appendix II to Part 200—Contract Provisions for Non-Federal Entity Contracts Under Federal Awards In addition to other provisions required by the Federal agency or non-Federal entity, all contracts made by the non-Federal entity under the Federal award must contain provisions covering the following, as applicable.

(A) Contracts for more than the simplified acquisition threshold currently set at \$150,000, which is the inflation adjusted amount determined by the Civilian Agency Acquisition Council and the Defense Acquisition Regulations Council (Councils) as authorized by 41 U.S.C. 1908, must address administrative, contractual, or legal remedies in instances where contractors violate or breach contract terms, and provide for such sanctions and penalties as appropriate.

(B) All contracts in excess of \$10,000 must address termination for cause and for convenience by the non-Federal entity including the manner by which it will be effected and the basis for settlement.

(C) Equal Employment Opportunity. Except as otherwise provided under 41 CFR Part 60, all contracts that meet the definition of "federally assisted construction contract" in 41 CFR Part 60-1.3 must include the equal opportunity clause provided under 41 CFR 60-1.4(b), in accordance with Executive Order 11246, "Equal Employment Opportunity" (30 FR 12319, 12935, 3 CFR Part, 1964-1965 Comp., p. 339), as amended by Executive Order 11375, "Amending Executive Order 11246 Relating to Equal Employment Opportunity," and implementing regulations at 41 CFR part 60, "Office of Federal Contract Compliance Programs, Equal Employment Opportunity, Department of Labor."

(D) Davis-Bacon Act, as amended (40 U.S.C. 3141-3148). When required by Federal program legislation, all prime construction contracts in excess of \$2,000 awarded by non-Federal entities must include a provision for compliance with the Davis-Bacon Act (40 U.S.C. 3141-3144, and 3146-3148) as supplemented by Department of Labor regulations (29 CFR Part 5, "Labor Standards Provisions Applicable to Contracts Covering Federally Financed and Assisted Construction"). In accordance with the statute, contractors must be required to pay wages to laborers and mechanics at a rate not less than the prevailing wages specified in a wage determination made by the Secretary of Labor. In addition, contractors must be required to pay wages not less than once a week. The non-Federal entity must place a copy of the current prevailing wage determination issued by the Department of Labor in each solicitation. The decision to award a contract or subcontract must be conditioned upon the acceptance of the wage determination. The non-Federal entity must report all suspected or reported violations to the Federal awarding agency. The contracts must also include a provision for compliance with the Copeland "Anti-Kickback" Act (40 U.S.C. 3145), as supplemented by Department of Labor regulations (29 CFR Part 3, "Contractors and Subcontractors on Public Building or Public Work Financed in Whole or in Part by Loans or Grants from the United States"). The Act provides that each contractor or subrecipient must be prohibited from inducing, by any means, any person employed in the construction, completion, or repair of public work, to give up any part of the compensation to which he or she is otherwise entitled. The non-Federal entity must report all suspected or reported violations to the Federal awarding agency.

(E) Contract Work Hours and Safety Standards Act (40 U.S.C. 3701-3708). Where applicable, all contracts awarded by the non-Federal entity in excess of \$100,000 that involve the employment of mechanics or laborers must include a provision for compliance with 40 U.S.C. 3702 and 3704, as supplemented by Department of Labor regulations (29 CFR Part 5). Under 40 U.S.C. 3702 of the Act, each contractor must be required to compute the wages of every mechanic and laborer on the basis of a standard work week of 40 hours. Work in excess of the standard work week is permissible provided that the worker is compensated at a rate of not less than one and

a half times the basic rate of pay for all hours worked in excess of 40 hours in the work week. The requirements of 40 U.S.C. 3704 are applicable to construction work and provide that no laborer or mechanic must be required to work in surroundings or under working conditions which are unsanitary, hazardous or dangerous. These requirements do not apply to the purchases of supplies or materials or articles ordinarily available on the open market, or contracts for transportation or transmission of intelligence.

(F) Rights to Inventions Made Under a Contract or Agreement. If the Federal award meets the definition of “funding agreement” under 37 CFR § 401.2 (a) and the recipient or subrecipient wishes to enter into a contract with a small business firm or nonprofit organization regarding the substitution of parties, assignment or performance of experimental, developmental, or research work under that “funding agreement,” the recipient or subrecipient must comply with the requirements of 37 CFR Part 401, “Rights to Inventions Made by Nonprofit Organizations and Small Business Firms Under Government Grants, Contracts and Cooperative Agreements,” and any implementing regulations issued by the awarding agency.

(G) Clean Air Act (42 U.S.C. 7401-7671q.) and the Federal Water Pollution Control Act (33 U.S.C. 1251-1387), as amended—Contracts and subgrants of amounts in excess of \$150,000 must contain a provision that requires the non-Federal award to agree to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal awarding agency and the Regional Office of the Environmental Protection Agency (EPA).

(H) Mandatory standards and policies relating to energy efficiency which are contained in the state energy conservation plan issued in compliance with the Energy Policy and Conservation Act (42 U.S.C. 6201).

(I) Debarment and Suspension (Executive Orders 12549 and 12689)—A contract award (see 2 CFR 180.220) must not be made to parties listed on the governmentwide Excluded Parties List System in the System for Award Management (SAM), in accordance with the OMB guidelines at 2 CFR 180 that implement Executive Orders 12549 (3 CFR Part 1986 Comp., p. 189) and 12689 (3 CFR Part 1989 Comp., p. 235), “Debarment and Suspension.” The Excluded Parties List System in SAM contains the names of parties debarred, suspended, or otherwise excluded by agencies, as well as parties declared ineligible under statutory or regulatory authority other than Executive Order 12549.

(J) Byrd Anti-Lobbying Amendment (31 U.S.C. 1352)—Contractors that apply or bid for an award of \$100,000 or more must file the required certification. Each tier certifies to the tier above that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant or any other award covered by 31 U.S.C. 1352. Each tier must also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award. Such disclosures are forwarded from tier to tier up to the non-Federal award.

(K) See § 200.322 Procurement of recovered materials.

As specified herein the following provisions shall apply unless otherwise noted:

1. Equal Opportunity Employment

As required by 41 CFR 60-1.4(b) for Federally-assisted construction contracts:

The applicant hereby agrees that it will incorporate or cause to be incorporated into any contract for construction work, or modification thereof, as defined in the regulations of the Secretary of Labor at 41 CFR Chapter 60, which is paid for in whole or in part with funds obtained from the Federal Government or borrowed on the credit of the Federal Government pursuant to a grant, contract, loan insurance, or guarantee, or undertaken pursuant to any Federal program involving such grant, contract, loan, insurance, or guarantee, the following equal opportunity clause:

During the performance of this contract, the contractor agrees as follows:

- (a) The contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, or national origin. Such action shall include, but not be limited to the following: Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- (b) The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive considerations for employment without regard to race, color, religion, sex, or national origin.
- (c) The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided advising the said labor union or workers' representatives of the contractor's commitments under this section and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (d) The contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (e) The contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the administering agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.

- (f) In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of the said rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts or federally assisted construction contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965,

and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.

- (g) The contractor will include the portion of the sentence immediately preceding paragraph a and the provisions of paragraphs (a) through (f) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The contractor will take such action with respect to any subcontract or purchase order as the administering agency may direct as a means of enforcing such provisions, including sanctions for noncompliance: *Provided, however,* That in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction by the administering agency the contractor may request the United States to enter into such litigation to protect the interests of the United States.

The applicant further agrees that it will be bound by the above equal opportunity clause with respect to its own employment practices when it participates in federally assisted construction work: *Provided,* That if the applicant so participating is a State or local government, the above equal opportunity clause is not applicable to any agency, instrumentality or subdivision of such government which does not participate in work on or under the contract.

The applicant agrees that it will assist and cooperate actively with the administering agency and the Secretary of Labor in obtaining the compliance of contractors and subcontractors with the equal opportunity clause and the rules, regulations, and relevant orders of the Secretary of Labor, that it will furnish the administering agency and the Secretary of Labor such information as they may require for the supervision of such compliance, and that it will otherwise assist the administering agency in the discharge of the agency's primary responsibility for securing compliance.

The applicant further agrees that it will refrain from entering into any contract or contract modification subject to Executive Order 11246 of September 24, 1965, with a contractor debarred from, or who has not demonstrated eligibility for, Government contracts and federally assisted construction contracts pursuant to the Executive order and will carry out such sanctions and penalties for violation of the equal opportunity clause as may be imposed upon contractors and subcontractors by the administering agency or the Secretary of Labor pursuant to Part II, Subpart D of the Executive order. In addition, the applicant agrees that if it fails or refuses to comply with these undertakings, the administering agency may

take any or all of the following actions: Cancel, terminate, or suspend in whole or in part this grant (contract, loan, insurance, guarantee); refrain from extending any further assistance to the applicant under the program with respect to which the failure or refund occurred until satisfactory assurance of future compliance has been received from such applicant; and refer the case to the Department of Justice for appropriate legal proceedings.

2. Contract Work Hours and Safety Standards

As required by 29 CFR § 5.5(b); 40 USC § 3702 and 3704 for contracts in excess of \$100,000:

- (a) Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- (b) Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (a) of this section the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (a) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (a) of this section.
- (c) Withholding for unpaid wages and liquidated damages. The Federal Emergency Management Agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (b) of this section.

- (d) Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraphs (a) through (d) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (a) through (d) of this section.

3. Compliance with the Clean Air Act and the Federal Water Pollution Control Act

Clean Air Act

- (a) The contractor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act, as amended, 42 U.S.C. § 7401 et seq.
- (b) The contractor agrees to report each violation to the County and understands and agrees that the County will, in turn, report each violation as required to assure notification to the Grant Administrator, Federal Emergency Management Agency, and the appropriate Environmental Protection Agency Regional Office.
- (c) The contractor agrees to include these requirements in each subcontract exceeding \$150,000 financed in whole or in part with Federal assistance provided by FEMA. For contracts in excess of \$150,000, the contractor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act, as amended, 42 U.S.C. § 7401-7671q and the Federal Water Pollution Control Act as amended (33 U.S.C. 1251-1387), and will report violations to FEMA and the Regional Office of the Environmental Protection Agency (EPA).

Federal Water Pollution Control Act

- (a) The contractor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Federal Water Pollution Control Act, as amended, 33 U.S.C. 1251 et seq.
- (b) The contractor agrees to report each violation to the County and understands and agrees that the County will, in turn, report each violation as required to assure notification to the Grant Administrator, Federal Emergency Management Agency, and the appropriate Environmental Protection Agency Regional Office.
- (c) The contractor agrees to include these requirements in each subcontract exceeding \$150,000 financed in whole or in part with Federal assistance provided by FEMA.”

4. Suspension and Debarment

- (a) This contract is a covered transaction for purposes of 2 C.F.R. pt. 180 and 2 C.F.R. pt. 3000. As such the contractor is required to verify that none of the contractor, its principals (defined at 2 C.F.R. § 180.995), or its affiliates (defined at 2 C.F.R. § 180.905) are excluded (defined at 2 C.F.R. § 180.940) or disqualified (defined at 2 C.F.R. § 180.935).
- (b) The contractor must comply with 2 C.F.R. pt. 180, subpart C and 2 C.F.R. pt. 3000, subpart C and must include a requirement to comply with these regulations in any lower tier covered transaction it enters into.
- (c) This certification is a material representation of fact relied upon by FEMA. If it is later determined that the contractor did not comply with 2 C.F.R. pt. 180, subpart C and 2 C.F.R. pt. 3000, subpart C, in addition to remedies available to the County and FEMA, the Federal Government may pursue available remedies, including but not limited to suspension and/or debarment.
- (d) The contractor agrees to comply with the requirements of 2 C.F.R. pt. 180, subpart C and 2 C.F.R. pt. 3000, subpart C while this offer is valid and throughout the period of any contract that may arise from this offer. The contractor further agrees to include a provision requiring such compliance in its lower tier covered transactions.
- (e) Contractor certifies to the best of its knowledge and belief, that it and its subcontractors:
 - (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from covered transactions by any federal department or agency [45 CFR § 92.35];
 - (2) Have not within a three-year period preceding this Agreement been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (federal, state, or local) transaction or contract under a public transaction; violation of federal or state antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
 - (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (federal, state, or local) with commission of any of the offenses enumerated in paragraph (e)(2) of this section; and

- (4) Have not within a three-year period preceding this Agreement had one or more public transactions (federal, state, or local) terminated for cause or default;
- (f) Contractor shall report immediately to the County Department of Public Works (“DPW”) in writing any incidents of alleged fraud and/or abuse by either Contractor or Contractor’s subcontractor. Contractor shall maintain any records, documents or other evidence of fraud and abuse until otherwise notified by DPW.
- (g) Contractor shall maintain any records, documents, or other evidence of fraud and abuse until otherwise notified by County.
- (h) Contractor agrees to timely execute any and all amendments to this Agreement or other required documentation relating to their subcontractors’ debarment/suspension status.

5. Byrd Anti-Lobbying Amendment

Contractors who apply or bid for an award of \$100,000 or more shall file the required certification. Each tier certifies to the tier above that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant, or any other award covered by 31 U.S.C. § 1352. Each tier shall also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award. Such disclosures are forwarded from tier to tier up to the recipient.”

6. Affirmative Procurement of EPA-designated Items in Service and Construction Contracts

Procurement of Recovered Materials

As required by Section 6002 of the Solid Waste Disposal Act (codified as amended by the Resource Conservation and Recovery Act at 42 U.S.C. § 6962):

(1) In the performance of this contract, the Contractor shall make maximum use of products containing recovered materials that are EPA- designated items unless the product cannot be acquired:

- (i) Competitively within a timeframe providing for compliance with the contract performance schedule;
- (ii) Meeting contract performance requirements; or
- (iii) At a reasonable price.

(2) Information about this requirement, along with the list of EPA-designate items, is available at EPA’s Comprehensive Procurement Guidelines web site, <https://www.epa.gov/smm/comprehensive-procurement-guideline-cpg-program>.

7. DHS Seal, Logo, Flags:

The Contractor shall not use the DHS seal (s), logos, crests, or reproductions of flags or likenesses of DHS agency officials without specific FEMA pre-approval.

8. Compliance with Federal Law, regulations, and Executive Orders

This is an acknowledgement that FEMA financial assistance will be used to fund the contract along with the requirement that the contractor will comply with all applicable Federal law, regulations, executive orders, and FEMA policies, procedures, and directives.

9. No Obligation by Federal Government

The Federal government is not party to this contract and is not subject to any obligations or liabilities to the County, contractor, or any other party pertaining to any matter resulting from this contract.

10. Program Fraud and False or Fraudulent Statements or Related Acts

The contractor acknowledges that 31 U.S.C. Chap. 38 (Administrative Remedies for False Claims and Statements) applies to the contractor's actions pertaining to this contract.

11. Contracting With Small and Minority Businesses, Women's Business Enterprises, and Labor Surplus Area Firms

- (a) The Prime Contractor must take all necessary affirmative steps to assure that minority businesses, women's business enterprises, and labor surplus area firms are used when possible.
- (b) Affirmative steps must include:
 - (1) Placing qualified small and minority businesses and women's business enterprises on solicitation lists;
 - (2) Assuring that small and minority businesses, and women's business enterprises are solicited whenever they are potential sources;
 - (3) Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority businesses, and women's business enterprises;
 - (4) Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority businesses, and women's business enterprises;
 - (5) Using the services and assistance, as appropriate, of such organizations as the Small Business Administration and the Minority Business Development Agency of the Department of Commerce; and
 - (6) Requiring the sub-contractor, if subcontracts are to be let, to take the affirmative steps listed in paragraphs (1) through (5) of this section.

12. Cost Analysis

The contractor shall perform cost analysis on all change orders. The cost analysis for all change orders will include a separate determination of profit for each change order requested.

FEDERAL WAGE RATES (NORTH COUNTY)

Incorporated herein are current Federal Wage Rates data for San Mateo County which is **General Decision CA20200018, dated 05/07/2021**, which can also be found at the following government website:

<https://beta.sam.gov/>

To obtain the data:

- (1) Go to the website at the link above.
- (2) Under **The Official U.S. Government System for, Select Wage Determinations (was wdol.gov)**
- (3) Under **Search by WD number**, type in **CA20210018**

CONTRACTOR is advised of the Federal “10-day rule” requiring local agencies to access the “Federal Wage Rates” ten (10) days prior to bid opening to see if updated Federal wage rates have been posted; and, if updated Federal wage rates have been posted, to issue an addendum informing all plan holders of said updated Federal wage rates.

"General Decision Number: CA20210018 05/07/2021

Superseded General Decision Number: CA20200018

State: California

Construction Types: Building, Heavy (Heavy and Dredging) and Highway

Counties: Alameda, Calaveras, Contra Costa, Fresno, Kings, Madera, Mariposa, Merced, Monterey, San Benito, San Francisco, San Joaquin, San Mateo, Santa Clara, Santa Cruz, Stanislaus and Tuolumne Counties in California.

BUILDING CONSTRUCTION PROJECTS; DREDGING PROJECTS (does not include hopper dredge work); HEAVY CONSTRUCTION PROJECTS (does not include water well drilling); HIGHWAY CONSTRUCTION PROJECTS

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.95 for calendar year 2021 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.95 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2021. If this contract is covered by the EO and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must pay workers in that classification at least the wage rate determined through the conformance process set forth in 29 CFR 5.5(a)(1)(ii) (or the EO minimum wage rate, if it is higher than the conformed wage rate). The EO minimum wage rate will be adjusted annually. Please note that this EO applies to the above-mentioned types of contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but it does not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60). Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number Publication Date
0 01/01/2021

- 1 01/08/2021
- 2 01/15/2021
- 3 01/22/2021
- 4 02/05/2021
- 5 02/19/2021
- 6 02/26/2021
- 7 03/05/2021
- 8 04/02/2021
- 9 04/23/2021
- 10 05/07/2021

ASBE0016-004 01/01/2021

AREA 1: CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS & TOULMNE COUNTIES

AREA 2: ALAMEDA, CONTRA COSTA, SAN FRANSICO, SAN MATEO & SANTA CLARA COUNTIES

	Rates	Fringes
Asbestos Removal worker/hazardous material handler (Includes preparation, wetting, stripping, removal, scrapping, vacuuming, bagging and disposing of all insulation materials from mechanical systems, whether they contain asbestos or not)		
Area 1.....	\$ 30.45	10.60
Area 2.....	\$ 36.53	9.27

ASBE0016-008 01/01/2021

AREA 1: ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANSICO, SAN MATEO, SANTA CLARA, & SANTA CRUZ

AREA 2: CALAVERAS, COLUSA, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAU, & TUOLUMNE

	Rates	Fringes
Asbestos Workers/Insulator		

(Includes the application of
all insulating materials,
Protective Coverings,
Coatings, and Finishes to all
types of mechanical systems)

Area 1.....	\$ 74.16	23.58
Area 2.....	\$ 46.81	33.50

BOIL0549-001 10/01/2016

AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO & SANTA CLARA COUNTIES

AREA 2: REMAINING COUNTIES

	Rates	Fringes
--	-------	---------

BOILERMAKER

Area 1.....	\$ 43.28	37.91
Area 2.....	\$ 39.68	35.71

BRCA0003-001 08/01/2020

	Rates	Fringes
--	-------	---------

MARBLE FINISHER.....	\$ 36.53	17.08
----------------------	----------	-------

BRCA0003-003 08/01/2020

	Rates	Fringes
--	-------	---------

MARBLE MASON.....	\$ 51.30	28.47
-------------------	----------	-------

BRCA0003-005 05/01/2020

	Rates	Fringes
--	-------	---------

BRICKLAYER

(1) Fresno, Kings, Madera, Mariposa, Merced....	\$ 43.68	22.19
(7) San Francisco, San Mateo.....	\$ 47.65	26.77
(8) Alameda, Contra Costa, San Benito, Santa Clara.....	\$ 49.42	22.70
(9) Calaveras, San Joaquin, Stanislaus,		

Toulumne.....	\$ 45.12	21.55
(16) Monterey, Santa Cruz...	\$ 45.88	25.02

BRCA0003-008 07/01/2019

	Rates	Fringes
TERRAZZO FINISHER.....	\$ 37.58	17.33
TERRAZZO WORKER/SETTER.....	\$ 48.53	26.84

BRCA0003-011 04/01/2019

AREA 1: Alameda, Contra Costa, Monterey, San Benito, San Francisco, San Mateo, Santa Clara, Santa Cruz

AREA 2: Calaveras, San Joaquin, Stanislaus, Tuolumne

AREA 3: Fresno, Kings, Madera, Mariposa, Merced

	Rates	Fringes
TILE FINISHER		
Area 1.....	\$ 29.94	16.38
Area 2.....	\$ 25.60	14.30
Area 3.....	\$ 26.58	15.65
Tile Layer		
Area 1.....	\$ 49.90	19.16
Area 2.....	\$ 42.67	16.81
Area 3.....	\$ 40.27	18.58

CARP0022-001 07/01/2020

San Francisco County

	Rates	Fringes
Carpenters		
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 52.80	30.82
Journeyman Carpenter.....	\$ 52.65	30.82
Millwright.....	\$ 52.75	32.41

CARP0034-001 07/01/2020

	Rates	Fringes
Diver		
Assistant Tender, ROV		
Tender/Technician.....	\$ 51.90	34.02
Diver standby.....	\$ 58.09	34.02
Diver Tender.....	\$ 57.09	34.02
Diver wet.....	\$ 101.42	34.02
Manifold Operator (mixed gas).....	\$ 62.09	34.02
Manifold Operator (Standby).	\$ 57.09	34.02

DEPTH PAY (Surface Diving):

050 to 100 ft	\$2.00 per foot
101 to 150 ft	\$3.00 per foot
151 to 220 ft	\$4.00 per foot
221 ft.-deeper	\$5.00 per foot

SATURATION DIVING:

The standby rate shall apply until saturation starts. The saturation diving rate applies when divers are under pressure continuously until work task and decompression are complete. The diver rate shall be paid for all saturation hours.

DIVING IN ENCLOSURES:

Where it is necessary for Divers to enter pipes or tunnels, or other enclosures where there is no vertical ascent, the following premium shall be paid: Distance traveled from entrance 26 feet to 300 feet: \$1.00 per foot. When it is necessary for a diver to enter any pipe, tunnel or other enclosure less than 48" in height, the premium will be \$1.00 per foot.

WORK IN COMBINATION OF CLASSIFICATIONS:

Employees working in any combination of classifications within the diving crew (except dive supervisor) in a shift are paid in the classification with the highest rate for that shift.

 CARP0034-003 07/01/2020

	Rates	Fringes
Piledriver.....	\$ 51.90	34.02

 CARP0035-007 07/01/2020

AREA 1: Alameda, Contra Costa, San Francisco, San Mateo, Santa Clara counties

AREA 2: Monterey, San Benito, Santa Cruz Counties

AREA 3: Calaveras, Fresno, Kings, Madera, Mariposa, Merced, San Joaquin, Stanislaus, Tuolumne Counties

	Rates	Fringes
Modular Furniture Installer		
Area 1		
Installer.....	\$ 28.76	22.53
Lead Installer.....	\$ 32.21	23.03
Master Installer.....	\$ 36.43	23.03
Area 2		
Installer.....	\$ 26.11	22.53
Lead Installer.....	\$ 29.08	23.03
Master Installer.....	\$ 32.71	23.03
Area 3		
Installer.....	\$ 25.16	22.53
Lead Installer.....	\$ 27.96	23.03
Master Installer.....	\$ 31.38	23.03

 CARP0035-008 08/01/2020

AREA 1: Alameda, Contra Costa, San Francisco, San Mateo, Santa Clara counties

AREA 2: Monterey, San Benito, Santa Cruz Counties

AREA 3: San Joaquin

AREA 4: Calaveras, Fresno, Kings, Madera, Mariposa, Merced, Stanislaus, Tuolumne Counties

	Rates	Fringes
Drywall Installers/Lathers:		
Area 1.....	\$ 52.65	31.26
Area 2.....	\$ 46.77	31.26
Area 3.....	\$ 47.27	31.26
Area 4.....	\$ 45.92	31.26

Drywall Stocker/Scrapper

Area 1.....	\$ 26.33	18.22
Area 2.....	\$ 23.39	18.22
Area 3.....	\$ 23.64	18.22
Area 4.....	\$ 22.97	18.22

 CARP0152-001 07/01/2020

Contra Costa County

	Rates	Fringes
--	-------	---------

Carpenters

Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 52.80	30.82
Journeyman Carpenter.....	\$ 52.65	30.82
Millwright.....	\$ 52.75	32.41

 CARP0152-002 07/01/2020

San Joaquin County

	Rates	Fringes
--	-------	---------

Carpenters

Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 46.92	30.82
Journeyman Carpenter.....	\$ 46.77	30.82
Millwright.....	\$ 49.27	32.41

 CARP0152-004 07/01/2020

Calaveras, Mariposa, Merced, Stanislaus and Tuolumne Counties

	Rates	Fringes
--	-------	---------

Carpenters

Bridge Builder/Highway		
------------------------	--	--

Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 45.57	30.82	
Journeyman Carpenter.....	\$ 45.42	30.82	
Millwright.....	\$ 47.92	32.41	

 CARP0217-001 07/01/2020

San Mateo County

	Rates	Fringes	
Carpenters			
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 52.80	30.82	
Journeyman Carpenter.....	\$ 52.65	30.82	
Millwright.....	\$ 52.75	32.41	

 CARP0405-001 07/01/2020

Santa Clara County

	Rates	Fringes	
Carpenters			
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 52.80	30.82	
Journeyman Carpenter.....	\$ 52.65	30.82	
Millwright.....	\$ 52.75	32.41	

 CARP0405-002 07/01/2020

San Benito County

Rates	Fringes
-------	---------

Carpenters

Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 46.92	30.82	
Journeyman Carpenter.....	\$ 46.77		30.82
Millwright.....	\$ 49.27	32.41	

 CARP0505-001 07/01/2020

Santa Cruz County

	Rates	Fringes	
--	-------	---------	--

Carpenters

Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 46.92	30.82	
Journeyman Carpenter.....	\$ 46.77		30.82
Millwright.....	\$ 49.27	32.41	

 CARP0605-001 07/01/2020

Monterey County

	Rates	Fringes	
--	-------	---------	--

Carpenters

Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82	
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 46.92	30.82	
Journeyman Carpenter.....	\$ 46.77		30.82
Millwright.....	\$ 49.27	32.41	

 CARP0701-001 07/01/2020

Fresno and Madera Counties

	Rates	Fringes
Carpenters		
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 45.57	30.82
Journeyman Carpenter.....	\$ 45.42	30.82
Millwright.....	\$ 47.92	32.41

 CARP0713-001 07/01/2020

Alameda County

	Rates	Fringes
Carpenters		
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 52.80	30.82
Journeyman Carpenter.....	\$ 52.65	30.82
Millwright.....	\$ 52.75	32.41

 CARP1109-001 07/01/2020

Kings County

	Rates	Fringes
Carpenters		
Bridge Builder/Highway Carpenter.....	\$ 52.65	30.82
Hardwood Floorlayer, Shingler, Power Saw Operator, Steel Scaffold & Steel Shoring Erector, Saw Filer.....	\$ 45.57	30.82
Journeyman Carpenter.....	\$ 45.42	30.82
Millwright.....	\$ 47.92	32.41

 ELEC0006-004 12/01/2020

SAN FRANCISCO COUNTY

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 46.00	3%+21.65
Technician.....	\$ 52.90	3%+21.65

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

 ELEC0006-007 06/01/2020

SAN FRANCISCO COUNTY

	Rates	Fringes
ELECTRICIAN.....	\$ 78.00	3%+35.96

 ELEC0100-002 03/01/2021

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
--	-------	---------

ELECTRICIAN.....\$ 40.50 25.37

 ELEC0100-005 12/01/2019

FRESNO, KINGS, MADERA

	Rates	Fringes
Communications System		
Installer.....\$ 35.25		20.86
Technician.....\$ 40.54		21.02

SCOPE OF WORK

Includes the installation testing, service and maintenance, of the following systems which utilize the transmission and/or transference of voice, sound, vision and digital for commercial, education, security and entertainment purposes for the following: TV monitoring and surveillance, background-foreground music, intercom and telephone interconnect, inventory control systems, microwave transmission, multi-media, multiplex, nurse call system, radio page, school intercom and sound, burglar alarms, and low voltage master clock systems.

A. SOUND AND VOICE TRANSMISSION/TRANSFERENCE SYSTEMS

Background foreground music, Intercom and telephone interconnect systems, Telephone systems Nurse call systems, Radio page systems, School intercom and sound systems, Burglar alarm systems, Low voltage, master clock systems, Multi-media/multiplex systems, Sound and musical entertainment systems, RF systems, Antennas and Wave Guide,

B. FIRE ALARM SYSTEMS Installation, wire pulling and testing

C. TELEVISION AND VIDEO SYSTEMS Television monitoring and surveillance systems Video security systems, Video entertainment systems, Video educational systems, Microwave transmission systems, CATV and CCTV

D. SECURITY SYSTEMS Perimeter security systems Vibration sensor systems Card access systems Access control systems, Sonar/infrared monitoring equipment

E. COMMUNICATIONS SYSTEMS THAT TRANSMIT OR RECEIVE INFORMATION AND/OR CONTROL SYSTEMS THAT ARE INTRINSIC TO THE ABOVE LISTED SYSTEMS SCADA (Supervisory Control and Data Acquisition) PCM (Pulse Code Modulation) Inventory Control Systems, Digital Data Systems Broadband and

Baseband and Carriers Point of Sale Systems, VSAT Data Systems Data Communication Systems RF and Remote Control Systems, Fiber Optic Data Systems

WORK EXCLUDED Raceway systems are not covered (excluding Ladder-Rack for the purpose of the above listed systems). Chases and/or nipples (not to exceed 10 feet) may be installed on open wiring systems. Energy management systems. SCADA (Supervisory Control and Data Acquisition) when not intrinsic to the above listed systems (in the scope). Fire alarm systems when installed in raceways (including wire and cable pulling) shall be performed at the electrician wage rate, when either of the following two (2) conditions apply:

1. The project involves new or major remodel building trades construction.
2. The conductors for the fire alarm system are installed in conduit.

ELEC0234-001 12/28/2020

MONTEREY, SAN BENITO AND SANTA CRUZ COUNTIES

	Rates	Fringes
ELECTRICIAN		
Zone A.....	\$ 53.41	27.95
Zone B.....	\$ 58.75	28.11

Zone A: All of Santa Cruz, Monterey, and San Benito Counties within 25 air miles of Highway 1 and Dolan Road in Moss Landing, and an area extending 5 miles east and west of Highway 101 South to the San Luis Obispo County Line

Zone B: Any area outside of Zone A

ELEC0234-003 12/01/2020

MONTEREY, SAN BENITO, AND SANTA CRUZ COUNTIES

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 45.50	22.52
Technician.....	\$ 52.33	22.72

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC0302-001 03/01/2021

CONTRA COSTA COUNTY

	Rates	Fringes
CABLE SPLICER.....	\$ 63.86	29.17
ELECTRICIAN.....	\$ 56.76	28.95

ELEC0302-003 12/01/2020

CONTRA COSTA COUNTY

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 42.11	22.52
Technician.....	\$ 44.83	22.72

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed

in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC0332-001 06/01/2020

SANTA CLARA COUNTY

	Rates	Fringes
CABLE SPLICER.....	\$ 82.25	40.66
ELECTRICIAN.....	\$ 71.52	40.34

FOOTNOTES: Work under compressed air or where gas masks are required, or work on ladders, scaffolds, stacks, "Bosun's chairs," or other structures and where the workers are not protected by permanent guard rails at a distance of 40 to 60 ft. from the ground or supporting structures: to be paid one and one-half times the straight-time rate of pay. Work on structures of 60 ft. or over (as described above): to be paid twice the straight-time rate of pay.

ELEC0332-003 12/01/2020

SANTA CLARA COUNTY

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 45.50	22.515
Technician.....	\$ 52.33	22.72

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other

data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC0595-001 06/01/2020

ALAMEDA COUNTY

	Rates	Fringes
CABLE SPLICER.....	\$ 69.00	3%+38.52
ELECTRICIAN.....	\$ 60.00	3%+38.52

ELEC0595-002 06/01/2020

CALAVERAS AND SAN JOAQUIN COUNTIES

	Rates	Fringes
CABLE SPLICER.....	\$ 48.00	7.75%+25.33
ELECTRICIAN		
(1) Tunnel work.....	\$ 42.00	7.75%+25.33
(2) All other work.....	\$ 40.00	7.75%+25.33

ELEC0595-006 12/01/2020

ALAMEDA COUNTY

	Rates	Fringes
Sound & Communications		

Installer.....	\$ 45.50	3%+21.15
Technician.....	\$ 52.33	3%+21.15

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC0595-008 12/01/2020

CALAVERAS AND SAN JOAQUIN COUNTIES

	Rates	Fringes
--	-------	---------

Communications System

Installer.....	\$ 36.83	3%+21.15
Technician.....	\$ 42.35	3%+21.15

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75'

above the lowest floor level having building access);
excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC0617-001 06/01/2020

SAN MATEO COUNTY

	Rates	Fringes
ELECTRICIAN.....	\$ 66.00	39.77

ELEC0617-003 12/01/2020

SAN MATEO COUNTY

	Rates	Fringes
Sound & Communications		
Installer.....	\$ 45.50	22.52
Technician.....	\$ 52.33	22.72

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are

installed in the conduit, shall be performed by the inside electrician.

ELEC0684-001 06/01/2020

MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES

	Rates	Fringes
ELECTRICIAN.....	\$ 41.00	3%+24.58
CABLE SPLICER = 110% of Journeyman Electrician		

ELEC0684-004 12/01/2019

MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES

	Rates	Fringes
Communications System		
Installer.....	\$ 35.25	20.86
Technician.....	\$ 40.54	21.02

SCOPE OF WORK: Including any data system whose only function is to transmit or receive information; excluding all other data systems or multiple systems which include control function or power supply; inclusion or exclusion of terminations and testings of conductors determined by their function; excluding fire alarm work when installed in raceways (including wire and cable pulling) and when performed on new or major remodel building projects or jobs for which the conductors for the fire alarm system are installed in conduit; excluding installation of raceway systems, line voltage work, industrial work, life-safety systems (all buildings having floors located more than 75' above the lowest floor level having building access); excluding energy management systems.

FOOTNOTE: Fire alarm work when installed in raceways (including wire and cable pulling), on projects which involve new or major remodel building construction, for which the conductors for the fire alarm system are installed in the conduit, shall be performed by the inside electrician.

ELEC1245-001 06/01/2020

	Rates	Fringes
LINE CONSTRUCTION		
(1) Lineman; Cable splicer..	\$ 59.14	20.78
(2) Equipment specialist (operates crawler tractors, commercial motor vehicles, backhoes, trenchers, cranes (50 tons and below), overhead & underground distribution line equipment).....	\$ 47.24	19.59
(3) Groundman.....	\$ 36.12	19.19
(4) Powderman.....	\$ 51.87	18.79

HOLIDAYS: New Year's Day, M.L. King Day, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day and day after Thanksgiving, Christmas Day

ELEV0008-001 01/01/2021

	Rates	Fringes
ELEVATOR MECHANIC.....	\$ 72.10	35.825+a+b

FOOTNOTE:

- a. PAID VACATION: Employer contributes 8% of regular hourly rate as vacation pay credit for employees with more than 5 years of service, and 6% for 6 months to 5 years of service.
b. PAID HOLIDAYS: New Year's Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, Friday after Thanksgiving, and Christmas Day.

ENGI0003-001 06/29/2020

""AREA 1"" WAGE RATES ARE LISTED BELOW

""AREA 2"" RECEIVES AN ADDITIONAL \$2.00 PER HOUR ABOVE AREA 1 RATES.

SEE AREA DEFINITIONS BELOW

Rates	Fringes
-------	---------

OPERATOR: Power Equipment
(AREA 1:)

GROUP 1.....	\$ 51.42	31.15
GROUP 2.....	\$ 49.89	31.15
GROUP 3.....	\$ 48.41	31.15
GROUP 4.....	\$ 47.03	31.15
GROUP 5.....	\$ 45.76	31.15
GROUP 6.....	\$ 44.44	31.15
GROUP 7.....	\$ 43.30	31.15
GROUP 8.....	\$ 42.16	31.15
GROUP 8-A.....	\$ 39.95	31.15

OPERATOR: Power Equipment
(Cranes and Attachments -
AREA 1:)

GROUP 1		
Cranes.....	\$ 52.30	31.15
Oiler.....	\$ 43.79	31.15
Truck crane oiler.....	\$ 46.08	31.15
GROUP 2		
Cranes.....	\$ 50.54	31.15
Oiler.....	\$ 42.83	31.15
Truck crane oiler.....	\$ 45.07	31.15
GROUP 3		
Cranes.....	\$ 48.80	31.15
Hydraulic.....	\$ 44.44	31.15
Oiler.....	\$ 42.55	31.15
Truck crane oiler.....	\$ 44.83	31.15
GROUP 4		
Cranes.....	\$ 45.76	31.15

OPERATOR: Power Equipment
(Piledriving - AREA 1:)

GROUP 1		
Lifting devices.....	\$ 52.64	31.15
Oiler.....	\$ 43.38	31.15
Truck Crane Oiler.....	\$ 45.66	31.15
GROUP 2		
Lifting devices.....	\$ 50.82	31.15
Oiler.....	\$ 43.11	31.15
Truck Crane Oiler.....	\$ 45.41	31.15
GROUP 3		
Lifting devices.....	\$ 49.14	31.15
Oiler.....	\$ 42.89	31.15
Truck Crane Oiler.....	\$ 45.12	31.15
GROUP 4		
Lifting devices.....	\$ 47.37	31.15
GROUP 5		
Lifting devices.....	\$ 44.73	31.15
GROUP 6		

Lifting devices.....\$ 42.50	31.15
OPERATOR: Power Equipment (Steel Erection - AREA 1:)	
GROUP 1	
Cranes.....\$ 53.27	31.15
Oiler.....\$ 43.72	31.15
Truck Crane Oiler.....\$ 45.95	31.15
GROUP 2	
Cranes.....\$ 51.50	31.15
Oiler.....\$ 43.45	31.15
Truck Crane Oiler.....\$ 45.73	31.15
GROUP 3	
Cranes.....\$ 50.02	31.15
Hydraulic.....\$ 45.07	31.15
Oiler.....\$ 43.23	31.15
Truck Crane Oiler.....\$ 45.46	31.15
GROUP 4	
Cranes.....\$ 48.00	31.15
GROUP 5	
Cranes.....\$ 46.70	31.15
OPERATOR: Power Equipment (Tunnel and Underground Work - AREA 1:)	
SHAFTS, STOPES, RAISES:	
GROUP 1.....\$ 47.52	31.15
GROUP 1-A.....\$ 49.99	31.15
GROUP 2.....\$ 46.26	31.15
GROUP 3.....\$ 44.93	31.15
GROUP 4.....\$ 43.79	31.15
GROUP 5.....\$ 42.65	31.15
UNDERGROUND:	
GROUP 1.....\$ 47.42	31.15
GROUP 1-A.....\$ 49.89	31.15
GROUP 2.....\$ 46.16	31.15
GROUP 3.....\$ 44.83	31.15
GROUP 4.....\$ 43.69	31.15
GROUP 5.....\$ 42.55	31.15

FOOTNOTE: Work suspended by ropes or cables, or work on a Yo-Yo Cat: \$.60 per hour additional.

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Operator of helicopter (when used in erection work); Hydraulic excavator, 7 cu. yds. and over; Power shovels, over 7 cu. yds.

GROUP 2: Highline cableway; Hydraulic excavator, 3-1/2 cu. yds. up to 7 cu. yds.; Licensed construction work boat operator, on site; Power blade operator (finish); Power shovels, over 1 cu. yd. up to and including 7 cu. yds. m.r.c.

GROUP 3: Asphalt milling machine; Cable backhoe; Combination backhoe and loader over 3/4 cu. yds.; Continuous flight tie back machine assistant to engineer or mechanic; Crane mounted continuous flight tie back machine, tonnage to apply; Crane mounted drill attachment, tonnage to apply; Dozer, slope brd; Gradall; Hydraulic excavator, up to 3 1/2 cu. yds.; Loader 4 cu. yds. and over; Long reach excavator; Multiple engine scraper (when used as push pull); Power shovels, up to and including 1 cu. yd.; Pre-stress wire wrapping machine; Side boom cat, 572 or larger; Track loader 4 cu. yds. and over; Wheel excavator (up to and including 750 cu. yds. per hour)

GROUP 4: Asphalt plant engineer/box person; Chicago boom; Combination backhoe and loader up to and including 3/4 cu. yd.; Concrete batch plant (wet or dry); Dozer and/or push cat; Pull- type elevating loader; Gradesetter, grade checker (GPS, mechanical or otherwise); Grooving and grinding machine; Heading shield operator; Heavy-duty drilling equipment, Hughes, LDH, Watson 3000 or similar; Heavy-duty repairperson and/or welder; Lime spreader; Loader under 4 cu. yds.; Lubrication and service engineer (mobile and grease rack); Mechanical finishers or spreader machine (asphalt, Barber-Greene and similar); Miller Formless M-9000 slope paver or similar; Portable crushing and screening plants; Power blade support; Roller operator, asphalt; Rubber-tired scraper, self-loading (paddle-wheels, etc.); Rubber- tired earthmoving equipment (scrapers); Slip form paver (concrete); Small tractor with drag; Soil stabilizer (P & H or equal); Spider plow and spider puller; Tubex pile rig; Unlicensed constuction work boat operator, on site; Timber skidder; Track loader up to 4 yds.; Tractor-drawn scraper; Tractor, compressor drill combination; Welder; Woods-Mixer (and other similar Pugmill equipment)

GROUP 5: Cast-in-place pipe laying machine; Combination slusher and motor operator; Concrete conveyor or concrete pump, truck or equipment mounted; Concrete conveyor, building site; Concrete pump or pumpcrete gun; Drilling equipment, Watson 2000, Texoma 700 or similar; Drilling and boring machinery, horizontal (not to apply to waterliners,

wagon drills or jackhammers); Concrete mixer/all; Person and/or material hoist; Mechanical finishers (concrete) (Clary, Johnson, Bidwell Bridge Deck or similar types); Mechanical burm, curb and/or curb and gutter machine, concrete or asphalt); Mine or shaft hoist; Portable crusher; Power jumbo operator (setting slip-forms, etc., in tunnels); Screed (automatic or manual); Self-propelled compactor with dozer; Tractor with boom D6 or smaller; Trenching machine, maximum digging capacity over 5 ft. depth; Vermeer T-600B rock cutter or similar

GROUP 6: Armor-Coater (or similar); Ballast jack tamper; Boom- type backfilling machine; Assistant plant engineer; Bridge and/or gantry crane; Chemical grouting machine, truck-mounted; Chip spreading machine operator; Concrete saw (self-propelled unit on streets, highways, airports and canals); Deck engineer; Drilling equipment Texoma 600, Hughes 200 Series or similar up to and including 30 ft. m.r.c.; Drill doctor; Helicopter radio operator; Hydro-hammer or similar; Line master; Skidsteer loader, Bobcat larger than 743 series or similar (with attachments); Locomotive; Lull hi-lift or similar; Oiler, truck mounted equipment; Pavement breaker, truck-mounted, with compressor combination; Paving fabric installation and/or laying machine; Pipe bending machine (pipelines only); Pipe wrapping machine (tractor propelled and supported); Screed (except asphaltic concrete paving); Self-propelled pipeline wrapping machine; Tractor; Self-loading chipper; Concrete barrier moving machine

GROUP 7: Ballast regulator; Boom truck or dual-purpose A-frame truck, non-rotating - under 15 tons; Cary lift or similar; Combination slurry mixer and/or cleaner; Drilling equipment, 20 ft. and under m.r.c.; Firetender (hot plant); Grouting machine operator; Highline cableway signalperson; Stationary belt loader (Kolman or similar); Lift slab machine (Vagtborg and similar types); Maginnes internal full slab vibrator; Material hoist (1 drum); Mechanical trench shield; Pavement breaker with or without compressor combination); Pipe cleaning machine (tractor propelled and supported); Post driver; Roller (except asphalt); Chip Seal; Self-propelled automatically applied concrete curing machine (on streets, highways, airports and canals); Self-propelled compactor (without dozer); Signalperson; Slip-form pumps (lifting device for concrete forms); Tie spacer; Tower mobile; Trenching machine, maximum digging capacity up to and including 5 ft. depth; Truck- type loader

GROUP 8: Bit sharpener; Boiler tender; Box operator; Brakeperson; Combination mixer and compressor (shotcrete/gunite); Compressor operator; Deckhand; Fire tender; Forklift (under 20 ft.); Generator; Gunite/shotcrete equipment operator; Hydraulic monitor; Ken seal machine (or similar); Mixermobile; Oiler; Pump operator; Refrigeration plant; Reservoir-debris tug (self-propelled floating); Ross Carrier (construction site); Rotomist operator; Self-propelled tape machine; Shuttlecar; Self-propelled power sweeper operator (includes vacuum sweeper); Slusher operator; Surface heater; Switchperson; Tar pot firetender; Tugger hoist, single drum; Vacuum cooling plant; Welding machine (powered other than by electricity)

GROUP 8-A: Elevator operator; Skidsteer loader-Bobcat 743 series or smaller, and similar (without attachments); Mini excavator under 25 H.P. (backhoe-trencher); Tub grinder wood chipper

ALL CRANES AND ATTACHMENTS

GROUP 1: Clamshell and dragline over 7 cu. yds.; Crane, over 100 tons; Derrick, over 100 tons; Derrick barge pedestal-mounted, over 100 tons; Self-propelled boom-type lifting device, over 100 tons

GROUP 2: Clamshell and dragline over 1 cu. yd. up to and including 7 cu. yds.; Crane, over 45 tons up to and including 100 tons; Derrick barge, 100 tons and under; Self-propelled boom-type lifting device, over 45 tons; Tower crane

GROUP 3: Clamshell and dragline up to and including 1 cu. yd.; Cranes 45 tons and under; Self-propelled boom-type lifting device 45 tons and under;

GROUP 4: Boom Truck or dual purpose A-frame truck, non-rotating over 15 tons; Truck-mounted rotating telescopic boom type lifting device, Manitex or similar (boom truck) over 15 tons; Truck-mounted rotating telescopic boom type lifting device, Manitex or similar (boom truck) - under 15 tons;

PILEDRIVERS

GROUP 1: Derrick barge pedestal mounted over 100 tons; Clamshell over 7 cu. yds.; Self-propelled boom-type lifting device over 100 tons; Truck crane or crawler, land or barge mounted over 100 tons

GROUP 2: Derrick barge pedestal mounted 45 tons to and including 100 tons; Clamshell up to and including 7 cu. yds.; Self-propelled boom-type lifting device over 45 tons; Truck crane or crawler, land or barge mounted, over 45 tons up to and including 100 tons; Fundex F-12 hydraulic pile rig

GROUP 3: Derrick barge pedestal mounted under 45 tons; Self-propelled boom-type lifting device 45 tons and under; Skid/scow piledriver, any tonnage; Truck crane or crawler, land or barge mounted 45 tons and under

GROUP 4: Assistant operator in lieu of assistant to engineer; Forklift, 10 tons and over; Heavy-duty repairperson/welder

GROUP 5: Deck engineer

GROUP 6: Deckhand; Fire tender

STEEL ERECTORS

GROUP 1: Crane over 100 tons; Derrick over 100 tons; Self-propelled boom-type lifting device over 100 tons

GROUP 2: Crane over 45 tons to 100 tons; Derrick under 100 tons; Self-propelled boom-type lifting device over 45 tons to 100 tons; Tower crane

GROUP 3: Crane, 45 tons and under; Self-propelled boom-type lifting device, 45 tons and under

GROUP 4: Chicago boom; Forklift, 10 tons and over; Heavy-duty repair person/welder

GROUP 5: Boom cat

TUNNEL AND UNDERGROUND WORK

GROUP 1-A: Tunnel bore machine operator, 20' diameter or more

GROUP 1: Heading shield operator; Heavy-duty repairperson; Mucking machine (rubber tired, rail or track type); Raised bore operator (tunnels); Tunnel mole bore operator

GROUP 2: Combination slusher and motor operator; Concrete pump or pumpcrete gun; Power jumbo operator

GROUP 3: Drill doctor; Mine or shaft hoist

GROUP 4: Combination slurry mixer cleaner; Grouting Machine operator; Motorman

GROUP 5: Bit Sharpener; Brakeman; Combination mixer and compressor (gunite); Compressor operator; Oiler; Pump operator; Slusher operator

AREA DESCRIPTIONS:

POWER EQUIPMENT OPERATORS, CRANES AND ATTACHMENTS, TUNNEL AND UNDERGROUND [These areas do not apply to Piledrivers and Steel Erectors]

AREA 1: ALAMEDA, CALAVERAS, CONTRA COSTA, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, STANISLAUS, TUOLUMNE
AREA 2 -NOTED BELOW

THE REMAINING COUNTIES ARE SPLIT BETWEEN AREA 1 AND AREA 2 AS NOTED BELOW:

CALAVERAS COUNTY:

Area 1: Remainder
Area 2: Eastern Part

FRESNO COUNTY:

Area 1: Remainder
Area 2: Eastern Part

MADERA COUNTY:

Area 1: Remainder
Area 2: Eastern Part

MARIPOSA COUNTY:

Area 1: Remainder

Area 2: Eastern Part

MONTEREY COUNTY:

Area 1: Remainder

Area 2: Southwestern part

TUOLUMNE COUNTY:

Area 1: Remainder

Area 2: Eastern Part

ENGI0003-008 07/20/2020

	Rates	Fringes
--	-------	---------

Dredging: (DREDGING:
CLAMSHELL & DIPPER DREDGING;
HYDRAULIC SUCTION DREDGING:)

AREA 1:

(1) Leverman.....	\$ 49.88	34.35
(2) Dredge Dozer; Heavy duty repairman.....	\$ 44.92	34.35
(3) Booster Pump Operator; Deck Engineer; Deck mate; Dredge Tender; Winch Operator.....	\$ 43.80	34.35
(4) Bargeman; Deckhand; Fireman; Leveehand; Oiler..	\$ 40.50	34.35

AREA 2:

(1) Leverman.....	\$ 51.88	34.35
(2) Dredge Dozer; Heavy duty repairman.....	\$ 46.92	34.35
(3) Booster Pump Operator; Deck Engineer; Deck mate; Dredge Tender; Winch Operator.....	\$ 45.80	34.35
(4) Bargeman; Deckhand; Fireman; Leveehand; Oiler..	\$ 42.50	34.35

AREA DESCRIPTIONS

AREA 1: ALAMEDA,BUTTE, CONTRA COSTA, KINGS, MARIN, MERCED,
NAPA, SACRAMENTO, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN,
SAN MATEO, SANTA CLARA, SANTA CRUZ, SOLANO, STANISLAUS,

SUTTER, YOLO, AND YUBA COUNTIES

AREA 2: MODOC COUNTY

THE REMAINING COUNTIES ARE SPLIT BETWEEN AREA 1 AND AREA 2
AS NOTED BELOW:

ALPINE COUNTY:

Area 1: Northernmost part

Area 2: Remainder

CALAVERAS COUNTY:

Area 1: Remainder

Area 2: Eastern part

COLUSA COUNTY:

Area 1: Eastern part

Area 2: Remainder

ELDORADO COUNTY:

Area 1: North Central part

Area 2: Remainder

FRESNO COUNTY:

Area 1: Remainder

Area 2: Eastern part

GLENN COUNTY:

Area 1: Eastern part

Area 2: Remainder

LASSEN COUNTY:

Area 1: Western part along the Southern portion of border
with Shasta County

Area 2: Remainder

MADERA COUNTY:

Area 1: Except Eastern part

Area 2: Eastern part

MARIPOSA COUNTY

Area 1: Except Eastern part

Area 2: Eastern part

MONTERREY COUNTY

Area 1: Except Southwestern part

Area 2: Southwestern part

NEVADA COUNTY:

Area 1: All but the Northern portion along the border of
Sierra County

Area 2: Remainder

PLACER COUNTY:

Area 1: All but the Central portion

Area 2: Remainder

PLUMAS COUNTY:

Area 1: Western portion

Area 2: Remainder

SHASTA COUNTY:

Area 1: All but the Northeastern corner

Area 2: Remainder

SIERRA COUNTY:

Area 1: Western part

Area 2: Remainder

SISKIYOU COUNTY:

Area 1: Central part

Area 2: Remainder

SONOMA COUNTY:

Area 1: All but the Northwestern corner

Area 2: Remainder

TEHAMA COUNTY:

Area 1: All but the Western border with Mendocino & Trinity
Counties

Area 2: Remainder

TRINITY COUNTY:

Area 1: East Central part and the Northeastern border with
Shasta County

Area 2: Remainder

TUOLUMNE COUNTY:

Area 1: Except Eastern part

Area 2: Eastern part

ENGI0003-019 06/29/2020

SEE AREA DESCRIPTIONS BELOW

	Rates	Fringes
OPERATOR: Power Equipment (LANDSCAPE WORK ONLY)		
GROUP 1		
AREA 1.....	\$ 39.95	30.28
AREA 2.....	\$ 41.95	30.28
GROUP 2		
AREA 1.....	\$ 36.35	30.28
AREA 2.....	\$ 38.35	30.28
GROUP 3		
AREA 1.....	\$ 31.74	30.28
AREA 2.....	\$ 33.74	30.28

GROUP DESCRIPTIONS:

GROUP 1: Landscape Finish Grade Operator: All finish grade work regardless of equipment used, and all equipment with a rating more than 65 HP.

GROUP 2: Landscape Operator up to 65 HP: All equipment with a manufacturer's rating of 65 HP or less except equipment covered by Group 1 or Group 3. The following equipment shall be included except when used for finish work as long as manufacturer's rating is 65 HP or less: A-Frame and Winch Truck, Backhoe, Forklift, Hydragraphic Seeder Machine, Roller, Rubber-Tired and Track Earthmoving Equipment, Skiploader, Straw Blowers, and Trencher 31 HP up to 65 HP.

GROUP 3: Landscae Utility Operator: Small Rubber-Tired Tractor, Trencher Under 31 HP.

AREA DESCRIPTIONS:

AREA 1: ALAMEDA, BUTTE, CONTRA COSTA, KINGS, MARIN, MERCED, NAPA, SACRAMENTO, SAN BENITO, SAN FRANCISCO, SAN JOAQUIN, SAN MATEO, SANTA CLARA, SANTA CRUZ, SOLANO, STANISLAUS, SUTTER, YOLO, AND YUBA COUNTIES

AREA 2 - MODOC COUNTY

THE REMAINING COUNTIES ARE SPLIT BETWEEN AREA 1 AND AREA 2 AS NOTED BELOW:

ALPINE COUNTY:

Area 1: Northernmost part

Area 2: Remainder

CALAVERAS COUNTY:

Area 1: Except Eastern part

Area 2: Eastern part

COLUSA COUNTY:

Area 1: Eastern part

Area 2: Remainder

DEL NORTE COUNTY:

Area 1: Extreme Southwestern corner

Area 2: Remainder

ELDORADO COUNTY:

Area 1: North Central part

Area 2: Remainder

FRESNO COUNTY

Area 1: Except Eastern part

Area 2: Eastern part

GLENN COUNTY:

Area 1: Eastern part

Area 2: Remainder

HUMBOLDT COUNTY:

Area 1: Except Eastern and Southwestern parts

Area 2: Remainder

LAKE COUNTY:

Area 1: Southern part

Area 2: Remainder

LASSEN COUNTY:

Area 1: Western part along the Southern portion of border
with Shasta County

Area 2: Remainder

MADERA COUNTY

Area 1: Remainder

Area 2: Eastern part

MARIPOSA COUNTY

Area 1: Remainder

Area 2: Eastern part

MENDOCINO COUNTY:

Area 1: Central and Southeastern parts

Area 2: Remainder

MONTEREY COUNTY

Area 1: Remainder

Area 2: Southwestern part

NEVADA COUNTY:

Area 1: All but the Northern portion along the border of
Sierra County

Area 2: Remainder

PLACER COUNTY:

Area 1: All but the Central portion

Area 2: Remainder

PLUMAS COUNTY:

Area 1: Western portion

Area 2: Remainder

SHASTA COUNTY:

Area 1: All but the Northeastern corner

Area 2: Remainder

SIERRA COUNTY:

Area 1: Western part

Area 2: Remainder

SISKIYOU COUNTY:

Area 1: Central part

Area 2: Remainder

SONOMA COUNTY:

Area 1: All but the Northwestern corner

Area 2: Reaminder

TEHAMA COUNTY:

Area 1: All but the Western border with mendocino & Trinity
Counties

Area 2: Remainder

TRINITY COUNTY:

Area 1: East Central part and the Northeaster border with
Shasta County

Area 2: Remainder

TULARE COUNTY;

Area 1: Remainder

Area 2: Eastern part

TUOLUMNE COUNTY:

Area 1: Remainder

Area 2: Eastern Part

 IRON0377-001 07/01/2020

ALAMEDA, CONTRA COSTA, SAN MATEO, SANTA CLARA & SAN FRANCISCO
 COUNTIES

	Rates	Fringes
Ironworkers:		
Fence Erector.....	\$ 34.58	24.81
Ornamental, Reinforcing and Structural.....	\$ 42.50	33.45

PREMIUM PAY:

\$6.00 additional per hour at the following locations:

China Lake Naval Test Station, Chocolate Mountains Naval Reserve-Niland, Edwards AFB, Fort Irwin Military Station, Fort Irwin Training Center-Goldstone, San Clemente Island, San Nicholas Island, Susanville Federal Prison, 29 Palms - Marine Corps, U.S. Marine Base - Barstow, U.S. Naval Air Facility - Sealey, Vandenberg AFB

\$4.00 additional per hour at the following locations:

Army Defense Language Institute - Monterey, Fallon Air Base, Naval Post Graduate School - Monterey, Yermo Marine Corps Logistics Center

\$2.00 additional per hour at the following locations:

Port Hueneme, Port Mugu, U.S. Coast Guard Station - Two Rock

 IRON0433-005 07/01/2020

REMAINING COUNTIES

	Rates	Fringes
--	-------	---------

IRONWORKER

Fence Erector.....	\$ 34.58	24.81
Ornamental, Reinforcing and Structural.....	\$ 41.00	33.45

PREMIUM PAY:

\$6.00 additional per hour at the following locations:

China Lake Naval Test Station, Chocolate Mountains Naval Reserve-Niland, Edwards AFB, Fort Irwin Military Station, Fort Irwin Training Center-Goldstone, San Clemente Island, San Nicholas Island, Susanville Federal Prison, 29 Palms - Marine Corps, U.S. Marine Base - Barstow, U.S. Naval Air Facility - Sealey, Vandenberg AFB

\$4.00 additional per hour at the following locations:

Army Defense Language Institute - Monterey, Fallon Air Base, Naval Post Graduate School - Monterey, Yermo Marine Corps Logistics Center

\$2.00 additional per hour at the following locations:

Port Hueneme, Port Mugu, U.S. Coast Guard Station - Two Rock

LABO0067-002 06/29/2020

AREA ""A"" - ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO AND SANTA CLARA COUNTIES

AREA ""B"" - CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, STANISLAUS, AND TUOLUMNE COUNTIES

	Rates	Fringes
Asbestos Removal Laborer		
All Counties.....	\$ 25.05	12.00
LABORER (Lead Removal)		
Area A.....	\$ 33.07	25.30
Area B.....	\$ 32.07	25.30

ASBESTOS REMOVAL-SCOPE OF WORK: Site mobilization; initial site clean-up; site preparation; removal of

asbestos-containing materials from walls and ceilings; or from pipes, boilers and mechanical systems only if they are being scrapped; encapsulation, enclosure and disposal of asbestos-containing materials by hand or with equipment or machinery; scaffolding; fabrication of temporary wooden barriers; and assembly of decontamination stations.

LABO0073-002 06/25/2018

CALAVERAS AND SAN JOAQUIN COUNTIES

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person..	\$ 29.54	23.65
Traffic Control Person I....	\$ 29.84	23.65
Traffic Control Person II...	\$ 27.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0073-003 07/01/2020

SAN JOAQUIN COUNTY

	Rates	Fringes
LABORER		
Mason Tender-Brick.....	\$ 32.84	23.71

LABO0073-005 06/25/2018

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 37.82	24.11
GROUP 2.....	\$ 37.59	24.11
GROUP 3.....	\$ 37.34	24.11
GROUP 4.....	\$ 36.89	24.11
GROUP 5.....	\$ 36.35	24.11
Shotcrete Specialist.....	\$ 38.34	24.11

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0073-007 06/25/2018

CALAVERAS AND SAN JOAQUIN COUNTIES

Rates Fringes

LABORER (CONSTRUCTION CRAFT
LABORERS)

Construction Specialist		
Group.....	\$ 30.49	23.20
GROUP 1.....	\$ 29.79	23.20
GROUP 1-a.....	\$ 30.01	23.20
GROUP 1-c.....	\$ 29.84	23.20
GROUP 1-e.....	\$ 30.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 2.....	\$ 29.64	23.20
GROUP 3.....	\$ 29.54	23.20
GROUP 4.....	\$ 23.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,

HORTICULTURAL & LANDSCAPE
LABORERS)

(1) New Construction.....\$ 29.54 23.20

(2) Establishment Warranty
Period.....\$ 23.23 23.20

LABORER (GUNITE)

GROUP 1.....\$ 29.75 22.31

GROUP 2.....\$ 29.25 22.31

GROUP 3.....\$ 28.66 22.31

GROUP 4.....\$ 28.54 22.31

LABORER (WRECKING)

GROUP 1.....\$ 29.79 23.20

GROUP 2.....\$ 29.64 23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and buckler; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying,

dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after

the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

- A: at demolition site for the salvage of the material.
- B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
- C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Guniting laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0073-009 07/01/2018

CALAVERAS AND SAN JOAQUIN COUNTIES

	Rates	Fringes
LABORER (Plaster Tender).....	\$ 32.02	23.00

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0261-003 06/25/2018

SAN FRANCISCO AND SAN MATEO COUNTIES

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person..	\$ 20.54	23.65
Traffic Control Person I....	\$ 30.84	23.65
Traffic Control Person II...	\$ 28.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0261-005 06/25/2018

SAN FRANCISCO AND SAN MATEO COUNTIES

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 37.82	24.11
GROUP 2.....	\$ 37.59	24.11
GROUP 3.....	\$ 37.34	24.11
GROUP 4.....	\$ 36.89	24.11
GROUP 5.....	\$ 36.35	24.11
Shotcrete Specialist.....	\$ 38.34	24.11

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Guniting and shotcrete nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickers - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Guniting & shotcrete gunner & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0261-009 06/25/2018

SAN FRANCISCO, AND SAN MATEO COUNTIES

Rates Fringes

LABORER (CONSTRUCTION CRAFT
LABORERS - AREA A:)

Construction Specialist

Group.....	\$ 31.49	23.20
GROUP 1.....	\$ 30.79	23.20
GROUP 1-a.....	\$ 31.01	23.20
GROUP 1-c.....	\$ 30.84	23.20
GROUP 1-e.....	\$ 31.34	23.20
GROUP 1-f.....	\$ 31.37	23.20
GROUP 2.....	\$ 30.64	23.20
GROUP 3.....	\$ 30.54	23.20
GROUP 4.....	\$ 24.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,
HORTICULTURAL & LANDSCAPE
LABORERS - AREA A:)

(1) New Construction.....	\$ 30.54	23.20
(2) Establishment Warranty Period.....	\$ 24.23	23.20

LABORER (WRECKING - AREA A:)

GROUP 1.....	\$ 30.79	23.20
GROUP 2.....	\$ 30.64	23.20

Laborers: (GUNITE - AREA A:)

GROUP 1.....	\$ 30.75	22.31
GROUP 2.....	\$ 30.25	22.31
GROUP 3.....	\$ 29.66	22.31
GROUP 4.....	\$ 29.54	22.31

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in-place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and buckler; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and

explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shotcrete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12

inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:
 A: at demolition site for the salvage of the material.
 B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
 C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Gunitite laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0261-011 05/01/2018

SAN FRANCISCO AND SAN MATEO COUNTIES:

	Rates	Fringes
MASON TENDER, BRICK.....	\$ 35.37	20.70

FOOTNOTES: Underground work such as sewers, manholes, catch basins, sewer pipes, telephone conduits, tunnels and cut trenches: \$5.00 per day additional. Work in live sewage: \$2.50 per day additional.

LABO0261-014 07/01/2017

SAN FRANCISCO AND SAN MATEO COUNTIES:

	Rates	Fringes
PLASTER TENDER.....	\$ 34.70	23.11

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0270-003 06/25/2018

AREA A: SANTA CLARA

AREA B: MONTEREY, SAN BENITO AND SANTA CRUZ COUNTIES

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person		
Area A.....	\$ 30.54	23.65
Area B.....	\$ 29.54	23.65
Traffic Control Person I		
Area A.....	\$ 30.84	23.65
Area B.....	\$ 29.84	23.65
Traffic Control Person II		
Area A.....	\$ 28.34	23.65
Area B.....	\$ 27.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0270-004 06/25/2018

MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 37.82	24.11
GROUP 2.....	\$ 37.59	24.11
GROUP 3.....	\$ 37.34	24.11
GROUP 4.....	\$ 36.89	24.11
GROUP 5.....	\$ 36.35	24.11
Shotcrete Specialist.....	\$ 38.34	24.11

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete nozzlelemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0270-005 07/01/2020

MONTEREY AND SAN BENITO COUNTIES

	Rates	Fringes
LABORER		
Mason Tender-Brick.....	\$ 32.84	23.71

LABO0270-007 06/25/2018

MONTEREY, SAN BENITO, AND SANTA CRUZ, COUNTIES

	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS - AREA B)		
Construction Specialist		
Group.....	\$ 30.40	23.20
GROUP 1.....	\$ 29.79	23.20
GROUP 1-a.....	\$ 30.01	23.20
GROUP 1-c.....	\$ 29.84	23.20
GROUP 1-e.....	\$ 30.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 2.....	\$ 29.64	23.20
GROUP 3.....	\$ 29.54	23.20
GROUP 4.....	\$ 23.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - AREA B)		
(1) New Construction.....	\$ 29.54	23.20
(2) Establishment Warranty Period.....	\$ 23.23	23.20

LABORER (GUNITE - AREA B)		
GROUP 1.....	\$ 29.75	22.31
GROUP 2.....	\$ 29.25	22.31
GROUP 3.....	\$ 28.66	22.31
GROUP 4.....	\$ 28.54	22.31

LABORER (WRECKING - AREA B)		
GROUP 1.....	\$ 29.79	23.20
GROUP 2.....	\$ 29.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in-place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and buckler; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100

lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:
 A: at demolition site for the salvage of the material.
 B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
 C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Guniting laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0270-010 06/25/2018

SANTA CLARA COUNTY

Rates Fringes

LABORER (CONSTRUCTION CRAFT
LABORERS - AREA A:)

Construction Specialist

Group.....	\$ 31.49	23.20
GROUP 1.....	\$ 30.79	23.20
GROUP 1-a.....	\$ 31.01	23.20
GROUP 1-c.....	\$ 30.84	23.20
GROUP 1-e.....	\$ 31.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 2.....	\$ 30.64	23.20
GROUP 3.....	\$ 30.54	23.20
GROUP 4.....	\$ 24.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,
HORTICULTURAL & LANDSCAPE
LABORERS - AREA A:)

(1) New Construction.....	\$ 30.54	23.20
(2) Establishment Warranty Period.....	\$ 24.23	23.20

LABORER (GUNITE - AREA A:)

GROUP 1.....	\$ 30.75	22.31
GROUP 2.....	\$ 30.25	22.31
GROUP 3.....	\$ 29.66	22.31
GROUP 4.....	\$ 29.54	22.31

LABORER (WRECKING - AREA A:)

GROUP 1.....	\$ 30.79	23.20
GROUP 2.....	\$ 30.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and bucket; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143

and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling

of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

A: at demolition site for the salvage of the material.

B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.

C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Guniting laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash,

windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0270-011 07/01/2017

MONTEREY, SAN BENITO, SANTA CRUZ, SANTA CLARA COUNTIES

	Rates	Fringes
LABORER (Plaster Tender).....	\$ 34.70	21.22

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0294-001 07/01/2020

FRESNO, KINGS AND MADERA COUNTIES

	Rates	Fringes
LABORER (Brick)		
Mason Tender-Brick.....	\$ 32.84	23.71

LABO0294-002 06/25/2018

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person..	\$ 29.54	23.65
Traffic Control Person I....	\$ 29.84	23.65
Traffic Control Person II...	\$ 27.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0294-005 06/25/2018

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 37.82	24.11
GROUP 2.....	\$ 37.59	24.11
GROUP 3.....	\$ 37.34	24.11
GROUP 4.....	\$ 36.89	24.11
GROUP 5.....	\$ 36.35	24.11
Shotcrete Specialist.....	\$ 38.34	24.11

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0294-008 06/25/2018

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS - AREA B:)		
Construction Specialist Group.....	\$ 30.49	23.20

GROUP 1.....	\$ 29.79	23.20
GROUP 1-a.....	\$ 30.01	23.20
GROUP 1-c.....	\$ 29.84	23.20
GROUP 1-e.....	\$ 30.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 2.....	\$ 29.64	23.20
GROUP 3.....	\$ 29.54	23.20
GROUP 4.....	\$ 23.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,
HORTICULTURAL & LANDSCAPE
LABORERS - AREA B:)

(1) New Construction.....	\$ 29.54	23.20
(2) Establishment Warranty Period.....	\$ 23.23	23.20

LABORER (GUNITE - AREA B:)

GROUP 1.....	\$ 29.75	22.31
GROUP 2.....	\$ 29.25	22.31
GROUP 3.....	\$ 28.66	22.31
GROUP 4.....	\$ 28.54	22.31

LABORER (WRECKING - AREA B:)

GROUP 1.....	\$ 29.79	23.20
GROUP 2.....	\$ 29.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2

yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and bucket; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building

including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

A: at demolition site for the salvage of the material.

B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.

C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Gunitite laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0294-010 07/01/2018

CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE

	Rates	Fringes
Plasterer tender.....	\$ 32.02	23.00

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0294-011 07/01/2017

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
LABORER (Plaster Tender).....	\$ 31.02	22.52

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0304-002 06/25/2018

ALAMEDA COUNTY

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person..	\$ 30.54	23.65
Traffic Control Person I....	\$ 30.84	23.65
Traffic Control Person II...\$	28.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0304-003 06/26/2017

ALAMEDA COUNTY

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 36.60	24.83
GROUP 2.....	\$ 36.37	24.83
GROUP 3.....	\$ 36.12	24.83
GROUP 4.....	\$ 35.67	24.83
GROUP 5.....	\$ 35.13	24.83
Shotcrete Specialist.....	\$ 37.12	24.83

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete

nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0304-004 06/25/2018

ALAMEDA COUNTY

Rates Fringes

LABORER (CONSTRUCTION CRAFT
LABORERS - AREA A:)

Construction Specialist		
Group.....	\$ 31.49	23.20
GROUP 1.....	\$ 30.79	23.20
GROUP 1-a.....	\$ 31.01	23.20
GROUP 1-c.....	\$ 30.84	23.20
GROUP 1-e.....	\$ 31.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 2.....	\$ 30.64	23.20
GROUP 3.....	\$ 30.54	23.20
GROUP 4.....	\$ 24.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,
HORTICULTURAL & LANDSCAPE
LABORERS - AREA A:)

(1) New Construction.....	\$ 30.54	23.20
(2) Establishment Warranty		

Period.....	\$ 24.23	23.20
LABORER (GUNITE - AREA A:)		
GROUP 1.....	\$ 30.75	22.31
GROUP 2.....	\$ 30.25	22.31
GROUP 3.....	\$ 29.66	22.31
GROUP 4.....	\$ 29.54	22.31
LABORER (WRECKING - AREA A:)		
GROUP 1.....	\$ 30.79	23.20
GROUP 2.....	\$ 30.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and bucket; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of

voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. "Sewer cleaner" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing

is a hole 15 feet or more in depth.) In the event the depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

- A: at demolition site for the salvage of the material.
- B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
- C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

 GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Gunitite laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO0304-005 05/01/2018

ALAMEDA COUNTY

	Rates	Fringes
Brick Tender.....	\$ 35.37	20.70

FOOTNOTES: Work on jobs where heat-protective clothing is required: \$2.00 per hour additional. Work at grinders: \$.25 per hour additional. Manhole work: \$2.00 per day additional.

LABO0304-008 07/01/2017

ALAMEDA AND CONTRA COSTA COUNTIES:

	Rates	Fringes
Plasterer tender.....	\$ 34.70	23.11

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO0324-002 06/25/2018

CONTRA COSTA COUNTY

	Rates	Fringes
LABORER (TRAFFIC CONTROL/LANE CLOSURE)		
Escort Driver, Flag Person..	\$ 30.54	23.65
Traffic Control Person I....	\$ 30.84	23.65
Traffic Control Person II...	\$ 28.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO0324-006 06/25/2018

CONTRA COSTA COUNTY

	Rates	Fringes
Tunnel and Shaft Laborers:		
GROUP 1.....	\$ 37.82	24.11
GROUP 2.....	\$ 37.59	24.11
GROUP 3.....	\$ 37.34	24.11
GROUP 4.....	\$ 36.89	24.11
GROUP 5.....	\$ 36.35	24.11
Shotcrete Specialist.....	\$ 38.34	24.11

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and

setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO0324-012 06/25/2018

CONTRA COSTA COUNTY

Rates Fringes

LABORER (CONSTRUCTION CRAFT

LABORERS - AREA A:)

Construction Specialist

Group.....	\$ 31.49	23.20
GROUP 1.....	\$ 30.79	23.20
GROUP 1-a.....	\$ 31.01	23.20
GROUP 1-c.....	\$ 30.84	23.20
GROUP 1-e.....	\$ 31.34	23.20
GROUP 1-f.....	\$ 30.37	23.20
GROUP 1-g.....	\$ 30.99	23.20
GROUP 2.....	\$ 30.64	23.20
GROUP 3.....	\$ 30.54	23.20
GROUP 4.....	\$ 24.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS,
HORTICULURAL & LANDSCAPE

LABORERS - AREA A:)

(1) New Construction.....	\$ 30.54	23.20
(2) Establishment Warranty Period.....	\$ 24.23	23.20

LABORER (GUNITE - AREA A:)

GROUP 1.....	\$ 30.75	22.31
GROUP 2.....	\$ 30.25	22.31
GROUP 3.....	\$ 29.66	22.31
GROUP 4.....	\$ 29.54	22.31

LABORER (WRECKING - AREA A:)

GROUP 1.....	\$ 30.79	23.20
GROUP 2.....	\$ 30.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging

scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and buckler; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder; Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster;

Vibrascreed, bull float in connection with laborers' work;
Vibrator; Hazardous waste worker (lead removal); Asbestos
and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143
and similar type drills; Track driller; Jack leg driller;
Wagon driller; Mechanical drillers, all types regardless of
type or method of power; Mechanical pipe layers, all types
regardless of type or method of power; Blaster and powder;
All work of loading, placing and blasting of all powder and
explosives of whatever type regardless of method used for
such loading and placing; High scalers (including drilling
of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above
Group 1 wage rates. ""Sewer cleaner"" means any worker who
handles or comes in contact with raw sewage in small
diameter sewers. Those who work inside recently active,
large diameter sewers, and all recently active sewer
manholes shall receive \$5.00 per day above Group 1 wage
rates.

GROUP 1-c: Burning and welding in connection with laborers'
work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All
employees performing work covered herein shall receive \$
.25 per hour above their regular rate for all work
performed on underground structures not specifically
covered herein. This paragraph shall not be construed to
apply to work below ground level in open cut. It shall
apply to cut and cover work of subway construction after
the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts
thereof, and work on and in deep footings. (A deep footing
is a hole 15 feet or more in depth.) In the event the
depth of the footing is unknown at the commencement of
excavation, and the final depth exceeds 15 feet, the deep
footing wage rate would apply to all employees for each and
every day worked on or in the excavation of the footing
from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting
or shot crete

GROUP 1-g, CONTRA COSTA COUNTY: Pipelayer (including grade
checking in connection with pipelaying); Caulker; Bander;

Pipewrapper; Conduit layer; Plastic pipe layer; Pressure pipe tester; No joint pipe and stripping of same, including repair of voids; Precast manhole setters, cast in place manhole form setters

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

- A: at demolition site for the salvage of the material.
- B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
- C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Guniting laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

GROUP 1-g, CONTRA COSTA COUNTY: Pipelayer (including grade checking in connection with pipelaying); Caulker; Bander; Pipewrapper; Conduit layer; Plastic pipe layer; Pressure pipe tester; No joint pipe and stripping of same, including repair of voids; Precast manhole setters, cast in place manhole form setters

LABO0324-014 05/01/2018

CONTRA COSTA COUNTY:

	Rates	Fringes
Brick Tender.....	\$ 35.37	20.70

FOOTNOTES: Work on jobs where heat-protective clothing is required: \$2.00 per hour additional. Work at grinders: \$.25 per hour additional. Manhole work: \$2.00 per day additional.

LABO0324-018 07/01/2018

ALAMEDA AND CONTRA COSTA COUNTIES:

	Rates	Fringes
Plasterer tender.....	\$ 37.14	22.32

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO1130-002 06/25/2018

MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES

Rates Fringes

LABORER (TRAFFIC CONTROL/LANE CLOSURE)

Escort Driver, Flag Person..\$ 29.54	23.65
Traffic Control Person I....\$ 29.84	23.65
Traffic Control Person II...\$ 27.34	23.65

TRAFFIC CONTROL PERSON I: Layout of traffic control, crash cushions, construction area and roadside signage.

TRAFFIC CONTROL PERSON II: Installation and removal of temporary/permanent signs, markers, delineators and crash cushions.

LABO1130-003 06/26/2017

MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES

Rates Fringes

Tunnel and Shaft Laborers:

GROUP 1.....\$ 36.60	24.83
GROUP 2.....\$ 36.37	24.83
GROUP 3.....\$ 36.12	24.83
GROUP 4.....\$ 35.67	24.83
GROUP 5.....\$ 35.13	24.83
Shotcrete Specialist.....\$ 37.12	24.83

TUNNEL AND SHAFT CLASSIFICATIONS

GROUP 1: Diamond driller; Groundmen; Gunite and shotcrete nozzlemen

GROUP 2: Rodmen; Shaft work & raise (below actual or excavated ground level)

GROUP 3: Bit grinder; Blaster, driller, powdermen, heading; Cherry pickermen - where car is lifted; Concrete finisher in tunnel; Concrete screedman; Grout pumpman and potman; Gunite & shotcrete gunman & potman; Headermen; High pressure nozzleman; Miner - tunnel, including top and

bottom man on shaft and raise work; Nipper; Nozzleman on slick line; Sandblaster - potman, Robotic Shotcrete Placer, Segment Erector, Tunnel Muck Hauler, Steel Form raiser and setter; Timberman, retimberman (wood or steel or substitute materials therefore); Tugger (for tunnel laborer work); Cable tender; Chuck tender; Powderman - primer house

GROUP 4: Vibrator operator, pavement breaker; Bull gang - muckers, trackmen; Concrete crew - includes rodding and spreading, Dumpmen (any method)

GROUP 5: Grout crew; Reboundman; Swamper/ Brakeman

LABO1130-005 07/01/2018

MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES

	Rates	Fringes
LABORER		
Mason Tender-Brick.....	\$ 31.20	22.20

LABO1130-007 06/25/2018

MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE , COUNTIES

	Rates	Fringes
LABORER (CONSTRUCTION CRAFT LABORERS - AREA B:)		
Construction Specialist		
Group.....	\$ 30.49	23.20
GROUP 1.....	\$ 29.79	23.20
GROUP 1-a.....	\$ 30.01	23.20
GROUP 1-c.....	\$ 29.84	23.20
GROUP 1-e.....	\$ 30.34	23.20
GROUP 1-f.....	\$ 29.37	23.20
GROUP 2.....	\$ 29.64	23.20
GROUP 3.....	\$ 29.54	23.20
GROUP 4.....	\$ 23.23	23.20

See groups 1-b and 1-d under laborer classifications.

LABORER (GARDENERS, HORTICULTURAL & LANDSCAPE LABORERS - AREA B:)		
(1) New Construction.....	\$ 29.54	23.20
(2) Establishment Warranty Period.....	\$ 23.23	23.20

LABORER (GUNITE - AREA B:)		
GROUP 1.....	\$ 29.75	22.31
GROUP 2.....	\$ 29.25	22.31
GROUP 3.....	\$ 28.66	22.31
GROUP 4.....	\$ 28.54	22.31
LABORER (WRECKING - AREA B:)		
GROUP 1.....	\$ 29.79	23.20
GROUP 2.....	\$ 29.64	23.20

FOOTNOTES:

Laborers working off or with or from bos'n chairs, swinging scaffolds, belts shall receive \$0.25 per hour above the applicable wage rate. This shall not apply to workers entitled to receive the wage rate set forth in Group 1-a below.

LABORER CLASSIFICATIONS

CONSTRUCTION SPECIALIST GROUP: Asphalt ironer and raker; Chainsaw; Laser beam in connection with laborers' work; Cast-in- place manhole form setter; Pressure pipelayer; Davis trencher - 300 or similar type (and all small trenchers); Blaster; Diamond driller; Multiple unit drill; Hydraulic drill

GROUP 1: Asphalt spreader boxes (all types); Barko, Wacker and similar type tampers; Buggymobile; Caulker, bander, pipewrapper, conduit layer, plastic pipelayer; Certified hazardous waste worker including Leade Abatement; Compactors of all types; Concrete and magnesite mixer, 1/2 yd. and under; Concrete pan work; Concrete sander; Concrete saw; Cribber and/or shoring; Cut granite curb setter; Dri-pak-it machine; Faller, logloader and bucket; Form raiser, slip forms; Green cutter; Headerboard, Hubsetter, aligner, by any method; High pressure blow pipe (1-1/2" or over, 100 lbs. pressure/over); Hydro seeder and similar type; Jackhammer operator; Jacking of pipe over 12 inches; Jackson and similar type compactor; Kettle tender, pot and worker applying asphalt, lay-kold, creosote, lime, caustic and similar type materials (applying means applying, dipping or handling of such materials); Lagging, sheeting, whaling, bracing, trenchjacking, lagging hammer; Magnesite, epoxyresin, fiberglass, mastic worker (wet or dry); No joint pipe and stripping of same, including repair of voids; Pavement breaker and spader, including tool grinder;

Perma curb; Pipelayer (including grade checking in connection with pipelaying); Precast-manhole setter; Pressure pipe tester; Post hole digger, air, gas and electric; Power broom sweeper; Power tampers of all types (except as shown in Group 2); Ram set gun and stud gun; Riprap stonepaver and rock-slinger, including placing of sacked concrete and/or sand (wet or dry) and gabions and similar type; Rotary scarifier or multiple head concrete chipping scarifier; Roto and Ditch Witch; Rototiller; Sandblaster, pot, gun, nozzle operators; Signalling and rigging; Tank cleaner; Tree climber; Turbo blaster; Vibrascreed, bull float in connection with laborers' work; Vibrator; Hazardous waste worker (lead removal); Asbestos and mold removal worker

GROUP 1-a: Joy drill model TWM-2A; Gardner-Denver model DH143 and similar type drills; Track driller; Jack leg driller; Wagon driller; Mechanical drillers, all types regardless of type or method of power; Mechanical pipe layers, all types regardless of type or method of power; Blaster and powder; All work of loading, placing and blasting of all powder and explosives of whatever type regardless of method used for such loading and placing; High scalers (including drilling of same); Tree topper; Bit grinder

GROUP 1-b: Sewer cleaners shall receive \$4.00 per day above Group 1 wage rates. ""Sewer cleaner"" means any worker who handles or comes in contact with raw sewage in small diameter sewers. Those who work inside recently active, large diameter sewers, and all recently active sewer manholes shall receive \$5.00 per day above Group 1 wage rates.

GROUP 1-c: Burning and welding in connection with laborers' work; Synthetic thermoplastics and similar type welding

GROUP 1-d: Maintenance and repair track and road beds. All employees performing work covered herein shall receive \$.25 per hour above their regular rate for all work performed on underground structures not specifically covered herein. This paragraph shall not be construed to apply to work below ground level in open cut. It shall apply to cut and cover work of subway construction after the temporary cover has been placed.

GROUP 1-e: Work on and/or in bell hole footings and shafts thereof, and work on and in deep footings. (A deep footing is a hole 15 feet or more in depth.) In the event the

depth of the footing is unknown at the commencement of excavation, and the final depth exceeds 15 feet, the deep footing wage rate would apply to all employees for each and every day worked on or in the excavation of the footing from the date of inception.

GROUP 1-f: Wire winding machine in connection with guniting or shot crete

GROUP 2: Asphalt shoveler; Cement dumper and handling dry cement or gypsum; Choke-setter and rigger (clearing work); Concrete bucket dumper and chute; Concrete chipping and grinding; Concrete laborer (wet or dry); Driller tender, chuck tender, nipper; Guinea chaser (stake), grout crew; High pressure nozzle, adductor; Hydraulic monitor (over 100 lbs. pressure); Loading and unloading, carrying and hauling of all rods and materials for use in reinforcing concrete construction; Pittsburgh chipper and similar type brush shredders; Sloper; Single foot, hand-held, pneumatic tamper; All pneumatic, air, gas and electric tools not listed in Groups 1 through 1-f; Jacking of pipe - under 12 inches

GROUP 3: Construction laborers, including bridge and general laborer; Dump, load spotter; Flag person; Fire watcher; Fence erector; Guardrail erector; Gardener, horticultural and landscape laborer; Jetting; Limber, brush loader and piler; Pavement marker (button setter); Maintenance, repair track and road beds; Streetcar and railroad construction track laborer; Temporary air and water lines, Victaulic or similar; Tool room attendant (jobsite only)

GROUP 4: Final clean-up work of debris, grounds and building including but not limited to: street cleaner; cleaning and washing windows; brick cleaner (jobsite only); material cleaner (jobsite only). The classification "material cleaner" is to be utilized under the following conditions:

- A: at demolition site for the salvage of the material.
- B: at the conclusion of a job where the material is to be salvaged and stocked to be reused on another job.
- C: for the cleaning of salvage material at the jobsite or temporary jobsite yard.

The material cleaner classification should not be used in the performance of "form stripping, cleaning and oiling and moving to the next point of erection".

GUNITE LABORER CLASSIFICATIONS

GROUP 1: Structural Nozzleman

GROUP 2: Nozzleman, Gunman, Potman, Groundman

GROUP 3: Reboundman

GROUP 4: Guniting laborer

WRECKING WORK LABORER CLASSIFICATIONS

GROUP 1: Skilled wrecker (removing and salvaging of sash, windows and materials)

GROUP 2: Semi-skilled wrecker (salvaging of other building materials)

LABO1130-008 07/01/2018

CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE

	Rates	Fringes
Plasterer tender.....	\$ 32.02	23.00

Work on a swing stage scaffold: \$1.00 per hour additional.

LABO1130-009 07/01/2018

MARIPOSA, MERCED, STANISLAUS, AND TUOLUMNE COUNTIES

	Rates	Fringes
LABORER (Plaster Tender).....	\$ 32.02	23.00

Work on a swing stage scaffold: \$1.00 per hour additional.

PAIN0016-001 01/01/2021

ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN MATEO, SANTA CLARA, AND SANTA CRUZ COUNTIES

	Rates	Fringes
Painters:.....	\$ 45.22	25.48

PREMIUMS:

EXOTIC MATERIALS - \$1.25 additional per hour.
 SPRAY WORK: - \$0.50 additional per hour.
 INDUSTRIAL PAINTING - \$0.25 additional per hour
 [Work on industrial buildings used for the manufacture and
 processing of goods for sale or service; steel construction
 (bridges), stacks, towers, tanks, and similar structures]

HIGH WORK:

over 50 feet - \$2.00 per hour additional
 100 to 180 feet - \$4.00 per hour additional
 Over 180 feet - \$6.00 per hour additional

 PAIN0016-003 06/01/2020

AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO & SANTA CLARA COUNTIES

AREA 2: CALAVERAS, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS & TUOLUMNE COUNTIES

	Rates	Fringes
Drywall Finisher/Taper		
AREA 1.....	\$ 51.51	27.39
AREA 2.....	\$ 47.38	25.99

 PAIN0016-012 01/01/2019

ALAMEDA, CONTRA COSTA, MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA AND SANTA CRUZ COUNTIES

	Rates	Fringes
SOFT FLOOR LAYER.....	\$ 48.60	27.43

 * PAIN0016-015 01/01/2021

CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE
COUNTIES

	Rates	Fringes
PAINTER		
Brush.....	\$ 35.88	21.16

FOOTNOTES:

SPRAY/SANDBLAST: \$0.50 additional per hour.

EXOTIC MATERIALS: \$1.25 additional per hour.

HIGH TIME: Over 50 ft above ground or water level \$2.00
additional per hour. 100 to 180 ft above ground or water
level \$4.00 additional per hour. Over 180 ft above ground
or water level \$6.00 additional per hour.

PAIN0016-022 01/01/2021

SAN FRANCISCO COUNTY

	Rates	Fringes
PAINTER.....	\$ 48.84	25.48

PAIN0169-001 06/01/2020

FRESNO, KINGS, MADERA, MARIPOSA AND MERCED COUNTIES:

	Rates	Fringes
GLAZIER.....	\$ 40.00	26.76

* PAIN0169-005 01/01/2021

ALAMEDA CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN
MATEO, SANTA CLARA & SANTA CRUZ COUNTIES

	Rates	Fringes
GLAZIER.....	\$ 53.07	31.15

PAIN0294-004 01/01/2021

FRESNO, KINGS AND MADERA COUNTIES

	Rates	Fringes
PAINTER		
Brush, Roller.....	\$ 31.36	20.33
Drywall Finisher/Taper.....	\$ 40.10	25.00

FOOTNOTE:

Spray Painters & Paperhangers receive \$1.00 additional per hour. Painters doing Drywall Patching receive \$1.25 additional per hour. Lead Abaters & Sandblasters receive \$1.50 additional per hour. High Time - over 30 feet (does not include work from a lift) \$0.75 per hour additional.

PAIN0294-005 01/01/2021

FRESNO, KINGS & MADERA

	Rates	Fringes
SOFT FLOOR LAYER.....	\$ 34.55	21.67

* PAIN0767-001 01/01/2021

CALAVERAS, SAN JOAQUIN, STANISLAUS AND TUOLUMNE COUNTIES:

	Rates	Fringes
GLAZIER.....	\$ 41.51	31.36

PAID HOLIDAYS: New Year's Day, Martin Luther King, Jr. Day, President's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, and Christmas Day.

Employee required to wear a body harness shall receive \$1.50 per hour above the basic hourly rate at any elevation.

PAIN1176-001 07/01/2020

HIGHWAY IMPROVEMENT

	Rates	Fringes
Parking Lot Striping/Highway		
Marking:		
GROUP 1.....	\$ 38.48	16.88
GROUP 2.....	\$ 32.71	16.88

GROUP 3.....\$ 33.09 16.88

CLASSIFICATIONS

GROUP 1: Striper: Layout and application of painted traffic stripes and marking; hot thermo plastic; tape, traffic stripes and markings

GROUP 2: Gamecourt & Playground Installer

GROUP 3: Protective Coating, Pavement Sealing

PAIN1237-003 06/01/2020

CALAVERAS; SAN JOAQUIN COUNTIES; STANISLAUS AND TUOLUMNE COUNTIES:

	Rates	Fringes
SOFT FLOOR LAYER.....	\$ 39.61	22.59

PLAS0066-002 07/01/2019

ALAMEDA, CONTRA COSTA, SAN MATEO AND SAN FRANCISCO COUNTIES:

	Rates	Fringes
PLASTERER.....	\$ 42.41	30.73

PLAS0300-001 07/01/2018

	Rates	Fringes
PLASTERER		
AREA 188: Fresno.....	\$ 32.70	31.68
AREA 224: San Benito, Santa Clara, Santa Cruz.....	\$ 32.88	31.68
AREA 295: Calaveras & San Joaquin Counties.....	\$ 32.70	31.68
AREA 337: Monterey County..	\$ 32.88	31.68
AREA 429: Mariposa, Merced, Stanislaus, Tuolumne Counties.....	\$ 32.70	31.68

PLAS0300-005 07/01/2017

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER...	\$ 33.49	23.67

PLUM0038-001 07/01/2020

SAN FRANCISCO COUNTY

	Rates	Fringes
PLUMBER (Plumber, Steamfitter, Refrigeration Fitter).....	\$ 75.30	46.27

PLUM0038-005 07/01/2019

SAN FRANCISCO COUNTY

	Rates	Fringes
Landscape/Irrigation Fitter (Underground/Utility Fitter)....	\$ 63.04	31.48

PLUM0062-001 01/01/2021

MONTEREY AND SANTA CRUZ COUNTIES

	Rates	Fringes
PLUMBER & STEAMFITTER.....	\$ 45.50	37.05

PLUM0159-001 07/01/2019

CONTRA COSTA COUNTY

	Rates	Fringes
Plumber and steamfitter		
(1) Refrigeration.....	\$ 56.93	41.04
(2) All other work.....	\$ 57.82	41.04

PLUM0246-001 01/01/2021

FRESNO, KINGS & MADERA COUNTIES

	Rates	Fringes
PLUMBER & STEAMFITTER.....	\$ 43.40	35.64

 PLUM0246-004 01/01/2017

FRESNO, MERCED & SAN JOAQUIN COUNIES

	Rates	Fringes
PLUMBER (PIPE TRADESMAN).....	\$ 13.00	10.74

PIPE TRADESMAN SCOPE OF WORK:

Installation of corrugated metal piping for drainage, as well as installation of corrugated metal piping for culverts in connection with storm sewers and drains; Grouting, dry packing and diapering of joints, holes or chases including paving over joints, in piping; Temporary piping for dirt work for building site preparation; Operating jack hammers, pavement breakers, chipping guns, concrete saws and spades to cut holes, chases and channels for piping systems; Digging, grading, backfilling and ground preparation for all types of pipe to all points of the jobsite; Ground preparation including ground leveling, layout and planting of shrubbery, trees and ground cover, including watering, mowing, edging, pruning and fertilizing, the breaking of concrete, digging, backfilling and tamping for the preparation and completion of all work in connection with lawn sprinkler and landscaping; Loading, unloading and distributing materials at jobsite; Putting away materials in storage bins in jobsite secure storage area; Demolition of piping and fixtures for remodeling and additions; Setting up and tearing down work benches, ladders and job shacks; Clean-up and sweeping of jobsite; Pipe wrapping and waterproofing where tar or similar material is applied for protection of buried piping; Flagman

 PLUM0342-001 07/01/2020

ALAMEDA & CONTRA COSTA COUNTIES

	Rates	Fringes
PIPEFITTER		
CONTRA COSTA COUNTY.....	\$ 67.75	42.50
PLUMBER, PIPEFITTER, STEAMFITTER		
ALAMEDA COUNTY.....	\$ 67.75	42.50

 PLUM0355-004 07/01/2020

ALAMEDA, CALAVERAS, CONTRA COSTA, FRESNO, KINGS, MADERA,
MARIPOSA, MERCED, MONTEREY, SAN BENITO, SAN JOAQUIN, SAN MATEO,
SANTA CLARA, SANTA CRUZ, STANISLAUS, AND TUOLUMNE COUNTIES:

	Rates	Fringes
Underground Utility Worker /Landscape Fitter.....	\$ 29.90	16.30

PLUM0393-001 07/01/2020

SAN BENITO AND SANTA CLARA COUNTIES

	Rates	Fringes
PLUMBER/PIPEFITTER.....	\$ 66.66	44.83

PLUM0442-001 07/01/2020

CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS & TUOLUMNE
COUNTIES

	Rates	Fringes
PLUMBER & STEAMFITTER.....	\$ 45.50	31.89

PLUM0467-001 07/01/2020

SAN MATEO COUNTY

	Rates	Fringes
Plumber/Pipefitter/Steamfitter...	\$ 70.00	37.86

ROOF0027-002 01/01/2021

FRESNO, KINGS, AND MADERA COUNTIES

	Rates	Fringes
ROOFER.....	\$ 32.01	14.61

FOOTNOTE: Work with pitch, pitch base of pitch impregnated
products or any material containing coal tar pitch, on any
building old or new, where both asphalt and pitchers are

used in the application of a built-up roof or tear off:
\$2.00 per hour additional.

ROOF0040-002 08/01/2020

SAN FRANCISCO & SAN MATEO COUNTIES:

	Rates	Fringes
ROOFER.....	\$ 44.38	19.69

ROOF0081-001 08/01/2020

ALAMEDA AND CONTRA COSTA COUNTIES:

	Rates	Fringes
Roofer.....	\$ 44.62	19.36

ROOF0081-004 08/01/2020

CALAVERAS, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS AND
TUOLUMNE COUNTIES:

	Rates	Fringes
ROOFER.....	\$ 39.73	19.11

ROOF0095-002 08/01/2020

MONTEREY, SAN BENITO, SANTA CLARA, AND SANTA CRUZ COUNTIES:

	Rates	Fringes
ROOFER		
Journeyman.....	\$ 46.54	20.69
Kettle person (2 kettles); Bitumastic, Enameler, Coal Tar, Pitch and Mastic worker.....	\$ 48.54	20.69

SFCA0483-001 01/01/2021

ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO AND SANTA CLARA
COUNTIES:

	Rates	Fringes
SPRINKLER FITTER (FIRE).....	\$ 67.99	32.85

SFCA0669-011 04/01/2021

CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, MONTEREY,
SAN BENITO, SAN JOAQUIN, SANTA CRUZ, STANISLAUS AND TUOLUMNE
COUNTIES:

	Rates	Fringes
SPRINKLER FITTER.....	\$ 40.36	26.15

SHEE0104-001 07/01/2020

AREA 1: ALAMEDA, CONTRA COSTA, SAN FRANCISCO, SAN MATEO, SANTA
CLARA

AREA 2: MONTEREY & SAN BENITO

AREA 3: SANTA CRUZ

	Rates	Fringes
SHEET METAL WORKER		
AREA 1:		
Mechanical Contracts		
under \$200,000.....	\$ 55.92	45.29
All Other Work.....	\$ 64.06	46.83
AREA 2.....	\$ 52.90	36.44
AREA 3.....	\$ 55.16	34.18

SHEE0104-003 07/01/2020

CALAVERAS AND SAN JOAQUIN COUNTIES:

	Rates	Fringes
SHEET METAL WORKER.....	\$ 43.50	37.42

SHEE0104-005 07/01/2020

MARIPOSA, MERCED, STANISLAUS AND TUOLUMNE COUNTIES:

	Rates	Fringes
SHEET METAL WORKER (Excluding metal deck and siding).....	\$ 40.38	43.47

SHEE0104-007 07/01/2020

FRESNO, KINGS, AND MADERA COUNTIES:

	Rates	Fringes
SHEET METAL WORKER.....	\$ 42.53	39.64

SHEE0104-015 07/01/2020

ALAMEDA, CONTRA COSTA, MONTEREY, SAN BENITO, SAN FRANCISCO, SAN MATEO, SANTA CLARA AND SANTA CRUZ COUNTIES:

	Rates	Fringes
SHEET METAL WORKER (Metal Decking and Siding only).....	\$ 44.45	35.55

SHEE0104-018 07/01/2020

CALAVERAS, FRESNO, KINGS, MADERA, MARIPOSA, MERCED, SAN JOAQUIN, STANISLAUS AND TUOLUMNE COUNTIES:

	Rates	Fringes
Sheet metal worker (Metal decking and siding only).....	\$ 44.45	35.55

TEAM0094-001 07/01/2019

	Rates	Fringes
Truck drivers:		
GROUP 1.....	\$ 32.80	29.19
GROUP 2.....	\$ 33.10	29.19
GROUP 3.....	\$ 33.40	29.19
GROUP 4.....	\$ 33.75	29.19
GROUP 5.....	\$ 34.10	29.19

FOOTNOTES:

Articulated dump truck; Bulk cement spreader (with or without

auger); Dumpcrete truck; Skid truck (debris box); Dry pre-batch concrete mix trucks; Dumpster or similar type; Slurry truck: Use dump truck yardage rate.

Heater planer; Asphalt burner; Scarifier burner; Industrial lift truck (mechanical tailgate); Utility and clean-up truck: Use appropriate rate for the power unit or the equipment utilized.

TRUCK DRIVER CLASSIFICATIONS

GROUP 1: Dump trucks, under 6 yds.; Single unit flat rack (2-axle unit); Nipper truck (when flat rack truck is used appropriate flat rack shall apply); Concrete pump truck (when flat rack truck is used appropriate flat rack shall apply); Concrete pump machine; Fork lift and lift jitneys; Fuel and/or grease truck driver or fuel person; Snow buggy; Steam cleaning; Bus or personhaul driver; Escort or pilot car driver; Pickup truck; Teamster oiler/greaser and/or serviceperson; Hook tender (including loading and unloading); Team driver; Tool room attendant (refineries)

GROUP 2: Dump trucks, 6 yds. and under 8 yds.; Transit mixers, through 10 yds.; Water trucks, under 7,000 gals.; Jetting trucks, under 7,000 gals.; Single-unit flat rack (3-axle unit); Highbed heavy duty transport; Scissor truck; Rubber-tired muck car (not self-loaded); Rubber-tired truck jumbo; Winch truck and "A" frame drivers; Combination winch truck with hoist; Road oil truck or bootperson; Buggymobile; Ross, Hyster and similar straddle carriers; Small rubber-tired tractor

GROUP 3: Dump trucks, 8 yds. and including 24 yds.; Transit mixers, over 10 yds.; Water trucks, 7,000 gals. and over; Jetting trucks, 7,000 gals. and over; Vacuum trucks under 7500 gals. Trucks towing tilt bed or flat bed pull trailers; Lowbed heavy duty transport; Heavy duty transport tiller person; Self-propelled street sweeper with self-contained refuse bin; Boom truck - hydro-lift or Swedish type extension or retracting crane; P.B. or similar type self-loading truck; Tire repairperson; Combination bootperson and road oiler; Dry distribution truck (A bootperson when employed on such equipment, shall receive the rate specified for the classification of road oil trucks or bootperson); Ammonia nitrate distributor, driver and mixer; Snow Go and/or plow

GROUP 4: Dump trucks, over 25 yds. and under 65 yds.; Water

pulls - DW 10's, 20's, 21's and other similar equipment when pulling Aqua/pak or water tank trailers; Helicopter pilots (when transporting men and materials); Lowbedk Heavy Duty Transport up to including 7 axles; DW10's, 20's, 21's and other similar Cat type, Terra Cobra, LeTourneau Pulls, Tournorocker, Euclid and similar type equipment when pulling fuel and/or grease tank trailers or other miscellaneous trailers; Vacuum Trucks 7500 gals and over and truck repairman

GROUP 5: Dump trucks, 65 yds. and over; Holland hauler; Low bed Heavy Duty Transport over 7 axles

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification

and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
 Wage and Hour Division
 U.S. Department of Labor
 200 Constitution Avenue, N.W.

Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

=====

END OF GENERAL DECISION"

Appendix E of the Title VI Assurances

(US DOT Order 1050.2A)

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following nondiscrimination statutes and authorities; including but not limited to:

Pertinent Nondiscrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 U.S.C. § 4 71, Section 4 7123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, subrecipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;

- The Federal Aviation Administration's Nondiscrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

Appendix A

County of San Mateo Waste Management Plan Form

Waste Management Daily Transport Report



County of San Mateo WASTE MANAGEMENT PLAN

Case/group number(s):
BLD _____ - _____

Project address:
Street: _____

City: _____

Zip Code: _____

Green Halo number(s):

WMP required because project is a:

- Residential Demolition
- Nonresidential New Construction
- Addition

Submit to:
County of San Mateo
Department of Public Works
555 County Center, 5th Floor
Redwood City, CA 94063

Information and support: 888-442-2666
www.smcsustainability.org/waste-reduction/construction-demolition

Section One: Permit Application

This Waste Management Plan (WMP) must be completed, submitted for review, and approved to obtain a permit. Separate WMPs are required for demolition and construction at the same site unless the Building Department requires only one permit. Need for a WMP is at the discretion of the Building Official or designee.

Applicant's Name: _____ Owner's Name: _____

Phone Number: _____ Email: _____

Applicant is (please check one): Owner Architect Builder Owner/Builder Other _____

Contractor (if applicable): _____ Contact Phone Number: _____

Project Description: _____

Project Square Footage: _____ Estimated Completion Date: _____

Waste Management Requirements:

You are required to recycle or re-use all inert solids (asphalt, brick, concrete, dirt, fines, rock, sand, and stone) and 65% of all construction and demolition debris.

I understand that I am required by San Mateo County Building Regulations Section 9210 - Adoption Of 2016 California Green Building Standards Code (Building Regulations) to salvage, reuse, or recycle **all inert solids** (asphalt, brick, concrete, dirt, fines, rock, sand, and stone) and **a minimum of 65%** of all construction and demolition debris (C&D). _____ (Initial)

I understand that failure to meet the requirements of the Building Regulations shall constitute a misdemeanor, and shall be punishable by imprisonment in the county jail for up to 6 months and/or a fine of up to \$1,000, calculated as a percentage of the required 65% diversion of C&D debris, and that the fine must be paid as a condition of final approval. _____ (Initial)

At the completion of this project, or more frequently if required, all weight tags or other equivalent documentation from salvage, recycling and waste facilities will be provided and I understand that I may not be issued my final inspection unless all original receipts and documentation are submitted to the County of San Mateo Department of Public Works. _____ (Initial)

Recycling and waste facilities ask for the correct origin of the materials generated as they come through the scale house. These tons are reported to the State of California. I understand that I need to advise my debris box company, waste haulers, and my drivers that the materials generated on this project originated in Unincorporated County of San Mateo. _____ (Initial)

1) Deconstruction/salvage/reuse:

What materials will be salvaged/reused? _____

Deconstruction or salvage company (if applicable): _____

What materials will be reused on site? _____

How will this be documented? _____

2) Material transportation:

Will you be using a hauling company, debris box company or hauling the material yourself?

Hauler Debris Box Self-haul

If using a hauling or debris box company, which company? _____

Have they been notified that the diversion of 65% mixed debris and all inert solids is required? Yes No

3) Waste management plan:

Check the materials you anticipate generating and fill in the facilities that you plan to use.

Category	Material	√	Reuse, Recycling or Disposal Facility
Mixed C&D	Mixed Debris		
Inerts	Asphalt		
	Bricks		
	Concrete		
	Dirt		
	Other inert solids		
Source Separated	Cardboard		
	Metals		
	Wood		
	Roofing		
	Carpet		
	Drywall		
	Yard trimmings		
	Other		
Disposal	Waste		

The undersigned hereby agrees to comply with the Waste Management Plan as submitted and is the owner or authorized agent to sign for the owner of this project.

Applicant Signature _____ **Date** _____

County Approval: <input type="checkbox"/> Approved <input type="checkbox"/> Approved with comments <input type="checkbox"/> Denied All receipts, weight tags and documentation for salvage, recycling, and disposal must be submitted: <input type="checkbox"/> On completion of project <input type="checkbox"/> Other _____ Office of Sustainability Approval: _____ Date: _____



County of San Mateo

WASTE MANAGEMENT PLAN

Case/Group Number(s):
 BLD _____ - _____
 Project Address:
 Street: _____
 City: _____

Section Two: Final Report Approval

Please complete, submit, and get this section approved by the Department of Public Works, prior to obtaining final approval by the Department of Public Works no later than 30 days after completion of the demolition or construction project. Please provide weight of materials in **tons**. If needed, please use the conversion table on the next page to convert cubic yards to tons.

This section must be completed and signed, and all receipts or other supporting documentation must be attached in order to receive final project approval.

Category	Date	Material/items	Name of facility debris was hauled to	Weight (Tons)	Volume (CU. YD.)
Mixed C&D					
Salvage/Reuse					
Inerts Asphalt, bricks, concrete, dirt, rock, sand, soil, stone					
Source Separated Cardboard, wood, metal, sheetrock, wire, carpet, yard trimmings					
Disposal (Waste)					

- All receipts or equivalent documentation for salvage, recycling, and disposal are hereby attached.
- This project has recycled all of the inert solids and at least 65% of all debris generated.

Applicant Signature _____ **Date** _____

County Approval: Approved Approved with Comments Fine Payment Required
 Comments: _____

Fine Calculation: $1 - (\text{C\&D Diversion \% Achieved} \text{ ____} / 65\%) \times \$1000 = \$$ _____
 Office of Sustainability Approval: _____ Date: _____



County of San Mateo

WASTE MANAGEMENT PLAN

Cubic Yards to Tons Conversion Table

Category	Material	Cubic Yards	Pounds	Tons
Mixed C&D	Mixed load C&D	1	500	0.25
Inerts	Asphalt	1	1380	0.69
	Bricks	1	3000	1.5
	Concrete	1	1860	0.93
	Dirt	1	2000	1
	Other inert solids	1	1240	0.62
Source Separated	Cardboard	1	100	0.05
	Metals	1	900	0.45
	Wood	1	300	0.15
	Asphalt roofing	1	1188	0.59
	Carpet	1	600	0.3
	Drywall	1	400	0.2
	Green waste	1	300	0.15
	Gravel	1	2600	1.3
Disposal	Waste	1	300	0.15

WASTE MANAGEMENT DAILY TRANSPORT REPORT

Date : Day : Multiple Pages : Yes ___ No ___
Contractor Representative :

Project : County Inspector :

	Transport Vehicle Type	Vehicle License/I.D.	Load Destination	
			Inert Material	Non-Inert Material
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				

Note : Inert material shall be as defined in the Construction Waste Management Section of these specifications.

Comments :

Appendix B

Sample “Payment Bond” Form

Sample “Performance Bond” Form

PAYMENT BOND

KNOW ALL MEN BY THESE PRESENTS:

That **WHEREAS**, the County of San Mateo hereinafter designated as the "County," has awarded to _____, hereinafter designated
(Contractor's Name)
as the "Principal," a contract dated _____, hereinafter designated
(Contract Award Date)
as the "Contract," which Contract is by this reference made a part hereof, for the work described as _____.
(Project Name, Location & Number)

And WHEREAS, pursuant to law, the Principal is required, before entering upon the performance of the work, to file a good and sufficient bond with the body by whom the Contract is awarded to secure the claims to which reference is made in Sections 9550 to 9566 and 9100 to 9364 both inclusive, of the Civil Code of California.

NOW THEREFORE, THESE PRESENTS WITNESSETH:

That the said Principal and the undersigned, _____
(Surety's Name)
as corporate Surety, are held and firmly bound unto all laborers, material men and other persons referred to in said statutes in the sum of _____ Dollars (\$ _____)
lawful money of the United States, for the payment of which sum well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors, or assigns, jointly and severally, by these presents.

The condition of this obligation is that if the above bonded Principal, contractor, person, company or corporation, or his or its sub-contractor, fails to pay any claimant name in Section 9100 of the Civil Code of the State of California, or amounts due under the Unemployment Insurance Code, with respect to work or labor performed by any such claimant, that the Surety on this bond will pay the same, in an amount not exceeding the aggregate sum specified in this bond, and also, in case suit is brought upon this bond, a reasonable attorney's fee, which shall be awarded by the court to the prevailing party in said suit, and attorney's fees to be taxed as costs in said suit.

It is hereby expressly stipulated and agreed that this bond shall inure to the benefit of any and all persons, companies and corporations entitled to file claims under Section 9100 to 9364 of the Civil Code, so as to give a right of action to them or

their assigns in any suit brought upon this bond.

This bond is executed and filed to comply with the provisions of the act of Legislature of the State of California as designated in the Civil Code, Sections 9550-9566 inclusive, and all amendments thereto.

Should the condition of this bond be fully performed, then this obligation shall become null and void, otherwise it shall be and remain in full force and effect.

And the said Surety, for value received, hereby stipulates and agrees that no change will be made which increases the total Contract price more than twenty percent (20%) in excess of the original Contract price without notice to the Surety, then, this obligation to be void, otherwise to remain in full force and virtue.

Correspondence relating to this bond shall be sent to the Surety at the address set forth below.

IN WITNESS WHEREOF, this instrument has been duly executed by the Principal and Surety this _____ day of _____, 20____.

Principal

Surety

Signature

Signature

Printed Name

Printed Name

Address for Notices:

NOTE: Notary acknowledgement for Surety and Surety's Power of Attorney must be attached.

PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS:

That **WHEREAS**, the County of San Mateo hereinafter designated as the "County," has awarded to _____, hereinafter designated
(Contractor's Name)
as the "Principal," a contract dated _____, hereinafter designated
(Contract Award Date)
as the "Contract," which Contract is by this reference made a part hereof, for the work described as _____.
(Project Name, Location & Number)

And WHEREAS, Principal is required to furnish a bond in connection with the Contract, guaranteeing the faithful performance thereof.

NOW THEREFORE, THESE PRESENTS WITNESSETH:

That the said Principal and the undersigned, _____,
(Surety's Name)
as corporate Surety, are held and firmly bound unto the County in the sum of _____ Dollars (\$ _____)

lawful money of the United States, for the payment of which sum well and truly to be made, we bind ourselves, our heirs, executors, administrators, successors, or assigns, jointly and severally, firmly by these presents.

The condition of this obligation is such that if the above bonded Principal shall well and truly perform and fulfill all the undertakings, covenants, terms, conditions, and agreements of said Contract during the original term of said Contract and any extensions thereof that may be granted by the County, with or without notice to the Surety, and during the life of any guarantee required under the Contract, and shall also well and truly perform and fulfill all the undertakings, covenants, terms, conditions and agreements of any and all duly authorized modifications of said Contract that may hereafter be made, except that no change will be made which increases the total

Contract price more than twenty percent (20%) in excess of the original Contract price without notice to the Surety, then, this obligation to be void, otherwise to remain in full force and virtue.

Correspondence relating to this bond shall be sent to the Surety at the address set forth below.

IN WITNESS WHEREOF, this instrument has been duly executed by the Principal and Surety this _____ day of _____, 20____.

Principal

Surety

Signature

Signature

Printed Name

Printed Name

Address for Notices:

NOTE: Notary acknowledgement for Surety and Surety's Power of Attorney must be attached.

Appendix C

Daily Personnel and Equipment Log

DAILY PERSONNEL AND EQUIPMENT LOG

Using as many copies of this form necessary, the Contractor shall provide the Engineer with a list of all personnel and their title and, if applicable, equipment said employee is operating. This information is required of the Prime and their Subcontractors.

This form, if used in lieu of Contractor’s Daily Dispatch Report, shall be submitted to the Engineer by the start of the first working day subsequent to the performance of the work, or Contractor may incur task-specific liquidated damages in the amount of \$500 per day for every day hence until submittal is made. Reference is made to Section 7-4a, “Payroll Records,” of the Project Special Provisions.

Date: _____ Project No.: YY003

Project: Gazos Creek Road Repair Project

Contractor: _____

Is this log for Subcontractor? Yes No

If yes, Name of Subcontractor: _____

Personnel		Equipment			
Name	Title/ Trade	No.	Type	Make	Model

Notes:

Appendix D

**Public Contract Code
Sections 9204 and 20104 et seq.**

Public Contract Code Section 9204 et seq.

9204.

(a) The Legislature finds and declares that it is in the best interests of the state and its citizens to ensure that all construction business performed on a public works project in the state that is complete and not in dispute is paid in full and in a timely manner.

(b) Notwithstanding any other law, including, but not limited to, Article 7.1 (commencing with Section 10240) of Chapter 1 of Part 2, Chapter 10 (commencing with Section 19100) of Part 2, and Article 1.5 (commencing with Section 20104) of Chapter 1 of Part 3, this section shall apply to any claim by a contractor in connection with a public works project.

(c) For purposes of this section:

(1) "Claim" means a separate demand by a contractor sent by registered mail or certified mail with return receipt requested, for one or more of the following:

(A) A time extension, including, without limitation, for relief from damages or penalties for delay assessed by a public entity under a contract for a public works project.

(B) Payment by the public entity of money or damages arising from work done by, or on behalf of, the contractor pursuant to the contract for a public works project and payment for which is not otherwise expressly provided or to which the claimant is not otherwise entitled.

(C) Payment of an amount that is disputed by the public entity.

(2) "Contractor" means any type of contractor within the meaning of Chapter 9 (commencing with Section 7000) of Division 3 of the Business and Professions Code who has entered into a direct contract with a public entity for a public works project.

(3) (A) "Public entity" means, without limitation, except as provided in subparagraph (B), a state agency, department, office, division, bureau, board, or commission, the California State University, the University of California, a city, including a charter city, county, including a charter county, city and county, including a charter city and county, district, special district, public authority, political subdivision, public corporation, or nonprofit transit corporation wholly owned by a public agency and formed to carry out the purposes of the public agency.

(B) "Public entity" shall not include the following:

(i) The Department of Water Resources as to any project under the jurisdiction of that department.

(ii) The Department of Transportation as to any project under the jurisdiction of that department.

(iii) The Department of Parks and Recreation as to any project under the jurisdiction of that department.

(iv) The Department of Corrections and Rehabilitation with respect to any project under its jurisdiction pursuant to Chapter 11 (commencing with Section 7000) of Title 7 of Part 3 of the Penal Code.

(v) The Military Department as to any project under the jurisdiction of that department.

(vi) The Department of General Services as to all other projects.

(vii) The High-Speed Rail Authority.

(4) "Public works project" means the erection, construction, alteration, repair, or improvement of any public structure, building, road, or other public improvement of any kind.

(5) "Subcontractor" means any type of contractor within the meaning of Chapter 9 (commencing with Section 7000) of Division 3 of the Business and Professions Code who either is in direct contract with a contractor or is a lower tier subcontractor.

(d) (1) (A) Upon receipt of a claim pursuant to this section, the public entity to which the claim applies shall conduct a reasonable review of the claim and, within a period not to

exceed 45 days, shall provide the claimant a written statement identifying what portion of the claim is disputed and what portion is undisputed. Upon receipt of a claim, a public entity and a contractor may, by mutual agreement, extend the time period provided in this subdivision.

(B) The claimant shall furnish reasonable documentation to support the claim.

(C) If the public entity needs approval from its governing body to provide the claimant a written statement identifying the disputed portion and the undisputed portion of the claim, and the governing body does not meet within the 45 days or within the mutually agreed to extension of time following receipt of a claim sent by registered mail or certified mail, return receipt requested, the public entity shall have up to three days following the next duly publicly noticed meeting of the governing body after the 45-day period, or extension, expires to provide the claimant a written statement identifying the disputed portion and the undisputed portion.

(D) Any payment due on an undisputed portion of the claim shall be processed and made within 60 days after the public entity issues its written statement. If the public entity fails to issue a written statement, paragraph (3) shall apply.

(2) (A) If the claimant disputes the public entity's written response, or if the public entity fails to respond to a claim issued pursuant to this section within the time prescribed, the claimant may demand in writing an informal conference to meet and confer for settlement of the issues in dispute. Upon receipt of a demand in writing sent by registered mail or certified mail, return receipt requested, the public entity shall schedule a meet and confer conference within 30 days for settlement of the dispute.

(B) Within 10 business days following the conclusion of the meet and confer conference, if the claim or any portion of the claim remains in dispute, the public entity shall provide the claimant a written statement identifying the portion of the claim that remains in dispute and the portion that is undisputed. Any payment due on an undisputed portion of the claim shall be processed and made within 60 days after the public entity issues its written statement. Any disputed portion of the claim, as identified by the contractor in writing, shall be submitted to nonbinding mediation, with the public entity and the claimant sharing the associated costs equally. The public entity and claimant shall mutually agree to a mediator within 10 business days after the disputed portion of the claim has been identified in writing. If the parties cannot agree upon a mediator, each party shall select a mediator and those mediators shall select a qualified neutral third party to mediate with regard to the disputed portion of the claim. Each party shall bear the fees and costs charged by its respective mediator in connection with the selection of the neutral mediator. If mediation is unsuccessful, the parts of the claim remaining in dispute shall be subject to applicable procedures outside this section.

(C) For purposes of this section, mediation includes any nonbinding process, including, but not limited to, neutral evaluation or a dispute review board, in which an independent third party or board assists the parties in dispute resolution through negotiation or by issuance of an evaluation. Any mediation utilized shall conform to the timeframes in this section.

(D) Unless otherwise agreed to by the public entity and the contractor in writing, the mediation conducted pursuant to this section shall excuse any further obligation under Section 20104.4 to mediate after litigation has been commenced.

(E) This section does not preclude a public entity from requiring arbitration of disputes under private arbitration or the Public Works Contract Arbitration Program, if mediation under this section does not resolve the parties' dispute.

(3) Failure by the public entity to respond to a claim from a contractor within the time periods described in this subdivision or to otherwise meet the time requirements of this section shall result in the claim being deemed rejected in its entirety. A claim that is denied by reason of the public entity's failure to have responded to a claim, or its failure

to otherwise meet the time requirements of this section, shall not constitute an adverse finding with regard to the merits of the claim or the responsibility or qualifications of the claimant.

(4) Amounts not paid in a timely manner as required by this section shall bear interest at 7 percent per annum.

(5) If a subcontractor or a lower tier subcontractor lacks legal standing to assert a claim against a public entity because privity of contract does not exist, the contractor may present to the public entity a claim on behalf of a subcontractor or lower tier subcontractor. A subcontractor may request in writing, either on his or her own behalf or on behalf of a lower tier subcontractor, that the contractor present a claim for work which was performed by the subcontractor or by a lower tier subcontractor on behalf of the subcontractor. The subcontractor requesting that the claim be presented to the public entity shall furnish reasonable documentation to support the claim. Within 45 days of receipt of this written request, the contractor shall notify the subcontractor in writing as to whether the contractor presented the claim to the public entity and, if the original contractor did not present the claim, provide the subcontractor with a statement of the reasons for not having done so.

(e) The text of this section or a summary of it shall be set forth in the plans or specifications for any public works project that may give rise to a claim under this section.

(f) A waiver of the rights granted by this section is void and contrary to public policy, provided, however, that (1) upon receipt of a claim, the parties may mutually agree to waive, in writing, mediation and proceed directly to the commencement of a civil action or binding arbitration, as applicable; and (2) a public entity may prescribe reasonable change order, claim, and dispute resolution procedures and requirements in addition to the provisions of this section, so long as the contractual provisions do not conflict with or otherwise impair the timeframes and procedures set forth in this section.

(g) This section applies to contracts entered into on or after January 1, 2017.

(h) Nothing in this section shall impose liability upon a public entity that makes loans or grants available through a competitive application process, for the failure of an awardee to meet its contractual obligations.

(i) This section shall remain in effect only until January 1, 2020, and as of that date is repealed, unless a later enacted statute, that is enacted before January 1, 2020, deletes or extends that date.

SEC. 2.

The Legislature finds and declares that it is of statewide concern to require a charter city, charter county, or charter city and county to follow a prescribed claims resolution process to ensure there are uniform and equitable procurement practices.

SEC. 3.

If the Commission on State Mandates determines that this act contains costs mandated by the state, reimbursement to local agencies and school districts for those costs shall be made pursuant to Part 7 (commencing with Section 17500) of Division 4 of Title 2 of the Government Code.

Public Contract Code Section 20104 et seq.

20104.

(a) (1) This article applies to all public works claims of three hundred seventy-five thousand dollars (\$375,000) or less which arise between a contractor and a local agency.

(2) This article shall not apply to any claims resulting from a contract between a

contractor and a public agency when the public agency has elected to resolve any disputes pursuant to Article 7.1 (commencing with Section 10240) of Chapter 1 of Part 2.

(b) (1) "Public work" means "public works contract" as defined in Section 1101 but does not include any work or improvement contracted for by the state or the Regents of the University of California.

(2) "Claim" means a separate demand by the contractor for (A) a time extension, (B) payment of money or damages arising from work done by, or on behalf of, the contractor pursuant to the contract for a public work and payment of which is not otherwise expressly provided for or the claimant is not otherwise entitled to, or (C) an amount the payment of which is disputed by the local agency.

(c) The provisions of this article or a summary thereof shall be set forth in the plans or specifications for any work which may give rise to a claim under this article.

(d) This article applies only to contracts entered into on or after January 1, 1991.

(Amended by Stats. 2010, Ch. 697, Sec. 47. Effective January 1, 2011. Operative July 1, 2012, by Sec. 105 of Ch. 697.)

20104.2.

For any claim subject to this article, the following requirements apply:

(a) The claim shall be in writing and include the documents necessary to substantiate the claim. Claims must be filed on or before the date of final payment. Nothing in this subdivision is intended to extend the time limit or supersede notice requirements otherwise provided by contract for the filing of claims.

(b) (1) For claims of less than fifty thousand dollars (\$50,000), the local agency shall respond in writing to any written claim within 45 days of receipt of the claim, or may request, in writing, within 30 days of receipt of the claim, any additional documentation supporting the claim or relating to defenses to the claim the local agency may have against the claimant.

(2) If additional information is thereafter required, it shall be requested and provided pursuant to this subdivision, upon mutual agreement of the local agency and the claimant.

(3) The local agency's written response to the claim, as further documented, shall be submitted to the claimant within 15 days after receipt of the further documentation or within a period of time no greater than that taken by the claimant in producing the additional information, whichever is greater.

(c) (1) For claims of over fifty thousand dollars (\$50,000) and less than or equal to three hundred seventy-five thousand dollars (\$375,000), the local agency shall respond in writing to all written claims within 60 days of receipt of the claim, or may request, in writing, within 30 days of receipt of the claim, any additional documentation supporting the claim or relating to defenses to the claim the local agency may have against the claimant.

(2) If additional information is thereafter required, it shall be requested and provided pursuant to this subdivision, upon mutual agreement of the local agency and the claimant.

(3) The local agency's written response to the claim, as further documented, shall be submitted to the claimant within 30 days after receipt of the further documentation, or within a period of time no greater than that taken by the claimant in producing the additional information or requested documentation, whichever is greater.

(d) If the claimant disputes the local agency's written response, or the local agency fails to respond within the time prescribed, the claimant may so notify the local agency, in writing, either within 15 days of receipt of the local agency's response or within 15 days

of the local agency's failure to respond within the time prescribed, respectively, and demand an informal conference to meet and confer for settlement of the issues in dispute. Upon a demand, the local agency shall schedule a meet and confer conference within 30 days for settlement of the dispute.

(e) Following the meet and confer conference, if the claim or any portion remains in dispute, the claimant may file a claim as provided in Chapter 1 (commencing with Section 900) and Chapter 2 (commencing with Section 910) of Part 3 of Division 3.6 of Title 1 of the Government Code. For purposes of those provisions, the running of the period of time within which a claim must be filed shall be tolled from the time the claimant submits his or her written claim pursuant to subdivision (a) until the time that claim is denied as a result of the meet and confer process, including any period of time utilized by the meet and confer process.

(f) This article does not apply to tort claims and nothing in this article is intended nor shall be construed to change the time periods for filing tort claims or actions specified by Chapter 1 (commencing with Section 900) and Chapter 2 (commencing with Section 910) of Part 3 of Division 3.6 of Title 1 of the Government Code.

(Added by Stats. 1994, Ch. 726, Sec. 22. Effective September 22, 1994.)

20104.4.

The following procedures are established for all civil actions filed to resolve claims subject to this article:

(a) Within 60 days, but no earlier than 30 days, following the filing or responsive pleadings, the court shall submit the matter to nonbinding mediation unless waived by mutual stipulation of both parties. The mediation process shall provide for the selection within 15 days by both parties of a disinterested third person as mediator, shall be commenced within 30 days of the submittal, and shall be concluded within 15 days from the commencement of the mediation unless a time requirement is extended upon a good cause showing to the court or by stipulation of both parties. If the parties fail to select a mediator within the 15-day period, any party may petition the court to appoint the mediator.

(b) (1) If the matter remains in dispute, the case shall be submitted to judicial arbitration pursuant to Chapter 2.5 (commencing with Section 1141.10) of Title 3 of Part 3 of the Code of Civil Procedure, notwithstanding Section 1141.11 of that code. The Civil Discovery Act (Title 4 (commencing with Section 2016.010) of Part 4 of the Code of Civil Procedure) shall apply to any proceeding brought under this subdivision consistent with the rules pertaining to judicial arbitration.

(2) Notwithstanding any other provision of law, upon stipulation of the parties, arbitrators appointed for purposes of this article shall be experienced in construction law, and, upon stipulation of the parties, mediators and arbitrators shall be paid necessary and reasonable hourly rates of pay not to exceed their customary rate, and such fees and expenses shall be paid equally by the parties, except in the case of arbitration where the arbitrator, for good cause, determines a different division. In no event shall these fees or expenses be paid by state or county funds.

(3) In addition to Chapter 2.5 (commencing with Section 1141.10) of Title 3 of Part 3 of the Code of Civil Procedure, any party who after receiving an arbitration award requests a trial de novo but does not obtain a more favorable judgment shall, in addition to payment of costs and fees under that chapter, pay the attorney's fees of the other party arising out of the trial de novo.

(c) The court may, upon request by any party, order any witnesses to participate in the mediation or arbitration process.

(Amended by Stats. 2004, Ch. 182, Sec. 54. Effective January 1, 2005. Operative July

1, 2005, by Sec. 64 of Ch. 182.)

20104.6.


(a) No local agency shall fail to pay money as to any portion of a claim which is undisputed except as otherwise provided in the contract.

(b) In any suit filed under Section 20104.4, the local agency shall pay interest at the legal rate on any arbitration award or judgment. The interest shall begin to accrue on the date the suit is filed in a court of law.

(Added by Stats. 1994, Ch. 726, Sec. 22. Effective September 22, 1994.)


Appendix E

Vicinity and Location Maps and Typical Details



*** PROJECT LOCATION**
GAZOS CREEK ROAD (3.3 MI)
FROM CLOVERDALE ROAD TO GATE

F:\Users\design\C3D\S504-5000_2021 Gazos Creek Road Repair\01 FEMA Vicinity Map (Y0003).dwg



DESIGNED BY: J.RAWLEY
 CHECKED BY: Z.AZZARI
 DRAWN BY: J.RAWLEY

GAZOS CREEK ROAD REPAIR PROJECT
FEMA-4558-DR-CA
VICINITY MAP

SCALE: NONE
 DATE: 05/07/2021
 FILE NO: S5045

JAMES C. PORTER, DIRECTOR OF PUBLIC WORKS
 SAN MATEO COUNTY

555 COUNTY CENTER, 5TH FLOOR
 REDWOOD CITY, CALIFORNIA 94063-1665





F:\Users\design\CAD\S5045000_2021 Gazos Creek Road Repair\01 FEMA\S5045.dwg





NOTES:

1. CONSTRUCTION LIMITS FOR MICROSURFACING APPLICATION SHALL BE FIELD VERIFIED BY THE CONTRACTOR IN AGREEMENT WITH THE COUNTY ENGINEER PRIOR TO CONSTRUCTION. SEE SHEET 2 FOR TYP. DETAIL.
2. PAVEMENT REPAIR LOCATIONS SHALL BE MARKED IN THE FIELD BY THE COUNTY ENGINEER PRIOR TO CONSTRUCTION. SEE SHEET 2 FOR TYP. DETAIL.
3. ALL TRAFFIC CONTROL SIGNAGE/DEVICES SHALL BE PLACED IN ACCORDANCE WITH THE LATEST EDITION OF THE MUTCD SPECIFICATIONS AND STANDARDS.


LEGEND:

-  MICROSURFACING LIMITS
-  CONSTRUCTION SIGNAGE

APPROVED: _____
 DATE: 05/11/2021

 JAMES C. PORTER, DIRECTOR OF PUBLIC WORKS
 R. C. E. # 48056 / EXPIRES 12-31-2021




DESIGNED BY: J. RAWLEY	GAZOS CREEK ROAD REPAIR PROJECT (3.3 MILES) FEMA-4558-DR-CA LOCATION MAP - PESCADERO AREA	SCALE: NONE
CHECKED BY: Z. AZZARI		DATE: 05/07/21
DRAWN BY: J. RAWLEY		FILE NO: S5045
JAMES C. PORTER, DIRECTOR OF PUBLIC WORKS SAN MATEO COUNTY		555 COUNTY CENTER, 5TH FLOOR REDWOOD CITY, CALIFORNIA 94063-1665
		1 SHEET 1 OF 2



NOTES:

1. EXACT LOCATIONS AND DIMENSIONS OF PAVEMENT REPAIR AREAS SHALL BE DETERMINED AND MARKED IN THE FIELD BY THE COUNTY ENGINEER.
2. ASPHALTIC EMULSION (SS1) TACK COAT SHALL BE APPLIED BETWEEN BASE MATERIAL AND NEW ASPHALT CONCRETE, AND ALONG VERTICAL FACES PRIOR TO ASPHALT CONCRETE BACKFILL.
3. UNDERLYING MATERIAL SHALL BE COMPACTED TO 95% AND TO A DEPTH OF ONE FOOT (1').
4. ASPHALTIC EMULSION (SS1) SHALL BE APPLIED AND SAND COATED AS A FOG SEAL TO TOP SURFACE OF PAVEMENT REPAIR AREAS, AS REQUIRED AND AS DIRECTED BY THE COUNTY ENGINEER.

TYP. PAVEMENT REPAIR DETAIL (A)
N.T.S. 2




NOTES:

1. MICROSURFACING SHALL BE PLACED FROM EDGE OF PAVEMENT TO EDGE OF PAVEMENT. "EDGE OF PAVEMENT" IS CONSIDERED TO BE THE EDGE OF ROADWAY PAVEMENT, EDGE OF V-DITCHES (LINED AND UNLINED), OR AS DIRECTED BY THE COUNTY ENGINEER.
2. CONFORM TO EXISTING MONUMENTS, ETC., AS DIRECTED BY THE COUNTY ENGINEER.

TYP. SECTION MICROSURFACING SEAL (B)
N.T.S. 2


NOTES:

1. ALL CONSTRUCTION SHALL BE PERFORMED IN COMPLIANCE WITH THE PROJECT SPECIFICATIONS.



APPROVED:
DATE: 05/11/2021

JAMES C. PORTER, DIRECTOR OF PUBLIC WORKS
R. C. E. # 48056 / EXPIRES 12-31-2021



DESIGNED BY: J. RAWLEY
CHECKED BY: Z. AZZARI
DRAWN BY: J. RAWLEY

JAMES C. PORTER, DIRECTOR OF PUBLIC WORKS
SAN MATEO COUNTY

GAZOS CREEK ROAD REPAIR PROJECT (3.3 MILES)
FEMA-4558-DR-CA
DETAILS - PESCADERO AREA

555 COUNTY CENTER, 5TH FLOOR
REDWOOD CITY, CALIFORNIA 94063-1665

SCALE: NONE
DATE: 05/07/21
FILE NO: S5045

2
SHEET 2 OF 2

PROPOSAL SECTION

Contractor's Check-Off List:

1.	Complete Bidder's Information Sheet	1
2.	Complete Bid Proposal Sheet	4
3.	Check off for Bidder's Security (cash, cashier's check, certified check, or bidder's bond)	5
4.	Complete Principal(s) and Title(s) Sheet	7
5.	Complete State Contractor's License No. and Department of Industrial Relations Registration No.	8
6.	Complete Subcontractor List Sheets	9
7.	Complete Certification of Intent Sheet	14
8.	Equal Employment Opportunity Sheets:	
	i. Complete Questionnaire for Bidder Sheet	15
	ii. Complete Contractor Report Form	18
9.	Complete Equal Benefits Compliance Declaration Form	24
10.	Complete Employee Jury Service Compliance Declaration Form	28
11.	Complete Non-Collusion Declaration Form	29
12.	Complete Certification Regarding Lobbying, Sheet	30
13.	Complete Public Contract Code Section 10285.1 Statement	31
14.	Complete Public Contract Code Section 10162 Questionnaire	32
15.	Complete Debarment and Suspension Certification	35
16.	Complete Disclosure of Lobbying Activities	38
17.	Complete Certification of Bidder's Qualifications and Experience Form, Sheet	42

**PROPOSAL TO THE COUNTY OF SAN MATEO
STATE OF CALIFORNIA**

GAZOS CREEK ROAD REPAIR PROJECT

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO: 155545 FIPS NO: 081-99081-00**

NAME OF BIDDER: _____
STREET ADDRESS: _____
MAILING ADDRESS: _____
TELEPHONE NUMBER: (_____) _____
FAX NUMBER: (_____) _____
EMAIL FOR OFFICIAL NOTIFICATIONS: _____

The work for which this proposal is submitted is for construction in accordance with the Special Provisions and Agreement annexed hereto, the project plans described below, and the 2018 Department of Transportation Standard Plans and Standard Specifications, the Labor Surcharge and Equipment Rental Rates and the General Prevailing Wage Rates in effect on the date the work is accomplished.

It is the Contractor’s obligation and responsibility to ensure that all work associated with this Project complies with all current Orders of the Health Officer of the County of San Mateo related to the Novel Coronavirus Disease 2019 (COVID-19). The County of San Mateo assumes no responsibility for work performed by Contractor that is not in compliance with all current Orders. The Contractor is advised to review the Orders of the Health Officer of the County of San Mateo, which can be found at the following link:

<https://www.smchealth.org/post/health-officer-statements-and-orders>

LOCATION OF WORK

The work will be done in accordance with the Special Provisions and Agreement annexed hereto, and in accordance with the Standard Specifications of the County of San Mateo.

The location and details of said work are further shown on the Vicinity and Location Maps and Typical Details in Appendix E, File S5045 in the Department of Public Works.

**TO THE BOARD OF SUPERVISORS
COUNTY OF SAN MATEO
STATE OF CALIFORNIA**

The undersigned, as Bidder, declares that the only persons or parties interested in this Proposal as principals are those named herein; that this Proposal is made without collusion with any other person, firm or corporation; that he has carefully examined the location of the proposed work, the annexed proposed form of Agreement, and the Plans and Specifications therein referred to; that he proposes, and agrees if this Proposal is accepted, that he will contract with the County of San Mateo, in the form of the copy of the Agreement annexed hereto, to provide all necessary machinery, tools, apparatus and other means of construction and to do all the work and furnish all the materials specified in the Contract, in the manner and time therein prescribed and according to the requirements of the Engineer as therein set forth, and that he will accept in full payment therefor the following unit prices, to wit:

PROPOSAL TO THE COUNTY OF SAN MATEO

GAZOS CREEK ROAD REPAIR PROJECT

**TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

FEMA-4558-DR-CA

PROJECT NO: 155545 FIPS NO: 081-99081-00

Item No.	Section No.	Estimated Quantity	Unit of Measure	Item Description	Item Price (In Figures)	Total (In Figures)
1	11	1	LS	Mobilization	\$	\$
2	11-2	1	LS	Staging Area Restoration	\$	\$
3	12	1	LS	Maintaining Traffic	\$	\$
4	13	1	LS	Water Pollution Control	\$	\$
5	14	1	LS	Construction Waste Management	\$	\$
6	37	48,000	SY	Microsurfacing	\$	\$
7	39-3	200	SY	Pavement Repair (Type A, 3/4" Max-Med Grading)	\$	\$
TOTAL						\$

Bids are required for the entire work. The amount of the bid for comparison purposes will be the total of all items. The total of unit basis items will be determined by extension of the item price bid on the basis of the estimated quantity set forth for the item.

The Bidder shall set forth for each item of work, in clearly legible figures, an item price and a total for the item in the respective spaces provided for this purpose. In the case of unit basis items, the amount set forth under the "Total" column shall be the extension of the item price bid on the basis of the estimated quantity for the item.

In case of discrepancy between the item price and the total set forth for the item, the item price shall prevail, provided however, if the amount set forth as an item price is

ambiguous, unintelligible or uncertain for any cause, or is omitted, or in the case of unit basis items, is the same amount as the entry in the "Total" column, then the amount set forth in the "Total" column for the item shall prevail in accordance with the following:

1. As to lump sum items, the amount set forth in the "Total" column shall be the item price.
2. As to unit basis items, the amount set forth in the "Total" column shall be divided by the estimated quantity for the item and the price thus obtained shall be the item price.

After acceptance of this Proposal and award of the Contract, if the undersigned should fail to contract as aforesaid or should fail to give the "Performance" Surety Bond in the sum of one hundred percent (100%) of the Contract bid, the "Payment" Surety Bond in the sum of one hundred percent (100%) of the Contract bid, the Certificate of Insurance covering public liability and property damage in the amounts specified in the Agreement portion of these Contract documents, and the Certificate of Insurance covering Workmen's Compensation Insurance, within **TEN (10) WORKING DAYS** after award of the Contract, the County may, at its option, determine that the bidder has abandoned the Contract, thereupon this Proposal and the acceptance thereof shall be null and void, and the forfeiture of such security accompanying this Proposal shall operate and the same shall become the property of the County of San Mateo, State of California.

Accompanying this Proposal is:

- Cash
- A Cashier's Check (made payable to the "County of San Mateo")
- A Certified Check (made payable to the "County of San Mateo")
- A Bidder's Bond executed by an admitted surety insurer (made payable to the "County of San Mateo")

in the amount equal to at least ten percent (10%) of the total bid.

Bidders must, upon request, furnish evidence of their financial responsibility and ability to perform the work herein described.

PROVISIONS OF LABOR CODE

The Contractor shall be required to comply with all the payroll and apprenticeship provisions of Chapter 1, Division 2, Section 1776 and 1777.5 of the California Labor Code.

BIDDER'S FINANCIAL RESPONSIBILITY TECHNICAL ABILITY & EXPERIENCE

THE LOW BIDDER MUST, UPON REQUEST, FURNISH EVIDENCE OF FINANCIAL RESPONSIBILITY AND ABILITY TO PERFORM THE WORK INCLUDED IN THIS PROPOSED CONTRACT. SUCH EVIDENCE MAY INCLUDE, BUT NOT BE LIMITED TO, A FINANCIAL STATEMENT AS OF THE DATE OF BID; A STATEMENT, WITH REFERENCES, OF COMPLETED WORK OF A SIMILAR CHARACTER TO THAT INCLUDED HEREIN; A STATEMENT OF THE LAST TWO PROJECTS PERFORMED REGARDLESS OF THEIR CHARACTER; AND SUCH OTHER INFORMATION WHICH WILL ENABLE THE DIRECTOR OF PUBLIC WORKS TO JUDGE THE BIDDER'S RESPONSIBILITY, EXPERIENCE, SKILL AND BUSINESS STANDING.

The names of all persons interested in the foregoing Proposal as principals are as follows:

(Name of Corporation, Co-partnership, Individual)	
(Name and Title)	(Name and Title)
(Name and Title)	(Name and Title)
(Authorized Signature of Bidder)	(Authorized Signature of Bidder)

***(NOTICE:** If the Bidder is a corporation, the legal name of the corporation and the names of the president, secretary, treasurer, and manager thereof shall be set forth together with the signature of the officer or officers authorized to sign Contracts in behalf of the corporation; if the Bidder is a co-partnership, the true name of the firm and the names of the principal partners shall be set forth together with the signature of the partner or partners authorized to sign Contracts in behalf of the co-partnership; and, if the Bidder is an individual, his full name shall be set forth and his signature shall be as the authorized officer. If the signature is by an agent, other than by an officer of a corporation or a member of a partnership, a Power of Attorney must be on file with the County prior to opening of bids or submitted with the bid; otherwise, the bid will be disregarded as irregular and unauthorized.)

Corporations must, upon request, furnish certification attesting to corporate existence and authority of officers to sign contracts and other documents.

The undersigned is licensed by the Contractor's State License Board of the State of California to perform the work hereinafter described, which State Contractor's License No. is:

State Contractor's License No.: _____
(Expires: _____)

Pursuant to State Senate Bill SB 854 (Stat. 2014, chapter 28), effective January 1, 2015, No contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.

Department of Industrial Relations Registration No.: _____
(Expires: _____)

LICENSEE: _____
(Please print)

ADDRESS: _____

CITY AND STATE: _____

Date of Proposal

Signature

SUBCONTRACTORS

DESIGNATION OF SUBCONTRACTORS: Each Bidder shall set forth below the name, business address and telephone number of each subcontractor who will perform work or labor or render service to the Contractor in or about the construction of the work or improvement to be performed under these Contract Documents. The Bidder shall also list the proposal item number(s) to be done, in whole or in part, by each subcontractor and the total amount of each subcontractor's work in dollars and as a percentage of the total bid amount. The Bidder's attention is directed to Section 5-1.13, "Subcontracting", of the Standard Specifications.

SUBCONTRACTORS

1. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____

2. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____

3. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____

4. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____

SUBCONTRACTORS

(Continued)

5. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____
6. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____
7. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____
8. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____
9. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____
10. Name: _____ Item No(s). _____
 Address: _____ Dollar Amount: \$ _____
 Tel: (____) _____ Percent of Total Bid: _____%
 License No.: _____
 Department of Industrial Relations Registration No.: _____

SAN MATEO COUNTY
EQUAL EMPLOYMENT OPPORTUNITY (AFFIRMATIVE ACTION) PROGRAM

CONTRACT COMPLIANCE PROGRAM

The purpose of the **Contract Compliance Program** is two-fold:

1. **To prohibit and eliminate employment discrimination; and**
2. **To further the opportunities for minority persons to be gainfully employed in County construction contracts.**

The program requires equal employment opportunity efforts by Contractors to employ minority workers on the County's construction projects. The Contractor will not discriminate against any employee or applicant for employment because of race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex. The Contractor will take equal employment opportunity actions to ensure that applicants are employed, and that employees are treated, during employment, without regard to their race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex; with the goal that the ethnic composition of the Contractor's work force will approximate the ethnic composition of the population of San Mateo County. Such action shall include, but not be limited to, employment, upgrading, demotion or transfer; recruitment; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship training and on-the-job training.

The **San Mateo County Equal Employment Opportunity Program** requires the Contractor to make two certifications. The first assures compliance with laws prohibiting discrimination. The second concerns the intent to develop and implement an equal employment opportunity program.

The Contractor is further required to:

1. Post "**EQUAL EMPLOYMENT OPPORTUNITY NOTICE(S)**", including the statement: "**AN EQUAL OPPORTUNITY EMPLOYER**", in all announcements of job openings;
2. Permit access by County and State compliance officials to his employment records; and
3. File monthly reports on prescribed forms:
 - A. **Monthly Manpower-Utilization Report**
 - B. **Weekly payroll Form WH-347** (which form can be found on the U.S.

Department of Labor, Wage & Hour Division website, which website is addressed as <http://www.dir.ca.gov/dlsr/PWD/Northern.html>)

- C. **Statement of Compliance** (which form is on the back of payroll form WH-347 or separate form WH-348, as requested by the County's contract compliance representative)
- D. Assign an equal opportunity officer full time or as additional duty.

Union employees are to be recruited according to applicable labor agreements. If non-union employees are recruited for the project, the Contractor shall make use of minority-oriented news media and referral sources. The Contractor shall inform all subcontractors hired by him on the project(s) of their obligations under this program; and Contractor **will be responsible for the compliance with these regulations by his subcontractors.**

For failure to comply with the non-discrimination section, the Contractor is subject to a penalty of **two percent (2%) of the total amount payable for each working day during which he was found to be in non-compliance, or the cancellation of the contract in part or whole.**

The County's Contract Compliance Program is monitored by the San Mateo County Department of Public Works, 555 County Center, Redwood City, CA, 94063-1665, telephone (650) 363-4100.

Information and necessary forms are available at the **Department of Public Works**. In addition to evaluating Contractors' and subcontractors' equal opportunity efforts, the **Department of Public Works** will assist Contractors and subcontractors toward meeting these obligations.

**CERTIFICATION OF COMPLIANCE
WITH LAWS PROHIBITING DISCRIMINATION**

We are in compliance with the **EQUAL EMPLOYMENT OPPORTUNITY REQUIREMENT OF THE EXECUTIVE ORDER 11246, TITLE VII OF THE CIVIL RIGHTS ACT OF 1964, THE CALIFORNIA FAIR EMPLOYMENT AND HOUSING ACT**, any other Federal or State laws relating to equal employment opportunity and the provisions of **Title 2, Chapter 2.50 of the San Mateo County Ordinance Code** and the Board established guidelines implementing them.

We will not discriminate against any employee or applicant for employment based on **race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex**. This pertains to the areas of **recruitment, hiring, training, upgrading, transfer, compensation and termination**.

CERTIFICATION OF INTENT

We will maintain or develop and implement, during the course of the work concerned, an **Equal Employment Opportunity Program** of hiring and employment conducted without regard to **race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex** of the applicants. With this Certification we shall submit any and all information that may be required by the County in connection with this program.

We certify that we have read and understood the County of San Mateo's **GENERAL EQUAL EMPLOYMENT OPPORTUNITY STATEMENT SECTION III-A**, which is included in the proposal section of the Specifications.

As a private Contractor, working under contracts with the County of San Mateo, we understand that these policies are the requirements of said County employment and we will, in our recruitment, training and staffing, work to implement this Section as applicable.

Signature and Title of Authorized Representative or Bidder

Date

**SAN MATEO COUNTY
EQUAL EMPLOYMENT OPPORTUNITY PROGRAM**

QUESTIONNAIRE FOR BIDDER

THIS REPORT MUST BE COMPLETED IN FULL BY AN OFFICIAL OF THE COMPANY AND SUBMITTED WITH THE BID.

PROJECT: _____

NAME OF FIRM: _____

ADDRESS: _____

CITY/ZIP: _____

TELEPHONE: (____) _____ DATE OF SUBMITTAL: _____

OFFICIAL FOR COMPANY: _____

1. _____ Yes _____ No Have you read and are you acquainted with the **Equal Employment Opportunity Requirement** of the Executive Order 11246, Title VII of the **Civil Rights Act of 1964**, the California Fair Employment Practices Act and **Title 2, Chapter 2.50** of the San Mateo County Ordinance Code?

2. _____ Yes _____ No Does your employment advertising state that you are an Equal Opportunity Employer?

3. _____ Yes _____ No Have all recruitment sources been advised that all qualified applicants will be considered for employment without regard to race, religion, color, national origin, age, disability, ancestry, sexual orientation, or sex?

4. _____ Yes _____ No Were any employees hired by means other than the union hiring hall in the past year?

How many? _____

What positions? _____

5. If non-union personnel are employed by the company, or if a position cannot be filled by the union hall, specify the advertisement and recruitment sources that are

used. (For example, State HRD, newspapers, high schools, vocational schools, referral agencies/organizations, community groups.)

6. How many apprentices do you employ? _____
How many of these are minorities? _____

7. _____ Yes _____ No Do you have a program for upgrading and counseling present employees?

Describe: _____

8. _____ Yes _____ No Do you have a collective bargaining agreement with a labor union or other organization?

Please list these groups _____

9. What percentage of your work force is covered by union agreement? _____

10. _____ Yes _____ No Have you advised the labor union and/or worker

organizations of your company's responsibility under the Equal Employment Opportunity Program?

11. _____ Yes _____ No

Does your company's collective bargaining agreement include a provision for non-discrimination in employment?

12. Describe any previous experience with Equal Employment Opportunity Programs:

If your company has a written Equal Employment Opportunity Program now in effect, please attach a copy.

**COUNTY OF SAN MATEO
EQUAL EMPLOYMENT OPPORTUNITY PROGRAM**

**CONTRACTOR REPORT FORM
(To Be Submitted with Original Bid)**

PROJECT: _____ DATE: _____

NAME OF BIDDER: _____

NAME OF PERSON SUBMITTING REPORT: _____

RACIAL/ETHNIC MAKEUP OF THE COMPANY

Be sure to include the total of all employees in each classification in the first column. Report the number of employees enrolled in formal on-the-job (apprenticeship) training programs in parenthesis () for each classification.

Minority Employees									
Job Classification	Total (All Employee s)	Ethnicity							
		American- Indian or Native Alaskan	Asian	Native Hawaiian or Pacific Islander	Black American or African American	Caucasian	Filipino	Hispani c or Latino (1)	Other (2)
Total (s)									

Notes: (1) "Hispanic" includes all persons of Mexican, South and Central American, Puerto Rican, Cuban or Spanish ancestry.
 (2) "Other" includes all others whose origin consists of two or more races other than Hispanic or Latino.
 (3) Use this category for employees who have chosen not to identify any race or ethnicity, including "Other".

**SECTION III-A. GENERAL EQUAL EMPLOYMENT
OPPORTUNITY POLICY STATEMENT**

The Board of Supervisors of the County of San Mateo takes this opportunity to express its commitment to one of its highest priorities in the area of employment. This priority is assuring that all employees and applicants for employment are provided equal access to, and enjoyment of employment opportunities, and that they are not subjected to discrimination because of age (over 40), ancestry, creed, color, disability, marital status, medical condition, national origin, political or religious affiliation, race, sex, or sexual orientation.

The Board of Supervisors is committed to ensuring compliance with all applicable non-discrimination laws and regulations in order to attain a work environment that is free of discrimination so all County employees can provide quality public service.

The County will take positive measures toward eliminating artificial barriers to employment and achieving equal opportunity through its continued implementation and coordination of the County's Equal Employment Opportunity Program and through its review and evaluation of hiring and promotional policies and procedures.

It is the belief of the Board of Supervisors that equal employment opportunity is consistent with the basic merit system principle that all persons be afforded equal access to positions in public service based on their ability to do the job. Employment decisions shall be made on the basis of merit and in conformity with the principles of equal opportunity action.

Through adoption of the Equal Employment Opportunity Program, the Board of Supervisors commits the County, the operating departments, the Equal Employment Opportunity Coordinator, and all employees to a results-oriented Equal Employment Opportunity Program aimed at attaining a balanced workforce at all levels of County employment and achieving equal opportunity in County service.

EQUAL BENEFITS COMPLIANCE ORDINANCE NO. 04026**CHAPTER 2.84**ORDINANCE NO 04026

AN ORDINANCE OF THE SAN MATEO COUNTY ORDINANCE CODE (TITLE 2, ADMINISTRATION), REQUIRING SPECIFIED COUNTY CONTRACTORS TO PROVIDE FOR NON-DISCRIMINATION BY COUNTY CONTRACTORS IN THE PROVISION OF EMPLOYEE BENEFITS

WHEREAS, employee benefits routinely comprise a significant proportion of total employee compensation; and

WHEREAS, discrimination in the provision of employee benefits between employees with domestic partners and employees with spouses results in unequal pay for equal work; and

WHEREAS, County of San Mateo law prohibits discrimination based on marital status and/or sexual orientation; and

WHEREAS, it is the County's intent, through the contracting practices outlined herein, to equalize the total compensation between similarly situated employees with spouses and employees with domestic partners;

Section 1. The Board of Supervisors of the County of San Mateo, State of California, **ORDAINS** as follows:

Chapter 2.84 CONTRACTS – EQUAL BENEFITS**2.84.010 Definitions.**

For the purposes of this chapter,

- A. “Contract” means a legal agreement between the County and a contractor for public works, consulting, or other services, or for purchase of supplies, material or equipment for which the consideration is in excess of \$5,000.
- B. “Contractor” means a party who enters into a contract with the County.
- C. “Contract Awarding Authority” means the Board of Supervisors or the individual authorized by the Board of Supervisors to enter into contracts on behalf of the County.
- D. “Domestic Partner” means any person who is registered as a domestic partner with the Secretary of State, State of California registry or the registry of the state in which the employee is a resident.
- E. “Employee Benefits” means the provision of any benefit other than pension and retirement benefits provided to spouses of employees or provided to an employee on account of the employee's having a spouse, including but not

limited to bereavement leave; disability, life, and other types of insurance; family medical leave; health benefits; membership or membership discounts; moving expenses; vacation; travel benefits; and any other benefits given to employees, provided that it does not include benefits to the extent that the application of the requirements of this chapter to such benefits may be preempted by federal or state law.
(Ord. 4324, 08/15/06)

2.84.020 Discrimination in the provision of benefits prohibited.

(a) No contractor on a County contract shall discriminate in the provision of employee benefits between an employee with a domestic partner and an employee with a spouse, subject to the following conditions:

1. In the event that the contractor's actual cost of providing a particular benefit for the domestic partner of an employee exceeds that of providing it for the spouse of an employee, or the contractor's actual cost of providing a particular benefit to the spouse of an employee exceeds that of providing it for the domestic partner of an employee, the contractor shall not be deemed to discriminate in the provision of employee benefits if the contractor conditions providing such benefit upon the employee's agreement to pay the excess costs.
2. The contractor shall not be deemed to discriminate in the provision of employee benefits if, despite taking reasonable measures to do so, the contractor is unable to extend a particular employee benefit to domestic partners, so long as the contractor provides the employee with a cash payment equal to the contractor's cost of providing the benefit to an employee's spouse.

(b) The Board of Supervisors may waive the requirements of this chapter when it determines that it is in the best interests of the County. The County Manager may waive the requirements of this chapter for contracts not needing the approval of the Board of Supervisors where waiver would be in the best interests of the County for such reasons as follows:

1. Award of a contract or amendment is necessary to respond to an emergency;
2. The contractor is a sole source;
3. No compliant contractors are capable of providing goods or services that respond to the County's requirements;
4. The requirements are inconsistent with a grant, subvention or agreement with a public agency;
5. The County is purchasing through a cooperative or joint purchasing agreement;

(c) Contractors should submit requests for waivers of the terms of this chapter to the Contract Awarding Authority for that contract, or in the case of Contracts approved by the Board, the County Manager.

(d) The Contract Awarding Authority, or in the case of contracts approved by the Board, the County Manager, may reject an entity's bid or proposals, or terminate a contract, if the Contract Awarding Authority determines that the entity was set up, or is being used, for the purpose of evading the intent of this chapter.

(e) No Contract Awarding Authority shall execute a contract with a contractor unless such contractor has agreed that the contractor will not discriminate in the provision of employee benefits as provided for in this chapter. (Ord. 4324, 08/15/06)

2.84.030 Application of Chapter.

The requirements of this chapter shall only apply to those portions of a contractor's operations that occur (i) within the County; (ii) on real property outside of the County if the property is owned by the County or if the County has a right to occupy the property, and if the contractor's presence at that location is connected to a Contract with the County; and (iii) elsewhere in the United States where work related to a County Contract is being performed. The requirements of this Chapter shall not apply to subcontracts or subcontractors of any contract or contractor. (Ord. 4324, 08/15/06)

2.84.040 Powers and duties of the County Manager.

The County Manager's office shall have the authority to:

(a) Adopt rules and regulations, in accordance with this chapter and the Ordinance Code of the County of San Mateo, establishing standards and procedures for effectively carrying out this chapter.

(b) Receive notification from employees of contractors regarding violations of this chapter.

(c) Determine and recommend to the Board of Supervisors for final decision the imposition of appropriate sanctions for violation of this chapter by contractors including, but not limited to:

1. Disqualification of the contractor from bidding on or being awarded a County contract for a period of up to 5 years; and
2. Contractual remedies, including, but not limited to termination of contract.
3. Liquidated damages in the amount of \$2,500.

(d) Examine contractors' benefit programs covered by this chapter;

(e) Impose other appropriate contractual and civil remedies and sanctions for violations of this chapter;

(f) Allow for remedial action after a finding of non-compliance, as specified by rule;

(g) Perform such other duties as may be required or which are necessary to implement the purposes of this chapter. (Ord. 4324, 08/15/06)

2.84.050 Date of Application.

The provisions of this chapter shall apply to any contract awarded or amended on or after July 01, 2001, provided that if the contractor is then signatory to a collective bargaining agreement, this chapter shall only apply to any contract with that contractor which is awarded or amended after the effective date of the next collective bargaining agreement. (Ord. 4324, 08/15/06)

Section 2. Severability – The provisions of this ordinance are declared to be separate and severable. If a court of competent jurisdiction, all appeals having been exhausted or all appeal periods having run, finds any provision of this ordinance to be invalid or unenforceable as to any person or circumstance, such offending provision shall, if feasible, be deemed to be modified to be within the limits of enforceability or validity. However, if the offending provision cannot be so modified, it shall be null and void with respect to the particular person or circumstance, and all other provisions of this ordinance in all other respects, and the offending provision with respect to all other persons and all other circumstances, shall remain valid and enforceable.

COUNTY OF SAN MATEO
Equal Benefits Compliance Declaration Form
 (To Be Submitted with Proposal)

I Vendor Identification

Name of Contractor: _____

Contact Person: _____

Address: _____

Phone Number: _____ Fax Number: _____

II Employees

Does the Contractor have any employees? _____ Yes _____ No

Does the Contractor provide benefits to spouses of employees? _____ Yes _____
 _____ No

*If the answer to one or both of the above is no, please skip to Section IV. *

III Equal Benefits Compliance (Check One) Yes, the Contractor complies by offering equal benefits, as defined by Chapter 2.84, to its employees with spouses and its employees with domestic partners. Yes, the Contractor complies by offering a cash equivalent payment to eligible employees in lieu of equal benefits. No, the Contractor does not comply. *(NOTE: **DO NOT CHECK THIS BOX** unless the said agreement was executed/renewed on or before July 1, 2001. If checked, a copy of the collective bargaining agreement shall be submitted with Proposal.)*The Contractor is under a collective bargaining agreement which began **on or before July 1, 2001** and expires on _____ (date). (Section 2.84.050)**IV Declaration**

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct, and that I am authorized to bind this entity contractually.

Executed this _____ day of _____, 20__ at _____, _____.
 (City) (State)_____
Signature_____
Name (Please Print)_____
Title_____
Contractor Tax Identification Number

**CONTRACTOR EMPLOYEE JURY SERVICE ORDINANCE NO. 04269
CHAPTER 2.85**

ORDINANCE NO 04269

AN ORDINANCE OF THE SAN MATEO COUNTY ORDINANCE CODE (TITLE 2,
ADMINISTRATION), REQUIRING SPECIFIED COUNTY CONTRACTORS
TO PROVIDE PAID JURY SERVICE TO FULL-TIME EMPLOYEES

The Board of Supervisors of the County of San Mateo, State of California,
ORDAINS as follows:

Chapter 2.85 CONTRACTOR EMPLOYEE JURY SERVICE

2.85.010 Definitions

For the purposes of this chapter,

- (a) "Contract" means a legal agreement between the County and a contractor for public works, consulting, or other services, or for purchase of supplies, material or equipment.
- (b) "Contractor" means a party who enters into a contract with the County for which the contractor receives consideration of \$100,000 or more.
- (c) "Contract Authority" means the Board of Supervisors or the head of the department or agency presenting the proposed contract to the Board of Supervisors.
- (d) "Employee " means any California resident who is a full-time employee of a contractor under the laws of California.
- (e) "Full time " means 40 hours or more worked per week, or a lesser number of hours if (1) the lesser number is a recognized industry standard as determined by the County Manager, or (2) the contractor has a long standing practice that defines the lesser number of hours as full time. (Ord. 4324, 08/15/06)

2.85.020 Contractor jury service policy

- (a) A contractor shall have and adhere to a written policy that provides that its employees shall receive from the contractor, on an annual basis, no less than five days of regular pay for actual jury service in San Mateo County. The policy may provide that employees deposit any fees received for such jury service with the contractor or that the contractor deduct from the employees' regular pay the fees received for jury service.
- (b) At the time of seeking a contract, a contractor shall certify to the County that it has and adheres to a policy consistent with this chapter or will have and adhere to such a policy prior to award of the contract.

- (c) The Board of Supervisors may waive the requirements of this chapter when it determines that it is in the best interests of the County for such reasons as follows:
 - (1) Award of a contract or amendment is necessary to respond to an emergency;
 - (2) The contractor is a sole source;
 - (3) No compliant contractors are capable of providing goods or services that respond to the County's requirements;
 - (4) The requirements are inconsistent with a grant, subvention or agreement with a public agency;
 - (5) The County is purchasing through a cooperative or joint purchasing agreement.
- (d) Contractors should submit requests for waivers of the terms of this chapter to the Contract Authority or the County Manager.
- (e) The County Manager may reject a contractor's bid or proposal, or terminate a contract, if he determines that the contractor is in violation of the requirements of this chapter or was established, or is being used, for the purpose of evading the intent of this chapter.
- (f) No contract shall be executed with a contractor unless such contractor is in compliance with this chapter. (Ord. 4324, 08/15/06)

2.85.030 Powers and duties of the County Manager

The County Manager's office shall have the authority to:

- (a) Adopt rules and regulations, in accordance with this chapter and the Ordinance Code of the County of San Mateo, establishing standards and procedures for effectively carrying out this chapter.
- (b) Receive notification from employees of contractors regarding violations of this chapter.
- (c) Determine and recommend to the Board of Supervisors for final decision the imposition of appropriate sanctions for violation of this chapter by contractors including, but not limited to:
 - (1) Disqualification of the contractor from bidding on or being awarded a County contract for a period of up to 5 years; and
 - (2) Contractual remedies, including, but not limited to termination of contract.
- (d) Impose other appropriate contractual sanctions for violations of this chapter;
- (e) Allow for remedial action after a finding of non-compliance;

- (f) Perform such other duties as may be required or which are necessary to implement the purposes of this chapter. (Ord. 4324, 08/15/06)

2.85.040 Date of Application

The provisions of this chapter shall apply to any contract awarded or amended on or after September 01, 2005, provided that if the contractor is then signatory to a collective bargaining agreement, this chapter shall only apply to any contract with that contractor which is awarded or amended after the effective date of the next collective bargaining agreement. (Ord. 4324, 08/15/06)

COUNTY OF SAN MATEO
Employee Jury Service Compliance Declaration Form
 (To Be Submitted with Proposal)

I Vendor Identification

Name of Contractor: _____
 Contact Person: _____
 Address: _____
 Phone Number: _____ Fax Number: _____

II Employees

Does the Contractor have any employees? _____ Yes _____ No

*If the answer to the above is no, please skip to Section IV. *

III Contractor Employee Jury Service Compliance (Check One)

- Yes, the Contractor complies by offering paid employee jury service, as defined by Chapter 2.85, to its employees.
- The Contractor will have and adhere to, prior to award of the Contract, a policy that complies by offering paid employee jury service, as defined by Chapter 2.85, to its employees.
- No, the Contractor does not comply.
- (NOTE: **DO NOT CHECK THIS BOX** unless the said agreement was executed/renewed on or before September 1, 2005. If checked, a copy of the collective bargaining agreement shall be submitted with Proposal.)*

The Contractor is under a collective bargaining agreement which began **on or before September 1, 2005** and expires on _____ (date). (Section 2.85.040)

IV Declaration

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct, and that I am authorized to bind this entity contractually.

Executed this _____ day of _____, 20__ at _____, _____.
(City) (State)

 Signature

 Name (Please Print)

 Title

 Contractor Tax Identification Number

NON-COLLUSION DECLARATION FORM

THIS FORM SHALL BE EXECUTED BY BIDDER AND SUBMITTED WITH BID.

The undersigned declares:

I am the _____ of _____, the party making the foregoing bid.

The bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation. The bid is genuine and not collusive or sham. The bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid. The bidder has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or to refrain from bidding. The bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder. All statements contained in the bid are true. The bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, to any corporation, partnership, company, association, organization, bid depository, or to any member or agent thereof, to effectuate a collusive or sham bid, and has not paid, and will not pay, any person or entity for such purpose.

Any person executing this declaration on behalf of a bidder that is a corporation, partnership, joint venture, limited liability company, limited liability partnership, or any other entity, hereby represents that he or she has full power to execute, and does execute, this declaration on behalf of the bidder.

I declare under penalty of perjury under the laws of the State of California that the foregoing is true and correct and that this declaration is executed on _____ [Date], at _____ [City], _____ [State].

“Contractor”

(Print)

(Signature)

CERTIFICATION REGARDING LOBBYING

As required by 44 C.F.R. Part 18:

The undersigned [Contractor] certifies, to the best of his or her knowledge, that:

1. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
2. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
3. The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31, U.S.C. § 1352 (as amended by the Lobbying Disclosure Act of 1995). Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

The Contractor, _____, certifies or affirms the truthfulness and accuracy of each statement of its certification and disclosure, if any. In addition, the Contractor understands and agrees that the provisions of 31 U.S.C. § 3801 et seq., apply to this certification and disclosure, if any.

Signature of Contractor's Authorized Official

Name and Title of Contractor's Authorized Official

Date

PUBLIC CONTRACT CODE SECTION 10285.1 STATEMENT

In conformance with Public Contract Code Section 10285.1 (Chapter 376, Stats. 1985), the bidder hereby declares under penalty of perjury under the laws of the State of California that the bidder has _____/ has not _____ been convicted within the preceding three years of any offenses referred to in that section, including any charge of fraud, bribery, collusion, conspiracy, or any other act in violation of any state or Federal antitrust law in connection with the bidding upon, award of, or performance of, any public works contract, as defined in Public Contract Code Section 1101, with any public entity, as defined in Public Contract Code Section 1100, including the Regents of the University of California or the Trustees of the California State University. The term "bidder" is understood to include any partner, member, officer, director, responsible managing officer, or responsible managing employee thereof, as referred to in Section 10285.1.

Notes:

- (1) The bidder must place a check mark after "has" or "has not" in one of the blank spaces provided. The above Statement is part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Statement.
- (2) Bidders are cautioned that making a false certification may subject the certifier to criminal prosecution.

PUBLIC CONTRACT CODE SECTION 10162 QUESTIONNAIRE

In accordance with Public Contract Code Section 10162, the Bidder shall complete, under penalty of perjury, the following questionnaire:

Has the bidder, any officer of the bidder, or any employee of the bidder who has a proprietary interest in the bidder, ever been disqualified, removed, or otherwise prevented from bidding on, or completing a Federal, State, or local government project because of a violation of law or safety regulation?

Yes _____ No _____

If the answer is "Yes," explain the circumstances in the following space:

Notes:

- (1) The above Public Contract Code Section 10162 Questionnaire is part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Questionnaire.
- (2) Bidders are cautioned that making a false certification may subject the certifier to criminal prosecution.

PUBLIC CONTRACT SECTION 10232 STATEMENT

In conformance with Public Contract Code Section 10232, the Contractor hereby states, under penalty of perjury, that no more than one final unappealable finding of contempt of court by a Federal court has been issued against the Contractor within the immediately preceding two year period because of the Contractor's failure to comply with an order of a Federal court which orders the Contractor to comply with an order of the National Labor Relations Board.

Notes:

- (1) The above Statement and Questionnaire are part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Statement and Questionnaire.
- (2) Bidders are cautioned that making a false certification may subject the certifier to criminal prosecution.

NON-COLLUSION AFFIDAVIT

(Title 23 United States Code Section 112 and
Public Contract Code Section 7106)

To the COUNTY of SAN MATEO, *DEPARTMENT OF PUBLIC WORKS*.

In conformance with Title 23 United States Code Section 112, and Public Contract Code Section 7106, the bidder declares that the bid is not made in the interest of, or on behalf of, any undisclosed person, partnership, company, association, organization, or corporation; that the bid is genuine and not collusive or sham; that the bidder has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid, and has not directly or indirectly colluded, conspired, connived, or agreed with any bidder or anyone else to put in a sham bid, or that anyone shall refrain from bidding; that the bidder has not in any manner, directly or indirectly, sought by agreement, communication, or conference with anyone to fix the bid price of the bidder or any other bidder, or to fix any overhead, profit, or cost element of the bid price, or of that of any other bidder, or to secure any advantage against the public body awarding the contract of anyone interested in the proposed contract; that all statements contained in the bid are true; and, further, that the bidder has not, directly or indirectly, submitted his or her bid price or any breakdown thereof, or the contents thereof, or divulged information or data relative thereto, or paid, and will not pay, any fee to any corporation, partnership, company association, organization, bid depository, or to any member or agent thereof to effectuate a collusive or sham bid.

Notes:

- (1) The above Non-Collusion Affidavit is part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Non-Collusion Affidavit.
- (2) Bidders are cautioned that making a false certification may subject the certifier to criminal prosecution.

DEBARMENT AND SUSPENSION CERTIFICATION
TITLE 49, CODE OF FEDERAL REGULATIONS, PART 29

The bidder, under penalty of perjury, certifies that, except as noted below, he/she or any other person associated therewith in the capacity of owner, partner, director, officer, manager:

- is not currently under suspension, debarment, voluntary exclusion, or determination of ineligibility by any Federal agency;
- has not been suspended, debarred, voluntarily excluded or determined ineligible by any Federal agency within the past 3 years;
- does not have a proposed debarment pending; and
- has not been indicted, convicted, or had a civil judgement rendered against it by a court of competent jurisdiction in any matter involving fraud or official misconduct within the past 3 years.

If there are any exceptions to this certification, insert the exceptions in the following space.

Exceptions will not necessarily result in denial of award, but will be considered in determining bidder responsibility. For any exception noted above, indicate below to whom it applies, initiating agency, and dates of action.

Notes:

- (1) Providing false information may result in criminal prosecution or administrative sanctions.
- (2) The above certification is part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Certification.

**NON-LOBBYING CERTIFICATION
FOR FEDERAL-AID CONTRACTS**

The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

- (1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- (2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure of Lobbying Activities," in accordance with its instructions.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, Title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such sub-recipients shall certify and disclose accordingly.

Notes:

- (1) The above Non-Lobbying Certification for Federal-Aid Contracts is part of the Proposal. Signing this Proposal on the signature portion thereof shall also constitute signature of this Certification.
- (2) Bidders are cautioned that making a false certification may subject the certifier to criminal prosecution.

INSTRUCTIONS FOR COMPLETION OF SF-LLL, DISCLOSURE OF LOBBYING ACTIVITIES

This disclosure form shall be completed by the reporting entity, whether subawardee or prime Federal recipient, at the initiation or receipt of covered Federal action or a material change to previous filing pursuant to title 31 U.S.C. Section 1352. The filing of a form is required for such payment or agreement to make payment to lobbying entity for influencing or attempting to influence an officer or employee of any agency, a Member of Congress an officer or employee of Congress or an employee of a Member of Congress in connection with a covered Federal action. Attach a continuation sheet for additional information if the space on the form is inadequate. Complete all items that apply for both the initial filing and material change report. Refer to the implementing guidance published by the Office of Management and Budget for additional information.

1. Identify the type of covered Federal action for which lobbying activity is and/or has been secured to influence, the outcome of a covered Federal action.
2. Identify the status of the covered Federal action.
3. Identify the appropriate classification of this report. If this is a follow-up report caused by a material change to the information previously reported, enter the year and quarter in which the change occurred. Enter the date of the last, previously submitted report by this reporting entity for this covered Federal action.
4. Enter the full name, address, city, state and zip code of the reporting entity. Include Congressional District if known. Check the appropriate classification of the reporting entity that designates if it is or expects to be a prime or subaward recipient. Identify the tier of the subawardee, e.g., the first subawardee of the prime is the first tier. Subawards include but are not limited to subcontracts, subgrants and contract awards under grants.
5. If the organization filing the report in Item 4 checks "Subawardee" then enter the full name, address, city, state and zip code of the prime Federal recipient. Include Congressional District, if known.
6. Enter the name of the Federal agency making the award or loan commitment. Include at least one organization level below agency name, if known. For example, Department of Transportation, United States Coast Guard.
7. Enter the Federal program name or description for the covered Federal action (item 1). If known, enter the full Catalog of Federal Domestic Assistance (CFDA) number for grants, cooperative agreements, loans and loan commitments.
8. Enter the most appropriate Federal identifying number available for the Federal action identification in item 1 (e.g., Request for Proposal (RFP) number, Invitation for Bid (IFB) number, grant announcement number, the contract grant. or loan award number, the application/proposal control number assigned by the Federal agency). Include prefixes, e.g., "RFP-DE-90-001."

9. For a covered Federal action where there has been an award or loan commitment by the Federal agency, enter the Federal amount of the award/loan commitments for the prime entity identified in item 4 or 5.
10. (a) Enter the full name, address, city, state and zip code of the lobbying entity engaged by the reporting entity identified in item 4 to influenced the covered Federal action. (b) Enter the full names of the individual(s) performing services and include full address if different from 10 (a). Enter Last Name, First Name and Middle Initial (MI).
11. Enter the amount of compensation paid or reasonably expected to be paid by the reporting entity (item 4) to the lobbying entity (item 10). Indicate whether the payment has been made (actual) or will be made (planned). Check all boxes that apply. If this is a material change report, enter the cumulative amount of payment made or planned to be made.
12. Check the appropriate box(es). Check all boxes that apply. If payment is made through an in-kind contribution, specify the nature and value of the in-kind payment.
13. Check the appropriate box(es). Check all boxes that apply. If other, specify nature.
14. Provide a specific and detailed description of the services that the lobbyist has performed or will be expected to perform and the date(s) of any services rendered. Include all preparatory and related activity not just time spent in actual contact with Federal officials. Identify the Federal officer(s) or employee(s) contacted or the officer(s) employee(s) or Member(s) of Congress that were contacted.
15. Check whether or not a continuation sheet(s) is attached.
16. The certifying official shall sign and date the form, print his/her name title and telephone number.

Public reporting burden for this collection of information is estimated to average 30 minutes per response, including time for reviewing instruction, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding the burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to the Office of Management and Budget, Paperwork Reduction Project (0348-0046), Washington, D.C. 20503.

CERTIFICATION OF BIDDER'S QUALIFICATIONS AND EXPERIENCE

(To Be Submitted With Proposal)

The undersigned Bidder certifies that it is, at the time of bidding, and shall be, throughout the period of the contract, licensed under the provisions of Chapter 9, Division 3, of the Business and Professions Code of the State of California, to do the type of work contemplated in the Contract Documents. Bidder further certifies that it is skilled and regularly engaged in the general class and type of work called for in the Contract Documents.

The Bidder represents that it is competent, knowledgeable, and has special skills concerning the nature, extent, and inherent conditions concerning the work to be performed. Bidder further acknowledges that there are certain inherent conditions existent in the construction of the project which may create, during the construction program, unsafe conditions hazardous to persons and property. Bidder expressly acknowledges that it is aware of such risks and that it has the skill and experience to foresee and to adopt protective measures to adequately and safely perform the construction work with respect to such hazards.

A. ESSENTIAL REQUIREMENTS FOR QUALIFICATION

If the answer to any of questions 1 through 4 is "yes", or if the answer to question 5 is "no", the Bidder will be deemed ineligible or not responsible for purposes of the Contract.

1. Has your contractor's license been revoked at any time in the last five (5) years?
 Yes No

2. Has a surety firm completed a contract on your behalf, or paid for completion because your firm was default terminated by the project owner within the last five (5) years?
 Yes No

3. At the time of submitting this qualification form, is your firm ineligible to bid on or be awarded a public works contract, or perform as a subcontractor on a public works contract, pursuant to either Labor Code section 1777.1 or Labor Code section 1777.7?
 Yes No

4. At any time during the last five (5) years, has your firm, or any of its owners or officers been convicted of a crime involving the awarding of a contract of a government construction project, or the bidding or performance of a government contract?
 Yes No

5. The Bidder has been engaged in the contracting business, under the present business name for at least 5 years and has experience in work of a nature similar to this project?
 Yes No

B. COMPANY EXPERIENCE

The Bidder, as a Contractor, has never failed to satisfactorily complete a contract awarded to it, except as follows:

For the County of San Mateo to consider the Bidder properly experienced in work of similar nature to this project, the Bidder must list at least one project that involved.

Any projects listed below which are not as defined above will not be considered by the County of San Mateo in meeting this experience requirement.

Bidder also certifies that Bidder self-performed at least fifty percent (50%) of the Work when acting as a general contractor or ten percent (10%) of the Work when acting as a subcontractor on each of the projects listed below. The County of San Mateo considers this level of past self-performance demonstrates a benefit to a Project in terms of better control of cost, schedule and safety.

If the Bidder is a Joint Venture of two or more companies, each participant in the Joint Venture shall meet this prior project experience requirement and provide project information for each Joint Venture participant in the format below.

1. **Project Name & Description:** _____

Owner: _____

General Contractor or Subcontractor for Project: _____

Work Performed: _____

Total Construction Cost: \$ _____

Dollar Amount of Bidder's Work: \$ _____

Construction Time: _____ **Calendar Days**

Owner's Representative: _____

Owner's Telephone No.: _____

Date of Substantial Completion: _____

2. **Project Name & Description:** _____

Owner: _____
General Contractor or Subcontractor for Project: _____
Work Performed: _____
Total Construction Cost: \$ _____
Dollar Amount of Bidder's Work: \$ _____
Construction Time: _____ **Calendar Days**
Owner's Representative: _____
Owner's Telephone No.: _____
Date of Substantial Completion: _____

3. **Project Name & Description:** _____

Owner: _____
General Contractor or Subcontractor for Project: _____
Work Performed: _____
Total Construction Cost: \$ _____
Dollar Amount of Bidder's Work: \$ _____
Construction Time: _____ **Calendar Days**
Owner's Representative: _____
Owner's Telephone No.: _____
Date of Substantial Completion: _____

4. **Project Name & Description:** _____

Owner: _____

General Contractor or Subcontractor for Project: _____

Work Performed: _____

Total Construction Cost: \$ _____

Dollar Amount of Bidder's Work: \$ _____

Construction Time: _____ **Calendar Days**

Owner's Representative: _____

Owner's Telephone No.: _____

Date of Substantial Completion: _____

5. **Project Name & Description:** _____

Owner: _____

General Contractor or Subcontractor for Project: _____

Work Performed: _____

Total Construction Cost: \$ _____

Dollar Amount of Bidder's Work: \$ _____

Construction Time: _____ **Calendar Days**

Owner's Representative: _____

Owner's Telephone No.: _____

Date of Substantial Completion: _____

The undersigned hereby states that all representations regarding the Bidder's Company Experience are correct and true.

Signed this _____ day of _____, 20____

Bidder's Company Name

Authorized Signature

Date

Name and Title of Signatory

AGREEMENT

THIS AGREEMENT, made and entered into this _____ day of _____, 2021, by and between the COUNTY OF SAN MATEO, State of California, hereinafter called the "County" and _____, hereinafter called the "Contractor,"

W I T N E S S E T H:

THAT, for and in consideration of the mutual covenants and agreements hereinafter contained, the parties hereto agree as follows:

I. Services to be performed by Contractor: The Contractor will at his own proper cost and expense, do all the work and furnish all the labor, materials, equipment and utilities necessary to perform and complete in good workmanlike and substantial manner, and to the satisfaction of the Director of Public Works of the County of San Mateo, hereinafter called "Engineer," for the project

**GAZOS CREEK ROAD REPAIR PROJECT
TOTAL PROJECT APPROXIMATELY 3.3 MILES IN LENGTH
WITH APPURTENANT WORK THERETO
IN SAN MATEO COUNTY**

**COUNTY PROJECT NO. YY003
PROJECT FILE NO. S5045**

**FEMA-4558-DR-CA
PROJECT NO: 155545 FIPS NO: 081-99081-00**

and all in strict accordance with the Plans, Specifications, Notice to Contractors, Special Provisions and Proposal on file in the office of the Director of Public Works, which said Plans, Specifications, Notice to Contractors, Special Provisions and Proposal are hereby specifically referred to and by such reference made a part thereto.

II. Payments: The Contractor will receive and accept and the County will pay the prices specified in the Contractor's Proposal, dated _____, 2021, on file in the office of the Director of Public Works of the County of San Mateo and by

reference made a part of this Agreement, as full compensation for furnishing all labor, materials and equipment for doing all the work contemplated and embraced in this Agreement; the Contractor assumes any and all loss or damage arising out of the nature of the work aforesaid, or from the action of the elements, or from any unforeseen difficulties or obstructions which may arise or be encountered in the prosecution of the work until its acceptance by the County, and for all risks of every description connected with the work, and also assumes any and all expenses incurred by or in consequence of the suspension or discontinuance of work and for well and faithfully completing the work, and the whole thereof, in the manner and to the Plans, Specifications and Special Provisions and requirements of the Engineer hereunder. The Contractor shall guarantee all materials and workmanship for a period of one (1) year from date of acceptance of the project by the Director of Public Works. Any defects due to faulty materials, method of installation or workmanship within that period shall be repaired by the Contractor promptly upon notice by the Engineer, at the expense of the Contractor.

It is distinctly understood that the estimate set forth in the Notice to Contractors is only an approximation of the amount of work to be done and the County does not expressly or by implication agree that the actual amount of work will correspond with the amount set forth therein, and payment shall be made to the Contractor as above set forth.

Payment to the Contractor shall be made progressively by the County for the work and materials furnished under this Agreement in accordance with the provisions of Section 9 of the Special Provisions portion of these Contract documents.

III. Term: Time is of the essence in the Agreement, and the work to be performed hereunder shall be completed within

FIFTEEN (15) WORKING DAYS

from the date of commencement of the work, which commencement shall be within **TEN (10) CALENDAR DAYS** after receiving Notice to Proceed from the Engineer.

IV. Termination: This Contract is subject to termination as provided by Section 4410 and Section 4411 of the Government Code of the State of California, being portions of the Emergency Termination of Public Contracts Act of 1949. In the

event that the Contract is terminated pursuant to said sections, compensation to the Contractor shall be determined on the basis of the reasonable value of the work done, including preparatory work. As an exception to the foregoing, in the case of any fully completed separate item or portion of the work for which there is a separate Contract price, the Contract price shall control.

V. Relationship of Parties: Contractor agrees and understands that the work/services performed under this Agreement are performed as independent contractor and not as an employee of the County and that Contractor acquires none of the rights, privileges, powers, or advantages of County employees.

VI. Merger Clause: This Agreement, together with the Notice to Contractors, the Contractor's Proposal, the Plans, Specifications and Special Provisions and the Payment and Performance Bonds form the Contract, and said documents incorporated herein by reference become as fully a part of the Contract as if hereto attached or herein set forth in full. The Standard Specifications of the County of San Mateo, State of California, which, except as specifically noted in the County Contract documents and specifications, are identical with the Standard Specifications of the State of California, Department of Transportation, 2018 edition, and are on file with the County Manager/Clerk of the Board of Supervisors, County of San Mateo, are incorporated herein by reference as a part of the Contract documents and shall apply to this project except where the terms of this Agreement or other Contract documents are inconsistent therewith, in which case the provisions of this Contract shall prevail.

This Agreement constitutes the sole Agreement of the parties hereto and correctly states the rights, duties, and obligations of each party as of this document's date. Any prior agreement, promises, negotiations, or representations between the parties not expressly stated in this document are not binding. All subsequent modifications shall be in writing and signed by the parties.

VII. Surety Bonds: The performance of this Contract is secured by a "Payment" Surety Bond in the sum of one hundred percent (100%) of the Contract bid, and a "Performance" Surety Bond in the sum of one hundred percent (100%) of the

Contract bid. "Payment" and "Performance" Surety Bonds have been approved as to form by County Counsel, of which samples of same are attached as Appendix C in the Special Provisions.

VIII. Insurance: The Contractor shall not commence work under this Contract until he has obtained all insurance required under this paragraph and such insurance has been approved by the County, nor shall the Contractor allow any subcontractor to commence work on his subcontract until all similar insurance required of the subcontractor has been so obtained. The Contractor shall furnish County with certificates of insurance evidencing the required coverage, and there shall be a specific contractual liability endorsement extending the Contractor's coverage to include the contractual liability assumed by the Contractor pursuant to this Contract. Certificates of Insurance shall be filed with the County within **TEN (10) WORKING DAYS** after award of the contract. These certificates shall specify or be endorsed to provide that **THIRTY (30) CALENDAR DAYS'** notice must be given, in writing, to County of any pending change in the limits of liability or of any cancellation or modifications of the policy.

A. Worker's Compensation and Employer's Liability Insurance

The Contractor shall have in effect during the entire life of this Contract, Worker's Compensation and Employer's Liability Insurance providing full statutory coverage; and in case any work is sublet, the Contractor shall require all subcontractors similarly to provide Worker's Compensation and Employer's Liability Insurance to full statutory limits. In signing this Contract, the Contractor makes the following certifications, required by Section 1861 of the Labor Code:

"I am aware of the provisions of Section 3700 of the Labor Code which requires every employer to be insured against liability for Worker's Compensation or to undertake self-insurance in accordance with the provisions of the code, and I will comply with such provisions before commencing the performance of the work of this Contract."

B. Liability Insurance

The Contractor shall take out and maintain during the life of this Contract such Bodily Injury Liability and Property Damage Liability Insurance as shall

comply with Section 7-1.05, "Indemnification," and Section 7-1.06, "Insurance," of the Standard Specifications and protect him/her and any subcontractor performing work covered by this Contract, from claims for damages for bodily injury, including accidental death, as well as from claims for property damage including third party property damage, to include coverage on property in the care, custody and control of the Contractor, and also including coverage for what are commonly known as the "X, C and U" exclusions (having to do with blasting, collapse and underground property damage), which may arise from the Contractor's operations under this Contract, whether such operations be by himself/herself or by any subcontractor or by anyone directly or indirectly employed by either of them and the amounts of such insurance shall be **ONE MILLION DOLLARS (\$1,000,000)** combined single bodily injury and property damage for each occurrence. The County of San Mateo, Federal Emergency Management Agency, and their officers, agents, servants and employees, shall be named as additional insureds on any such policies of insurance, which shall also contain a provision stating that the insurance afforded thereby to the County of San Mateo, and their officers, agents, servants and employees, shall be primary insurance to the full limits of liability of the policy, and that if the County of San Mateo, Federal Emergency Management Agency or their officers and employees, have other insurance against a loss covered by such policy, such other insurance shall be excess insurance only.

Such statements, mentioned above, shall be included on a separate endorsement to be submitted to the County with the Certificate of Insurance.

Such insurance shall include:

- 1) Comprehensive General Liability \$1,000,000**
- 2) Motor Vehicle Liability Insurance \$1,000,000**

- C.** In case of the breach of any provision of this Article, the County, at its option, may take out and maintain at the expense of the Contractor, or subcontractor, such insurance as the County may deem proper and may deduct

the cost of taking out and maintaining such insurance from any sums which may be due, or become due, to the Contractor, under this Contract.

D. Hold Harmless

The Contractor's attention is directed to Section 7-1.05, "Indemnification," and Section 7-1.06, "Insurance," of the Standard Specifications.

The provisions contained in Section 7-1.05, "Indemnification," and Section 7-1.06, "Insurance," of the Standard Specifications of the State of California, Department of Transportation, shall be applicable with the understanding that where said provisions specifically refer to the State of California, a department or division of the State or an official, officer or employee of the State, said provision shall be interpreted to refer to the County of San Mateo, and all officers, agents, servants and employees thereof connected with the work, including but not limited to the Director of Public Works, their duly authorized representatives, other appropriate department, division, official, officer or employee of the County of San Mateo, and the Federal Emergency Management Agency.

The provisions of Section 7-1.05, "Indemnification," and Section 7-1.06, "Insurance," of the Standard Specifications are superseded by the following:

"To the full extent permitted by law, Contractor shall indemnify and save harmless the County, the Federal Emergency Management Agency, its officers, employees, and servants from all claims, suits, or actions of every name, kind, and description, brought for, or on account of:

1. Injuries to or death of any person, including Contractor, its officers, employees and servants, or
2. Damage to any property of any kind whatsoever and to whomsoever belonging, or
3. Any sanctions, penalties or claims of damages resulting from Contractor's failure to comply with applicable laws, or
4. Any other loss or cost resulting from the contractor's negligent or reckless acts or omissions or willful misconduct in connection with the performance of any work required of Contractor or payments made pursuant to this Agreement, provided that this shall not apply to injuries or damages for which the County has been found in a court of competent jurisdiction to be liable by reason of its own

negligence or willful misconduct.

The duty of Contractor to indemnify and save harmless, as set forth herein, shall include the duty to defend, as set forth In Section 2778 of the California Civil Code.

The obligations set forth in this Section shall continue beyond the term of this Agreement as to any act or omission which occurred during or under this Agreement.”

E. Compensation

All insurance required by the paragraphs of this section shall be obtained and maintained by the Contractor at Contractor’s own expense and County shall not compensate Contractor for said insurance expenses other than as they are included in the Contract prices the County pays for the various items of work.

F. Nothing herein contained shall be construed as limiting in anyway the extent to which the Contractor may be held responsible for payments of damages resulting from his operation.

IX. Prevailing Wages: Contractor hereby agrees to pay not less than prevailing rates of wages, which are effective on the date the Notice to Contractors is issued for each craft or type of workman or mechanic needed to execute the Contract as provided for by the County for the performance of public work., and be responsible for compliance with all the provisions of:

- a. Section 7-1.01A(2), “Prevailing Wage,” of the Standard Specifications and the Federal Requirements section of these Special Provisions. More specifically, reference is made to page FR-18, “Federal Wage Rates (North County)”; and
- b. California Labor Code, Article 2-Wages, Chapter 1, Part 7, Division 2, Section 1770 et seq. and Section 1810 et seq., and particularly Section 1775 and 1776(a) thereof. A copy of the prevailing wage scale established by the Department of Industrial Relations is on file in the office of the Director of Public Works, and available at www.dir.ca.gov/DLSR or by phone at 415-703-4774. California Labor Code Section 1776(a)

requires each contractor and subcontractor to keep accurate payroll records of trades workers on all public works projects and to submit copies of certified payroll records upon request.

Additionally, pursuant to State Senate Bill SB 854 (Stat. 2014, chapter 28), effective January 1, 2015:

- No contractor or subcontractor may be listed on a bid proposal for a public works project (submitted on or after March 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5 [with limited exceptions from this requirement for bid purposes only under Labor Code section 1771.1(a)].
- No contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.
- This project is subject to compliance monitoring and enforcement by the Department of Industrial Relations.

X. California Labor Code: The Contractor expressly covenants and agrees to comply with all the provisions of the Labor Code of the State of California limiting the hours of labor on public works to eight (8) hours during any one calendar day, and forty (40) hours in any one calendar week, requiring the payment of not less than the prevailing wage rates, and further agrees to the forfeitures provided for in said Labor Code and as set forth in Section 7, "Legal Relations and Responsibility to the Public," of the Standard Specifications and all amendments thereto, in the event of a violation of any of the provisions thereof during the course of execution of this Contract.

The Contractor expressly agrees to be responsible for compliance with all the provisions of Sections 1776 and 1777.5 of the California Labor Code.

XI. Non-Discrimination and Other Requirements:

a. General Non-discrimination:

No person shall be excluded from participation in, denied benefits of, or be subject to discrimination under this Agreement on the basis of their race, color, religion, national origin, ancestry, age, disability (physical or mental), sex, sexual orientation, gender identity, marital or domestic partner status, religion, political beliefs or affiliation, familial or parental status (including pregnancy, childbirth or

related conditions), medical condition (including cancer-related), military service, or genetic information. Contractor shall ensure full compliance with Federal, state and local laws, directives and executive orders regarding non-discrimination for all employees and Subcontractors under this Agreement.

b. Equal Employment Opportunity:

Contractor shall ensure equal employment opportunity based on objective standards of recruitment, classification, selection, promotion, compensation, performance evaluation, and management relations for all employees under this Agreement. Contractor's equal employment policies shall be made available to County upon request.

c. Section 504 of the Rehabilitation Act of 1973:

Contractor shall comply with Section 504 of the Rehabilitation Act of 1973, as amended, which provides that no otherwise qualified individual with a disability shall, solely by reason of a disability, be excluded from the participation in, be denied the benefits of, or be subjected to discrimination in the performance of any services this Agreement. This Section applies only to contractors who are providing services to members of the public under this Agreement.

d. Compliance with County's Equal Benefits Ordinance:

Contractor shall comply with all laws relating to the provision of benefits to its employees and their spouses or domestic partners, including, but not limited to, such laws prohibiting discrimination in the provision of such benefits on the basis that the spouse or domestic partner of the Contractor's employee is of the same or opposite sex as the employee.

e. Discrimination Against Individuals with Disabilities:

The nondiscrimination requirements of 41 C.F.R. 60-741.5(a) are incorporated into this Agreement as if fully set forth here, and Contractor and any subcontractor shall abide by the requirements of 41 C.F.R. 60-741.5(a). This regulation prohibits discrimination against qualified individuals on the basis of disability and requires affirmative action by covered prime contractors and subcontractors to employ and advance in employment qualified individuals with

disabilities.

f. History of Discrimination:

Contractor certifies that no finding of discrimination has been issued in the past 365 days against Contractor by the Equal Employment Opportunity Commission, the California Department of Fair Employment and Housing, or any other investigative entity. If any finding(s) of discrimination have been issued against Contractor within the past 365 days by the Equal Employment Opportunity Commission, the California Department of Fair Employment and Housing, or other investigative entity, Contractor shall provide County with a written explanation of the outcome(s) or remedy for the discrimination prior to execution of this Agreement. Failure to comply with this Section shall constitute a material breach of this Agreement and subjects the Agreement to immediate termination at the sole option of the County.

g. Reporting; Violation of Non-discrimination Provisions:

Contractor shall report to the County Manager the filing in any court or with any administrative agency of any complaint or allegation of discrimination on any of the bases prohibited by this Section of the Agreement or the Section titled "Compliance with Laws". Such duty shall include reporting of the filing of any and all charges with the Equal Employment Opportunity Commission, the California Department of Fair Employment and Housing, or any other entity charged with the investigation or adjudication of allegations covered by this subsection within 30 days of such filing, provided that within such 30 days such entity has not notified Contractor that such charges are dismissed or otherwise unfounded. Such notification shall include a general description of the circumstances involved and a general description of the kind of discrimination alleged (for example, gender-, sexual orientation-, religion-, or race-based discrimination).

Violation of the non-discrimination provisions of this Agreement shall be considered a breach of this Agreement and subject the Contractor to penalties, to be determined by the County Manager, including but not limited to:

- i) Termination of this Agreement;
- ii) Disqualification of the Contractor from bidding on or being awarded

- a County contract for a period of up to 3 years;
- iii) Liquidated damages of \$2,500 per violation; and/or
- iv) Imposition of other appropriate contractual and civil remedies and sanctions, as determined by the County Manager.

To effectuate the provisions of this paragraph, the County Manager shall have the authority to:

- i) Examine Contractor's employment records with respect to compliance with this paragraph;
- ii) Offset all or any portion of the amount described in this paragraph against amounts due to Contractor under the Contract or any other Contract between Contractor and County.

Contractor shall report to the County Manager the filing by any person in any court of any complaint of discrimination or the filing by any person of any and all charges with the Equal Employment Opportunity Commission, the Fair Employment and Housing Commission or any other entity charged with the investigation of allegations within 30 days of such filing, provided that within such 30 days such entity has not notified Contractor that such charges are dismissed or otherwise unfounded. Such notification shall include the name of the complainant, a copy of such complaint and a description of the circumstance. Contractor shall provide County with a copy of its response to the Complaint when filed.

Compliance with Equal Benefits Ordinance. With respect to the provisions of employee benefits, Contractor shall comply with the County Ordinance which prohibits contractors from discriminating in the provision of employee benefits between an employee with a domestic partner and an employee with a spouse.

XII. Compliance with County Employee Jury Service Ordinance:

Contractor shall comply with Chapter 2.85 of the County's Ordinance Code, which states that Contractor shall have and adhere to a written policy providing that its employees, to the extent they are full-time employees and live in San Mateo County, shall receive from the Contractor, on an annual basis, no fewer than five days of regular pay for jury service in San Mateo County, with jury pay being provided only for each day

of actual jury service. The policy may provide that such employees deposit any fees received for such jury service with Contractor or that the Contractor may deduct from an employee's regular pay the fees received for jury service in San Mateo County. By signing this Agreement, Contractor certifies that it has and adheres to a policy consistent with Chapter 2.85. For purposes of this Section, if Contractor has no employees in San Mateo County, it is sufficient for Contractor to provide the following written statement to County: "For purposes of San Mateo County's jury service ordinance, Contractor certifies that it has no full-time employees who live in San Mateo County. To the extent that it hires any such employees during the term of its Agreement with San Mateo County, Contractor shall adopt a policy that complies with Chapter 2.85 of the County's Ordinance Code." The requirements of Chapter 2.85 do not apply if this Agreement's total value listed in the Section 16 is less than one-hundred thousand dollars (\$100,000), but Contractor acknowledges that Chapter 2.85's requirements will apply if this Agreement is amended such that its total value meets or exceeds that threshold amount.

XIII. Termination of Agreement: The Contract may be terminated by the County in the event the Contractor should be adjudged bankrupt, or if he should make a general assignment for the benefit of his creditors, or if a receiver should be appointed on account of his insolvency, or if he or any of his subcontractors should violate any of the provisions of the Contract, or if he should persistently or repeatedly refuse, or should fail, except in cases where extension of time is provided, to furnish enough properly skilled workmen or proper materials, or if he should fail to make prompt payment to subcontractors, or for materials or labor, or persistently disregard laws, ordinances, or the instructions of the Engineer. In the event of any of the foregoing conditions, the Engineer is authorized and directed to serve written notice upon the Contractor and his Surety of its intention to terminate the Contract, such notice to contain the reasons for action and unless within **TWO (2) CALENDAR DAYS** after serving of such notice such conditions shall be remedied and satisfactory arrangements for continuation be made, the Contract shall, upon expiration of **TWO (2) CALENDAR DAYS**, cease and terminate. In the event of any such termination, the Engineer may take over the work and prosecute the same to completion by Contract or by any other

method he may deem advisable, and at the expense of the Contractor, and the Contractor and his Surety shall be liable to the County for any excess cost occasioned thereby, and in such event, the County may without liability to so doing take possession of and utilize such materials, appliances, plant and other property belonging to the Contractor as may be on the site of the work, and necessary therefore. In such cases, the Contractor shall not be entitled to receive any further payment until the work is completed.

XIV. Compliance with Laws: The Contractor shall comply with all existing and future State and Federal and regulating laws and all ordinances and regulations of the County of San Mateo which in any manner affect those engaged or employed in the work, or the materials used in the work, or which in any way affect the conduct of the work, and of all such orders and decrees of bodies or tribunals having any jurisdiction or authority over the same.

Controlling Law: The validity of this Agreement and of its terms or provisions, as well as the rights and duties of the parties hereunder, the interpretation, and performance of this Agreement shall be governed by the laws of the State of California.

The Contractor agrees to comply with Federal requirements and procedures in accordance with 2 CFR, Part 200, Uniform Administrative Requirements, Cost Principles, and Audit Requirements for Federal Awards. Furthermore, the Contractor shall require and enforce similar compliance with all subcontractors.

XV. Contract Assignability: Neither party to the Contract shall assign the Contract or sublet it as a whole without written consent of the other, nor shall the Contractor assign any monies due or to become due to him hereunder without the previous written consent of the County. The Contractor shall neither mortgage nor convey title to equipment or material to be used in this work, without the written permission of the County.

- (a) Contractor will assure that any authorized subcontracts with a third party for services complies with all terms and conditions set forth in this Agreement and pursuant to the requirements of applicable federal, state and local law, including but not limited to Title 2 of the CFR.

- (b) Debarment and Suspension: Contractor will assure that as provided in CFR, Title 2 as applicable, that it must not award subcontracts with at any time to any party that is debarred or suspended or is otherwise excluded from or ineligible for participation in federal assistance programs.
- (c) Procurement of Sub-contractors: Contractor's procurement procedures must conform to applicable federal, state and local law including procedures outlined in Title 2 of the CFR. In the event of any conflict between federal, state, and local requirements, the most restrictive requirement must be applied.
- (d) Monitoring: Contractor will be responsible for managing and monitoring routine operations of services performed under this Agreement including each project, program, sub grants or any other function supported by Contractor's sub-contractors/sub-grantees to ensure compliance with all applicable terms and conditions of this Agreement, including the requirements in Title 2 of the CFR . If Contractor at any time discovers that services under this Agreement have not been used in accordance with the terms and conditions of this Agreement including federal, state and local law, Contractor will take action to recover such funding.
- (e) In addition to complying with the Uniform Rules and the enabling laws, implementing regulations, and FEMA policies for a grant or cooperative agreement program, the contractor must also comply with all other applicable Federal laws, regulations, and executive orders, including those contained in the Department of Homeland Security Standard Terms and Conditions in effect at the time federal financial assistance funds are awarded.

XVI. COVID-19: This Provision relates to issues associated with the Novel Coronavirus Disease 2019 (COVID-19) and shall supersede any other conflicting sections or provisions of this Contract and its attachments. The ongoing COVID-19 pandemic may impact the County's ability to proceed with this Project.

Although this Project is proceeding as an Essential Infrastructure Project as determined by the County Board of Supervisors/County Manager, this determination could change in the future based on Health Orders issued by the San Mateo County Health Officer or State of California, or future determinations of the County Board of

Supervisors/County Manager. Should future Health Orders or the County Board of Supervisors/County Manager directives preclude the Project from proceeding as scheduled, the County reserves the right to:

- Cancel the Project, terminate the Contractor's work once the Contractor has safely secured the work area, and compensate the Contractor for work completed and materials purchased prior to cancellation of the Project and labor and materials, as approved by the Engineer, required to safely secure the work area such that work can be discontinued on the Project; **or**
- The County and Contractor may reach a mutually agreeable extension for completion of the Project such that the work can resume after being halted provided it complies with all Health Orders issued by the Health Officer of the County of San Mateo or the State of California and as approved by the County Board of Supervisors/County Manager.

It is the Contractor's obligation and responsibility to ensure that all work associated with this Project complies with all current Orders of the Health Officer of the County of San Mateo related to the Novel Coronavirus Disease 2019 (COVID-19). The County of San Mateo assumes no responsibility for work performed by Contractor that is not in compliance with all current Orders. The Contractor is advised to review the Orders of the Health Officer of the County of San Mateo, which can be found at the following link:

<https://www.smchealth.org/post/health-officer-statements-and-orders>

XVII. Contract Materials: The County hereby promises and agrees with the said Contractor to employ and does hereby employ the said Contractor to provide the materials, unless otherwise specified, and to do the work according to the terms and conditions herein contained and referred to, for the prices aforesaid and hereby contracts to pay the same at the time, in the manner and upon the conditions above set forth, and the said parties for themselves, their heirs, executors, administrators, successors, and assigns, do hereby agree to the full performance of the covenants herein contained.

XVIII. Retention of Records, Right to Monitor and Audit:

- A.** The CONTRACTOR shall retain all project records for a minimum of three years after all agency projects funded under this grant award (not just this present contract) are completed. In addition to this storage requirement, the contractor shall provide an electronic copy of all records in a bon fide electronic documents management format which provides unalterable copies. This requirement applies to the prime contractor and all sub contractor's project records. However, it is the responsibility of the prime contractor to provide all of the records, both the prime contractor and subcontractor's records. CONTRACTOR shall be subject to the examination and/or audit by County, a Federal grantor agency, and the State of California.
- B.** Reporting and Record Keeping: CONTRACTOR shall comply with all program and fiscal reporting requirements set forth by appropriate Federal, State and local agencies and as required by the COUNTY.
- C.** CONTRACTOR agrees upon reasonable notice to provide to COUNTY, to any Federal or State department having monitoring or review authority, to COUNTY's authorized representatives, and/or their appropriate audit agencies upon reasonable notice, access to and the right to examine all records and documents necessary to determine compliance with relevant Federal, State, and local statutes, rules and regulations, and this Agreement, and to evaluate the quality, appropriateness and timeliness of services performed.
- D.** The contractor agrees to provide San Mateo County, the FEMA Administrator, the Comptroller General of the United States, or any of their authorized representatives access to any books, documents, papers, and records of the Contractor which are directly pertinent to this contract for the purposes of making audits, examinations, excerpts and transcriptions.
- E.** The Contractor agrees to permit any of the foregoing parties to reproduce by any means whatsoever or to copy excerpts and transcriptions as reasonably needed.
- F.** The Contractor agrees to provide the FEMA Administrator or his

authorized representative access to construction or other work sites pertaining to the work being completed under the contract

XIX. Notices: Any notice, request, demand or other communication required or permitted hereunder shall be deemed to be properly given when both: (1) transmitted via email to the email address listed below or transmitted via facsimile, if available, to the number listed below; and (2) sent to the physical address listed below by either being deposited in the United States mail, postage prepaid, or deposited for overnight delivery, charges prepaid, with an established overnight courier that provides a tracking number showing confirmation of receipt.

In the case of County, to:

James C. Porter, Director of Public Works
 County of San Mateo
 555 County Center, 5th Floor
 Redwood City, CA 94063-1665
 Facsimile: 650-361-8220
 Email: jporter@smcgov.org

In the case of Contractor, to:

(Contractor Name)
 (Contractor Address)
 (City, State Zip)
 Facsimile:
 Email:

XX. Contract Amount and Change Orders:

A. Contract Amount

The amount payable to Contractor under the terms of this agreement is _____ DOLLARS (\$_____).

B. Change Orders

The Board of Supervisors has authorized the Director of Public Works to execute change orders to modify the scope of work provided under this agreement, and to increase the County's maximum fiscal obligation to correspond to those changes. The Board of Supervisors has directed that in the event of change orders, the County's maximum fiscal obligation shall not exceed

_____ DOLLARS (\$_____). Any payments in excess of the amount authorized by the Board of Supervisors will require additional approval of the Board of Supervisors.

XXI. Proprietary Rights and Confidentiality: The requirements of this Agreement pertaining to the protection of proprietary rights and confidentiality shall survive termination of this Agreement.

XXII. Electronic Signature: Both County and Contractor wish to permit this Agreement and future documents relating to this Agreement to be digitally signed in accordance with California law and County's Electronic and Facsimile Signatures Administrative Memo (B-29). Any party to this Agreement may revoke such agreement to permit electronic signatures at any time in relation to all future documents by providing notice pursuant to this Agreement.

IN WITNESS WHEREOF, the parties to these presents have hereunto set their hands the year and date first above written.

“County”

COUNTY OF SAN MATEO
State of California

BY: _____

**President, Board of Supervisors
County of San Mateo**

ATTEST:

Michael Callagy, County Manager/
Clerk of the Board of Supervisors

“Contractor”

Name of Contractor

BY: _____

(Authorized Signature and Seal of Bidder)