Grading for Chamberlain Project Lots 5-8, in cubic yards (CY)

DATE: 6/25/20

PLN APPROVAL (Source	Truck Trips based on 12cy = 1 truck load (Source: Final EIR)		
TOTAL	Cut	Fill	
Lots 5-8	4,700	700	0
Lots 9, 10	300	2,900	0
Lot 11	1,200	1,000	0
Overall - Import Only	0	900	75
	6,200	5,500	75

Note: Final EIR assumes balanced Grading for Lots and only calculates truck trip for imported materials (Rock, etc)

BLD PROPOSAL	FOUNDATION		SLOPE REPAIRRevised on BLD Plans					
						Offhaul (Source: Geo		
Lots 5-8	Cut	Fill	Cut Spoils after Bala	Cut - Slope Repair	Balanced Fill	letter 7/8/17)	Offhaul Trips	
5	1,220	0		520	-	-	•	
6	1,450	0		580	-	-	-	
7	1,560	90	1,470	660	-	-	-	BKF Agrees p
8	1,000	230	770	1120	-	-	-	7/17/19 Email
TOTAL	5,230	320	4,910	2,880		7,790	649	No Import Tri

per

Grading Quantities			
	Approved	Proposed	Difference
Cut (5-8)	4,700	5,230	530
Fill (5-8)	700	320	-380
Cut (9-11)	1,500	1,380	-120
Fill (9-11)	3,900	2,180	-1,720

TRUCK TRIPS			
On & Off Haul Trips	Approved Trips	Proposed Trips	
Lots 5-8	37.5	649.2	Off Haul On
Lots 9-11	37.5	66	Import Only
	75	715.2	