# 3252 MIDDLEFIELD ROAD

MENLO PARK, CA

SAN MATEO COUNTY DESIGN REVIEW SUBMITTAL AUGUST 20, 2018





VICINITY MAP

#### SHEET INDEX:

A000 COVER SHEET A001 EXISTING SITE PLAN A002 SITE CONTEXT A003 FLOOR AREA RATIO (F.A.R.) A004 PROPOSED SITE PLAN A005 FIRST FLOOR PLAN A006 SECOND FLOOR PLAN A007 THIRD FLOOR PLAN A08 ROOF PLAN A009 NORTH ELEVATION A010 WEST ELEVATION A011 SOUTH ELEVATION A012 EAST ELEVATION A013 SECTIONS A014 SECTIONS A015 COLOR AND MATERIALS TM-1 TITLE SHEET TM-2 DEMOLITION PLAN TM-3 UNIT DIMENSION PLAN FIRST FLOOR TM-4 UNIT DIMENSION PLAN SECOND FLOOR TM-5 UNIT DIMENSION PLAN THIRD FLOOR TM-6 CONCEPTUAL GRADING AND DRAINAGE PLAN TM-7 EXISTING PAVED AREA EXHIBIT TM-8 PROPOSED PAVED AREA EXHIBIT TM-9 STANDARD DETAILS TM-10 STANDARD DETAILS ER-1 EROSION CONTROL PLAN ER-2 EROSION CONTROL DETAILS SW-1 STORMWATER POLLUTION PREVENTION PLAN SU1 TOPOGRAPHIC SURVEY L1 PLANTING PLAN L2 IRRIGATION PLAN

#### PROJECT INFORMATION:

1 LIGHTING SUMMARY

- ZONING: NMU / DR
- LOT AREA: 6,622 SF
- EXISTING: COMMERCIAL = 2,763 SF
- RESIDENTIAL DENSITY: ALLOWED: 60 du/ac = 9 UNITS PROPOSED =

RESIDENTIAL =

SETBACKS REQUIRED :


FRONT = SIDE = REAR =

SETBACKS PROVIDED: FRONT = SIDE = REAR =

> **COVER SHEET** A000

> > SDG Architects, Inc.







EXISTING SITE PLAN A001


SDG Architects, Inc.







3252 MIDDLEFIELD ROAD - EXISTING SITE





3262 MIDDLEFIELD ROAD






3240 MIDDLEFIELD ROAD




MIDDLEFIELD STREETSCAPE

SITE CONTEXT A002




FIRST FLOOR



SECOND FLOOR


3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018





THIRD FLOOR

FLOOR AREA RATIO (F.A.R.)



 LOT COVERAGE SQUARE FOOTAGES

 TOTAL SITE AREA
 6,622 SQ. FT.

 ALLOWED 80% x 6,622
 5,298 SQ. FT.

 TOTAL LOT COVERAGE
 \* 5,702 SQ. FT.

 LOT COVERAGE

LOT COVERAGE CONCESSION OF 404 SQ.FT. REQUESTED



PROPOSED SITE PLAN A004


# PARKING CALCULATIONS REQUIRED PARKING COMMERCIAL 1 SPACE / 1000 SF 1330 SF / 1,000 SF : TRASH RESIDENTIAL 1 COVERED SPACE / UNIT **ENCLOSURE** 8 UNITS: G1 VISITOR 25% OF UNITS 8 UNITS x .25 : TOTAL PROVIDED PARKING: COMMERCIAL RESIDENTIAL VISITOR TOTAL 2 RISERS @ 5.50"-1 TREADS COMMERCIAL 1,330 S.F. ELEV.

3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018


. PROPERTY LINE .

FIRST FLOOR PLAN A005

UTILITIES




3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018 SECOND FLOOR PLAN A006



3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018

THIRD FLOOR PLAN A007





3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018

ROOF PLAN A008





SDG Architects, Inc.

NORTH ELEVATION A009





WEST ELEVATION A010

3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018






SOUTH ELEVATION

SDG Architects, Inc.





EAST ELEVATION A012




## **SECTION A**

3252 MIDDLEFIELD ROAD Menlo Park, CA

August 20, 2018

SECTION A013






SECTION B



SECTION A014



3252 MIDDLEFIELD ROAD Menlo Park, CA August 20, 2018

**COLORS AND MATERIALS** 

**DESCRIPTION** BOUNDARY PROPERTY LINE

RETAINING WALL LANDSCAPE RETAINING WALL

RAINWATER TIGHTLINE SUBDRAIN LINE TIGHTLINE

STORM DRAIN LINE

GAS LINE

PRESSURE LINE JOINT TRENCH

SET BACK LINE

EARTHEN SWALE

CATCH BASIN

JUNCTION BOX

AREA DRAIN

CURB INLET

STREET SIGN

SPOT ELEVATION

FLOW DIRECTION

TREE TO BE REMOVED

WATER LINE WATER METER WELDED WIRE FABRIC

BENCHMARK

CONTOURS

CONCRETE VALLEY GUTTER

STORM DRAIN MANHOLE

SANITARY SEWER MANHOLE

SANITARY SEWER LINE

**PROPOSED** 

~>· ~>· ~>

∭ св

∭ JB

 $\bigcirc_{\mathsf{SSMH}}$ 

**EXISTING** 

∭ JB

 $\bigcirc_{\rm SSMH}$ 

**+** 

222.57 INV

# AND 8 RESIDENTIAL UNITS 3252 MIDDLEFIELD ROAD MENLO PARK, CALIFORNIA

# SIXTH AVENUE (60') LANDS OF SANCHEZ

KEY MAP

1" = 20'

# **ABBREVIATIONS**

	TIDDIVE VIIIII	0110	
AB	ACCRECATE BASE	LF	LINEAR FEET
AC	AGGREGATE BASE ASPHALT CONCRETE	MAX	MAXIMUM
	ACCESSIBLE	MAA	
ACC	ACCESSIBLE AREA DRAIN BECINNING OF CURVE	MH	MANHOLE
AD	AREA DRAIN	MIN	MINIMUM
BC	BEGINNING OF CURVE	MON.	MONUMENT
B & D	AREA DRAIN BEGINNING OF CURVE BEARING & DISTANCE BENCHMARK	(N)	NEW
		ŇÓ.	NUMBER
BW/FG	BOTTOM OF WALL/FINISH	NTS	NOT TO SCALE
GRADE		NTS O.C.	ON CENTER
CB	CATCH BASIN CURB AND GUTTER CENTER LINE	O/ (PA) PED PIV	OVER
C & G	CURB AND GUTTER	(PA)	PLANTING AREA
C	CENTER LINE	NED.	PEDESTRIAN
© CPP	CORRUGATED PLASTIC PIPE	PIV	POST INDICATOR VALVE
011	(CHOOTH INTERIOR)	PIV PSS	PUBLIC SERVICES EASEMENT
co	(SMOOTH INTERIOR) CLEANOUT CLEANOUT TO GRADE	P33	
COTG	CLEANOUT TO ODADE	Ψ_	PROPERTY LINE
	CLEANOUT TO GRADE	PP	POWER POLE
CONC		PUE	PUBLIC UTILITY EASEMENT
CONST CONC COR	CONSTRUCT or -TION	PP PP PUE PVC R	POLYVINYL CHLORIDE
CONC COR	CONCRETE CORNER	R	RADIUS
CY	CUBIC YARD	RCP	REINFORCED CONCRETE PIPE
D	DIAMETER	RIM	RIM ELEVATION
DI	DROP INLET	RW	RAINWATER
DIP	CONSTRUCT OF —TION CONCRETE CORNER CUBIC YARD DIAMETER DROP INLET DUCTILE IRON PIPE EACH END OF CURVE EXISTING GRADE ELEVATIONS EDGE OF PAVEMENT EQUIPMENT EACH WAY EXISTING FACE OF CURB FINISHED FLOOR FINISHED FLOOR FINISHED FLOOR FINISHED FLOOR FINISHED FLOOR FINISHED SURFACE GAS GAS GAS OR GALIGE	R/W	RIGHT OF WAY SLOPE SEE ARCHITECTURAL DRAWINGS
EA	EACH	s'	SLOPE
EC	END OF CURVE	S.A.D.	SEE ARCHITECTURAL DRAWINGS SANITARY STORM DRAIN
EG	EXISTING GRADE	SAN	SANITARY
EL	ELEVATIONS	SD	STORM DRAIN
EP	EDGE OF PAVEMENT	SDMH	STORM DRAIN STORM DRAIN MANHOLE
EQ	EQUIPMENT	SHT	SHEET
EW	EACH WAY	S.L.D. SPEC	SHEET SEE LANDSCAPE DRAWINGS SPECIFICATION
(E)	FXISTING	SDEC.	SDECIFICATION
FC	FACE OF CURB	SS	SPECIFICATION SANITARY SEWER
FF	FINISHED ELOOP	33	CANITARY CEWER OF TANOUT
FG	FINISHED CRADE	SSCO SSMH	SANITARY SEWER CLEANOUT SANITARY SEWER MANHOLE
FH	FIDE HYDDANT	ST.	
FL	FLOW LINE	STA	STREET
FS	FINISHED SUBFACE	SIA	STATION
Ğ	GAS	31D	STANDARD
GA	GAS GAGE OR GAUGE GRADE BREAK	STD STRUCT T	STRUCTURAL
GB	ODADE DDEAM	<u>.</u> .	TELEPHONE
HDPE		†c_	TOP OF CURB
HDPE	HIGH DENSITY CORRUGATED	TEMP	TEMPORARY
HADIT	HIGH DENSITY CORRUGATED POLYETHYLENE PIPE HORIZONTAL HIGH POINT HUB & TACK INSIDE DIAMETER INVERT ELEVATION JUNCTION BOX	TP	TOP OF PAVEMENT
HORIZ	HURIZONTAL	TW/FG	TOP OF WALL/FINISH GRADE
HI PT	HIGH POINT	TYĖ	TIFICAL
H&T	HUB & TACK	VC	VERTICAL CURVE
ID	INSIDE DIAMETER	VCP	VITRIFIED CLAY PIPE
INV	INVERT ELEVATION	VERT	VERTICAL
JB	JUNCTION BOX	W./	MATTER

#### RETAINING WALL NOTES

- 1. TW/FG REPRESENTS FINISHED EARTHEN GRADE OR PAVEMENT ELEVATION AT TOP OF WALL, NOT ACTUAL TOP OF WALL MATERIAL. BW/FG REPRESENTS FINISH EARTHEN GRADE OR PAVEMENT ELEVATION AT BOTTOM OF WALL NOT INCLUDING FILL FOUNDATION. GRADES INDICATED ON THESE PLANS REFER TO THE FINISHED GRADES ADJACENT TO THE RETAINING WALL, NOT INCLUDING
- DIMENSIONS SHOWN IN BRACKETS SHOWN AS [X.X'] DENOTE THE EFFECTIVE WALL HEIGHT ONLY. THE ACTUAL WALL HEIGHT AND DEPTH MAY DIFFER DUE TO CONSTRUCTION REQUIREMENTS.
- REFER TO SPECIFIC WALL CONSTRUCTION DETAIL FOR STRUCTURAL ELEMENTS, FREEBOARD, AND EMBEDMENT.
- REFER TO ARCHITECTURAL, LANDSCAPE ARCHITECTURE, AND/OR STRUCTURAL PLANS FOR DETAILS, WALL ELEVATIONS, SUBDRAINAGE, WATERPROOFING, FINISHES, COLORS, STEEL REINFORCING, MATERIALS, ETC. PROVIDE CLIPS OR OTHER MEANS OF SECURING FINISH MATERIALS AS NECESSARY (WET SET INTO
- ALL RETAINING WALLS SHOULD HAVE A BACK-OF-WALL SUB-SURFACE DRAINAGE SYSTEM INCLUDING WEEPHOLES TO PREVENT HYDROSTATIC PRESSURE.
- 6. SEE DETAIL SHEET FOR SPECIFIC INFORMATION.
- 7. PROVIDE GUARDRAIL (WHERE APPLICABLE AND DESIGNED BY OTHERS) AS

CUBIC YARDS	WITHIN BUILDING FOOTPRINT	OUTSIDE BUILDING FOOTPRINT	TOTAL CUBIC YARDS				
CUT	5	30	35				
FILL	0	0	0				
EXPORT 35							
NOTE:							

TRENCHING. STRUCTURAL FOUNDATIONS OR PIERS. OR POOL EXCAVATION

(IF ANY), NOTE ADDITIONAL EARTHWORKS, SUCH AS KEYWAYS OR BENCHING MAY BE REQUIRED BY THE GEOTECHNICAL ENGINEER IN THE FIELD AT TIME OF CONSTRUCTION. CONTRACTOR TO VERIFY QUANTITIES.

# -FLAT OR SLOPING TOP TW/FG **EFFECTIVE** BW/FG

#### SURVEY NOTES

ALL DISTANCES AND DIMENSIONS ARE IN FEET AND DECIMALS OF A FOOT.

BUILDING FOOTPRINTS ARE SHOWN TO

AT DOOR THRESHOLD (EXTERIOR)

#### **EASEMENT NOTE**

EASEMENTS ARE SHOWN PER PRELIMINARY TITLE REPORT ISSUED BY CHICAGO TITLE COMPANY, ORDER NO. FWTO-4071700074-JJ, DATED AS OF MAY 10, 2017

#### **BENCHMARK**

BENCHMARK FD BRASS CAP IN WELL ELEVATION = 36.65' (NAVD 88)

#### SITE BENCHMARK

SURVEY CONTROL POINT MAG AND SHINER SET IN ASPHALT ELEVATION = 35.68' (NAVD 88)



FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116. . aabaya@leabraze.con

## SHEET INDEX

DEMOLITION PLAN DEMOLITION PLAN
UNIT DIMENSION PLAN-FIRST FLOOR
UNIT DIMENSION PLAN-SECOND FLOOR
UNIT DIMENSION PLAN-THIRD FLOOR
CONCEPTUAL DEVELOPMENT
EXISTING PAVED AREA EXHIBIT PROPOSED PAVED AREA EXHIBIT STANDARD DETAILS
COUNTY STANDARD DETAILS EROSION CONTROL PLAN EROSION CONTROL DETAILS STORMWATER POLLUTION PREVENTION PLAN SU-1 TOPOGRAPHIC SURVEY



VICINITY MAP

#### OWNER'S INFORMATION

OWNER:
ZACH TRAILER
1075 CURTIS STREET
MENLO PARK, CA 94025

APN: 060-092-140

#### REFERENCES

THIS IMPROVEMENT PLANS IS SUPPLEMENTAL TO:

1. TOPOGRAPHIC SURVEY BY LEA & BRAZE ENGINEERING
,INC. ENTILED:

"TOPOGRAPHIC SURVEY"

3252 MIDDLEFIELD ROAD
MENLO PARK, CA
DATED: 08-01-17
,ISP# 2170840 JOB#: 2170840

2. SITE PLAN BY SDG ARCHITECTS INC. ENTITLED: "BUILDING CONCEPT"
3252 MIDDLEFIELD ROAD
MENLO PARK, CA
DATED: 07-07-17

THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM.

#### EXISTING SITE DEVELOPMENT INFORMATION

AREA (GROSS): 0.152 ACRES (6,622 S.F.)
AREA (NET): 0.152 ACRES (6,622 S.F.)

#### PROPOSED SITE DEVELOPMENT INFORMATION PROPOSED PARCEL:

ZONING: NMU/DR PROPOSED USE: MIXED USE AREA (GROSS): AREA (NET): 0.464 ACRES (20,227 S.F.) 0.464 ACRES (20,227 S.F.) AREA BREAKDOWN\*:
COMMERCIAL: 1,252 SQ. FT. UNIT 1 (TYPE C): UNIT 2 (TYPE B) 947 SQ. FT. 948 SQ. FT. 883 SQ. FT. UNIT 3 (TYPE A) UNIT 4 (TYPE D): UNIT 5 (TYPE C): UNIT 6 (TYPE B): UNIT 7 (TYPE A) 883 SQ. FT.

\*REFER TO ARCHITECTURAL PLANS FOR DETAILS OF THE FLOOR LAYOUT.

#### SUBDIVIDER STATEMENT:

1) OWNER / DEVELOPERS: ZACH TRAILER 1075 CURTIS STREET MENLO PARK, CA 94025

2) APPLICANT NAME: SAME AS ABOVE EXISTING USAGE: COMMERCIAL PROPOSED USAGE: MIXED-USE

5) EXISTING WELLS: NONE

5) EASTING WELLS: NOTE.
6) FLOOD ZONE: ZONE X, PER PANEL 06081C030E
7) STREETS: ALL PROPOSED STREET MODIFICATIONS WILL BE IMPROVED TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC WORK

8) EXISTING USE OF ADJACENT PROPERTIES: COMMERCIAL 9) WATER: CALIFORNIA WATER SERVICE COMPANY 10) FIRE PROTECTION: MENLO PARK FIRE FIRE

11) SANITARY SEWER: FAIR OAKS SEWER MAINTENANCE DISTRICT

12) POWER AND GAS: PACIFIC GAS AND ELECTRIC
13) TELEPHONE / CABLE: SBC / COMCAST

14) STREET TREÉS: NONE 15) EASEMENT: NONE
16) CONTOUR ELEVATION: LOCAL DATUM AND MONUMENTS

17) ALL DIMENSIONS ARE APPROXIMATE 19) NO TREES PROPOSED FOR REMOVAL WITH THIS APPLICATION

01 OF 13 SHEETS

FIELD ROAD CALIFORNIA

MIDDLEFIELD PARK, CALIF

3252 N MENLO

SHEET

TITLE

REVISIONS 2170957P JOB NO: 09-19-18 1" = 20

SCALE: DESIGN BY: JH CHECKED BY: CA

SHEET NO: TM-1



ON PKWY WEST DRNIA 94545 4086

MIDDLEFIELD ROAD PARK, CALIFORNIA 3252 M MENLO

> PLAN DEMOLITION


REVISIONS BY 2170957P

JOB NO: DATE: 09-19-18 SCALE: 1" = 10'

DESIGN BY: JH CHECKED BY: CA SHEET NO:

\* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL SPACE DEPTH TO ESTABLISH PAD LEVEL.

**TM-2** 02 OF 13 SHEETS



#### **DEMOLITION LEGEND**

EVERYTHING WITHIN THE SITE AREA TO BE REMOVED. UNLESS NOTED TO REMAIN. ALL UTILITIES ARE TO BE TAKEN BACK TO THE MAIN. SEE UTILITY PLAN FOR TERMINATION POINT AND CONNECTIONS.

SAWCUT LINE. SAWCUT (E) IMPROVEMENTS TO A SMOOTH EDGE, MATCH (E) IMPROVEMENTS.



TREE PROTECTION TREES TO REMAIN SEE LANDSCAPE PLANS FOR DETAILS. DECONSTRUCT BY HAND WHEN DEMOLITION WORK IS WITHIN TREE PROTECTION ZONES






CONCRETE WASHOUT

STRAW ROLLS / SITE PROTECTION


SCHEDULING OR QUOTATIONS . aabaya@leabraze.com


NOTE: FOR CONSTRUCTION STAKING PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116.



2170957P 09-19-18 1" = 5'

**TM-3** 






**TM-5** 05 OF 13 SHEETS

TREATMENT FLOW-THROUGH PLANTER BOX DETAIL

TM-3 NTS



#### FLATWORK

PROVIDE 2% (1% MIN.) SLOPE ACROSS FLAT WORK AND/OR PAVING PER CBC 2304.12.1.2. SLOPE TOWARDS POSITIVE DRAINAGE AS SHOWN ON PLAN.

(N) CONCRETE PATIOS/WALKWAYS.

#### STORM DRAIN

INSTALL (N) STORMDRAIN SUMP PUMP ZOELLER MODEL 95 1/2 HP PUMP.

#### UTILITIES

MAJOR CHANGES IN DIRECTION AS SHOWN. REUSE (E) LATERAL IF POSSIBLE. CONNECT PER DISTRICT STANDARDS.

CONNECT (N) WATER SERVICE PER WATER DISTRICT STANDARDS. UPGRADE (E) WATER METER PER WATER DISTRICT STANDARDS AS APPLICABLE. INSTALL (N) 2" MINIMUM SERVICE LINE TO (N) RESIDENCE OR AS DIRECTED BY FIRE SPRINKLER DESIGNER.

DEMOLISH (E) IMPROVEMENTS AS NECESSARY TO ACCOMMODATE (N) CONSTRUCTION. NO DEMOLITION SHALL COMMENCE WITHOUT REQUIRED DEMOLITION PERMITS.

FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116.

aabaya@leabraze.com

\* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL SPACE DEPTH TO ESTABLISH PAD LEVEL.



SACF 3017 ROSE (P) (F)

WEST 94545

FIELD ROAD CALIFORNIA MIDDLEFIELD DARK, CALIF

GRADING GE PLAN CONCEPTUAL GHAND DRAINAGE

3252 N MENLO

REVISIONS JOB NO: 2170957F 09-19-1 1" = 10' SCALE: DESIGN BY: JH

SHEET NO:

TM-6 06 OF 13 SHEETS

CHECKED BY: CA

FLAT WORK.
FINISHED GRADES AT BUILDING PERIMETER SHALL BE SLOPED AT A
MINIMUM OF 5% FOR THE FIRST 10' AWAY FROM THE BUILDING PER CBC
1804.4 OR TO AN APPROVED DRAINAGE SWALE OR STRUCTURE. GRADES
SHALL CONTINUE TO SLOPE TOWARDS POSITIVE DRAINAGE AND A POSITIVE
OUTFALL. MAINTAIN 8" CLEARANCE BETWEEN FINISH EARTHEN GRADE AND
BOTTOM OF MUD SILL AT ALL TIMES PER CBC 2304.12.1.2 UNLESS
STRUCTURAL DETAILING ALLOWS LESS. REFER TO STRUCTURAL PLANS FOR
FOUNDATION DESIGN AND DETAILS.

(N) AC DRIVEWAY.

GRIND AC TO TIE (N) AC INTO (E) AC PAVING.

(N) CONCRETE PARKING LOT.

INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" PVC (SDR 35) OR HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). MAINTAIN 24" MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS OTHERWISE NOTED. PROVIDE CLEAN OUT TO GRADE AT MAJOR CHANGES IN DIRECTION. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS

DIRECT DOWNSPOUTS TO  $24^\circ$  Long precast concrete splashblocks or other hard surface. Direct away from any structure and towards positive drainage.

INSTALL (N) AT GRADE STORMWATER TREATMENT SYSTEM WITH 30" RETENTION PIPE BENEATH PER DETAIL 1 ON SHEET TM-3.

INSTALL (N) SANITARY SEWER LATERALS. USE 4" PVC (SDR-26) SLOPED AT 2% MINIMUM. CONNECT TO (E) SEWER MAIN AS SHOWN. PROVIDE CLEANOUT TO GRADE AT BUILDING AND BEHIND PROPERTY LINE AND AT


INSTALL (N) JOINT TRENCH FOR SERVICES INCLUDING GAS, CATV & ELECTRIC FROM NEAREST POINT OF CONNECTION. DESIGN BY OTHERS.


#### DEMOLITION

THRU CURB WITH SOLID BOTTOM

NTS

TM-3/





#### DEVELOPMENT INFORMATION

TOTAL SITE AREA	6,622 SQUAF	RE FEET (0.152	ACRE)				
TOTAL DISTURBED AREA	6,622 SQUARE FEET (0.152 ACRE)						
	EXISTING	REMOVED	NEW	PROPOSED			
IMPERVIOUS AREAS	TOTAL S.F.	TOTAL S.F.	TOTAL S.F.	TOTAL S.F.			
BUILDING AREA	2,763	2,763	5,836	5,836			
PARKING	1,571	1,571	156	156			
DRIVE AISLE	2,038	2,038	0	0			
PATIOS, WALKWAYS, & PADS	176	176	285	285			
TOTAL IMPERVIOUS AREA	6,548	6,548	6,277	6,277			
NET CHANGE IN IMPERVIOUS AREA	271 SQUARE FEET (NET DECREASE)						
FLOOR AREA	REFER TO THE ARCHITECTURAL PLANS FOR PROPOSED FLOOR AREA CALCULATIONS						

NOTE: FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116. aabaya@leabraze.com

\* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL SPACE DEPTH TO ESTABLISH PAD LEVEL.

SHEET NO: **TM-7** 07 OF 13 SHEETS

DESIGN BY: JH

CHECKED BY: CA

REVISIONS JOB NO:

DATE:

SCALE:

2170957P

09-19-18

1" = 10'

LEA & BRAZE ENGINEERING, INC.

ION PKWY WEST DRNIA 94545 -4086

EXISTING PAVED AREA EXHIBIT

3252 MIDDLEFIELD ROAD MENLO PARK, CALIFORNIA



PROPOSED PAVED EXHIBIT

\* BUILDING PAD NOTE: ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL. SPACE DEPTH TO ESTABLISH PAD LEVEL.

SCHEDULING OR QUOTATIONS

PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING

(510)887-4086 EXT 116.

. aabaya@leabraze.com

SCALE: DESIGN BY: JH

CHECK	KED	BY:	CA
SHEE1	NO:		
T	'N	1	-8
08	OF	13	SHEET


REVISIONS

2170957P

09-19-18

JOB NO:

DATE:



6,277

TOTAL IMPERVIOUS AREA

FLOOR AREA

NET CHANGE IN IMPERVIOUS AREA

6,548

6,548

271 SQUARE FEET (NET DECREASE)

REFER TO THE ARCHITECTURAL PLANS FOR

6,277



ENGINEERING, I SACRAMENT 3017 DOUGLA ROSEVILE, (P) (916)96 (F) (916)793

. WEST 94545

BRAZE

FIELD ROAD CALIFORNIA MIDDLEFIELD
D PARK, CALIF 3252 N MENLO

> DETAILS STANDARD

REVISIONS

JOB NO: 2170957P DATE: 09-19-18 1" = 10' SCALE:

DESIGN BY: JH

CHECKED BY: CA

**TM-9** 09 OF 13 SHEETS

NOTES:

1. CURB RAMPS SHALL HAVE 4 FOOT BY 3 FOOT LONG DETECTABLE WARNING BORDER CENTERED AND SQUARED AT THE RAMP BOTTOM.

2. THE DETECTABLE WARNING BORDER SHALL BE A CONTRASTING SURFACE.

3. DOME ORIENTATION SHALL CONFORM TO THE LATEST ADA/TITLE 24 REGULATIONS.

4. IF PRECAST CONCRETE DETECTABLE WARNING DOMES PAVERS ARE USED, THE WILL NEED TO BE INSTALLED ON TOP OF A 4" THICK CONCRETE SURFACE. PAVERS SHALL BE LAID SUCH THAT JOINTS ARE LEVEL WITH ADJOINING SURFACE, TO PROVIDE A SMOOTH TRANSITION FROM PAVER TO PAVER AND FROM PAVER TO CONCRETE.

5. IF THE PLASTIC MAT DETECTABLE WARNING DOMES IS USED. THE MAT NEEDS TO BE FLUSH WITH THE ADJOINING CONCRETE SURFACE.

WHERE THE MAT IS INSTALLED, THE CONCRETE SURFACE. WHERE THE MAT IS INSTALLED, THE CONCRETE SURFACE WILL NEED TO BE HELD DOWN THE THICKNESS OF THE MAT. THE LOADING AND UNLOADING ACCESS AISLE, ASSOCIATED WITH ACCESSIBLE PARKING, SHALL BE MARKED BY A BORDER PAINTED BLUE PER CBC SECTION 11B-208 & 11B-208 ACCESSIBLE SIGN -DESIGNATED VAN STALL WHERE SHOWN ON PLAN \_FLUSH CURB

> PAINT STRIPES

> > L


PAINT WITH 1" WIDE WHITE LETTER" HIGH

PARKING


ACCESSIBLE STALL Ç−4.9 NTS

L


ACCESSIBLE SYMBOL CENTER IN PARKING-STALL 12' FROM FACE OF CURB



DETECTABLE WARNING SURFACE C-4.0 NTS



ACCESSIBLE PARKING SYMBOLS C-4.0 NTS



NOTES
1. OFF-STREET PARKING FACILITIES TO HAVE SIGN AT STREET ENTRANCE NOT LESS THAN 17" x 22" IN SIZE. SIGN TEXT TO BE BEADED (OR EQUAL) TO STATE THE

FOLLOWING:
"UNAUTHORIZED VEHICLES NOT DISPLAYING
DISTINGUISHING PLACARD OR LICENSE
PLATE ISSUED FOR PHYSICALLY DISABLED
PERSONS MAY BE TOWED AWAY AT
OWNER'S EXPENSE. TOWED VEHICLES MAY
BE RECLAIMED AT OR BY TELEPHONING
"CONTRECTOR TO BUILDIN "CONTRACTOR TO FILL IN BLANKS PRIOR TO MANUFACTURING SIGN.

- 2. ACCESSIBLE PARKING SPACE SIGN TO BE BEADED (OR EQUAL) WITH ACCESSIBLE SYMBOL, AS SHOWN. SIZE TO BE 70 SQ. IN. MINIMUM.
- PROVIDE SIGN AT VAN STALL WITH ADD'L SIGN STATING "VAN ACCESSIBLE"


NTS C-4.0

ACCESSIBLE PARKING SIGNAGE


TOP OR RAMP 1/4"x1/4" GROOVES PARALLEL TO TOP OF RAMP .75" ratural de la comunicación de la c 

NOTE: THE GROOVES OCCUR ON LEVEL SURFACE AT TOP OF RAMP, NOT ON RAMP SURFACE.


GROOVES AT TOP OF RAMP 5 C-4.0 NTS



ACCESSIBLE RAMP




ACCESSIBLE RAMP **℃-4.0** NTS



NOTES:

- RAILINGS SHALL BE 1 1/2" SCHEDULE 40 ALUMINUM PIPE ALLOY 6105-T5, ASTM-B-429 OR ASTM-B-221. POSTS SHALL BE 1 1/2" SCHEDULE 40 ALUMINUM PIPE OF THE SAME ALLOY. POST SPACING SHALL BE A MAXIMUM OF 6'-0".
- 2. HANDRAILS SHALL BE DESIGNED TO WITHSTAND A 200 LB CONCENTRATED LOAD APPLIED IN ANY DIRECTION AND AT ANY POINT ON THE TOP RAIL.
- POSTS SHALL NOT INTERRUPT THE CONTINUATION OF THE TOP RAIL AT ANY POINT ALONG THE RAILING, INCLUDING CORNERS AND END TERMINATIONS (OSHA 1910.23). THE TOP SURFACE OF THE TOP RAILING SHALL BE SMOOTH AND SHALL NOT BE INTERRUPTED BY PROJECTED FITTINGS.
- FINISH SHALL BE ALUMINUM ASSOCIATION M10-C22-A41 (215-R1). THE PIPE SHALL BE PLASTIC-WRAPPED. THE PLASTIC WRAP IS TO BE REMOVED AFTER ERECTION.
- 5. ALUMINUM SURFACES IN CONTACT WITH CONCRETE, GROUT OR DISSIMILAR METALS WILL BE PROTECTED WITH A COAT OF BITUMINOUS PAINT, MYLAR ISOLATORS OR OTHER APPROVED MATERIAL.





NTS


SHEET NO:


C-4.0


DESIGN BY: JH

CHECKED BY: CA SHEET NO:

M-10







No. 200

2. STRUCTURE BACKFILL MATERIAL... MATERIAL WITH SAMD EQUIVALENT NOT LESS THAN 20 AND SEVE CRADATION BY MEIGHT AS FOLLOWS:

SEVE SIZE X PASSING SEVE 100 35-100 20-100

3. BACKFILL MATERIAL.... MATERIAL FROM EXCAVATION, FREE FROM STONES OR LUMPS EXCEEDING 3 INCHES GREATEST DIMENSION, ORGANIC MATTER, OR DITHER LINSATISFACTORY MATERIAL.

#### STANDARD TRENCH BACKFILL AND BEDDING DETAIL FOR PVC SEWER PIPE

SAN MATEO COUNTY DEPARTMENT

PUBLIC WORKS

SCALE: NONE DATE: 6/95 REVISET:

## 8AN MATEO COUNTY BEWER AND SANITATION DISTRICTS STANDARD SPECIFICATIONS

- all references to "district" in these general notes small mean the appropriate county sever or samitation district.
- THE APPROVAL OF THESE PLANS BY THE DISTRICT SHALL BE INTERPRETED TO MEAN THAT THE SANTTARY SENER DESIGN SHOWN ON THESE PLANS MEETS THE DISTRICT'S STANDARDS, THE DISTRICT'S STANDARDS, THE DISTRICT'S APPROVAL IN NO WAY GUARANTEES ANY OTHER ASPECT OF THIS PLAN OR ITS ACCURACY RELATIVE TO ACTUAL FIELD CONDITIONS.

- THE CONTRACTOR SHALL CONTACT UNDERGROUND SERVICE ALERT FORTY-EIGHT (48) HOURS IN ADVANCE OF BEGINNING ANY WORK.
- 6. THE CONTRACTOR SHALL FIELD VERIFY THE LOCATION OF ALL UTILITIES BEFORE BEGINNING ANY EXCAYATING.

- 10. PRIOR TO COMMENCING ANY SANITARY SEWER WORK IN OFF-SITE EASEMENTS THE CONTRACTOR SHALL PROMOE THE DISTRICT WITH ADEQUATE EVIDENCE THAT ALL AFFECTED PROPERTY OWNERS (AND TOWARTS WHERE APPLICABLE) WERE MOTRED WELL IN ADVANCE OF THE DATE WORK IN THESE CASSIMINTS AND TO BEGIN AND THAT THEY HAVE UPDATED THAT MOTRE IN A TIMELY MANINER WHEN THOSE DATES HAVE CHANGED.

C-13



- ALL JOINTS SHALL SE A BELL AND SPIGOT ASSEMBLY WITH ELASTOMERIC SEALING GASKETS, SEALING GASKETS SHALL MEET THE REQUIREMENTS OF ASTM SPECIFICATION D1889, SOLVENT COMMIT JOINTS ARE NOT PERMITTED.
- ALL PIPE ENTERING OR LEAVING A CONCRETE STRUCTURE SHALL HAVE A RUBBER WATERSTOP GASKET SHALL COMFORM TO THE PAPE MANUFACTURER'S SPECIFICATION. THE WATERSTOP GASKET SHALL COMFORM TO THE PAPE MANUFACTURER'S SPECIFICATION. THE WATERSTOP GASKET SHALL BE SEATED PRIMLY AROUND THE PAPE EXTERIOR AND SE CAST INTO THE CONCRETE STRUCTURE.
- ALL PIPE JOINTS SHALL BE MADE USING MANUFACTURED PVC COUPLINGS. BAND TYPE COMPRESSION COUPLINGS ARE NOT PERMITTED,

#### DUCTLE (RON PIPE (DIP)

- ALL PIPE SHALL BE THERNICSS CLASS 50 (FDUR INCH PIPE SHALL BE THERNICSS CLASS 51) IN ACCORDANCE WITH ANS SPECIFICATIONS AZI.55. FITTINGS SHALL BE IN ACCORDANCE WITH ANS SPECIFICATION AZI.10.
- JOINTS SHALL BE PUSH-ON TYPE OR MECHANICAL JOINT TYPE IN ACCORDANCE WITH ANS SPECIFICATION A21.11. RUBBER GAXETS FOR PUSH-ON JOINTS SHALL BE IN ACCORDANCE WITH ANS SPECIFICATIONS HEROIN.
- PPE AND FITTINGS SHALL HAVE A BITUMINOUS COATING OUTSIDE IN ACCORDANCE WITH ASTM SPECIFICATION A746-68, UNLESS OTHERWISE SPECIFIED HEREIN.
- 4. PIPE AND FITTINGS SHALL HAVE A 1/16" (ONE-SIXTEENTH INCH) CEMENT-MORTAR LINING WITH AN ASPHALTIC SEAL COAT.

#### WITHHELD CLAY PIPE (VCP)

- PIPE AND FITTINGS SHALL BE EXTRA STRENGTH, UNGLAZED, BELL AND SPIGOT, CONFORMING TO THE LATEST REVISION OF ASTM SPECIFICATION 0700.
- JOINTS SHALL BE A BILL AND SPIGOT ASSEMBLY WITH FACTORY INSTALLED FLEXIBLE COMPRESSION TYPE CASKETS MADE OF PLASHCIZED POLYWINTLOR POLYMETHAME COMPORING TO THE LATEST REVISION OF ASTM SPECIFICATIONS C425. BAND TYPE COUPLINGS ARE NOT ALLOW.

C-14



- all references to "district" in these testing requirements shall mean the appropriate county sewer or sanitation district.
- ALL REQUIRED CLEANING AND TESTING OF SANITARY SEMER MAINS AND LATERALS SHALL BE PERFORMED IN THE PRESENCE OF A REPRESENTATIVE OF THE DISTRICT,
- ALL SANITARY SEWER MARKS BEING CONSTRUCTED SHALL BE CLEANED BY MEANS OF A HIGH SPEED LET ROOCER PRIOR TO TESTING. VCP AND DIP SHALL BE TESTED FOR DESTRUCTION BY BALL ROLLING.

A COMPRESSED AIR SUPPLY SHALL BE ATTACHED TO AN AIR FITTING ON THE MAIN AND THE AIR PRESSURE WITHIN THE LINE INCREASED TO FOUR (4) POUNDS FER SQUARE INCH (FS)). AFTER THE AIR SUPPLY IS SCOURCY TURNED OF FO OSSCONICETO, THERE SHALL BE A TWO (2) MINUTE MATTHIS PETIOD BEFORE THE ACTUAL TEST PERIOD BEGINS TO ALLOW STABLIZATION OF AIR WITHIN THE MAIN.

IN NO CASE SHALL THE AR PRESSURE WITHIN THE LINE BELLESS THAN 3.5 PS AT THE BECONNING OF THE TEST PERIOD. REPER TO THE CHART WHICH FOLLOWS FOR THE LENGTH OF THE TEST PERIOD. THE ALIMINIUM LENGTH OF TEST IS THOUGO, THE MEDIAND AR PRESSURE LOSS QUINNO THE TEST PERIOD SHALL SE 1.0 PSL. A WRITTEN RECORD OF THE TEST SHALL BE SUBMITTED TO THE DISTRICT BY THE CONTRACTOR.

NOMINAL PIPE SIZE	LENOTH OF LINE	LENGTH OF TEST
(Inches)	(feet)	(minutes)
4 6 6 8 8 8 8 8 8 8 8 10 11 10 11 10 11 10 11 10	ALL 300 307 307 307 307 307 307 AND CREATER D 170 - 210 210 - 250 250 - 250 4 AND GREATER D 10 10 5 - 213 215 AND CREATER C - 155 AND CREATER C - 155	2 2 1/2 2 1/2 3 1/2 3 1/2 3 3/4 4 3/4

SAN MATEO COUNTY DEPARTMENT

SCALE: NONE DATE: 5/95 REVISED:\_\_\_\_\_ PUBLIC WORKS

5. A TILLWISON HISPECTION SHALL BE MADE OF ALL SANITARY SEWER MAINS BEING CONSTRUCTED. BURNIETY PHORN TO TILLMING HIS STWER. AN AUXOINT OF MATER ACCEPTABLE TO THE DISTRICT'S REPRESENTATIVE SHALL BE INTRODUCED INTO THE SEWER MAIN BEING INSPECTION.


A VIDED TAPE IN VAS FORMAT AT SP. OR EQUIVALENT, SPEED SHALL BE MADE OF THE NSSECTION AND DELIVERED ALONG WITH A TYPE LOG OF THE INSSECTION TO THE DISTRICT (SAN MATER COUNTY DEPARTMENT OF PUBLIC MORES) FOR REMEW AND ACCEPTANCE.

DEFICITION TESTING OF POLYVINY. CHLORICE (PVC) SEWER MAINS SHALL BE PERFORMED AFTER THE PLACEMENT OF ALL TRENCH BACKFILL. PIPE DISTLECTION SHALL BE TESTED BY PUBLIC BY HAND A GO/NO-GO MANOREL THROUGH THE INSTALLED SECTIONS OF SEWER MAIN.

THE MANDREL USED SHALL HAVE A MINIMUM LENGTH EQUAL TO ITS DIAMETER. THE MANDREL SHALL BE CONSTRUCTED WITH A MINIMUM OF NIME (8) MOSS FABRICATED PARALLEL TO ITS LONGTONIAL ANS BOTH THE DESIGN OF THE MANDREL AND THE FABRICATED MANDREL ITSELF SHALL BE INSPECTED AND APPROVED BY THE DISTRICT WELL IN ADVANCE OF THE INSPECTION TEST.

NOMINAL PIPE 802E (Inches)	AVERAGE INSIDE DIAMETER (Inchee)	MRMAM MANDREL DIAMETER (Inches)	
ቴ	5.893	5.598	
ፅ	7.891	7.497	
ነው	9.854	9.371	

Note: Average inside diameter = average outside diameter = 2(1.05)T; where T = minimum wall thickness as defined by astm specification 0.3034.



THE CONTRACTOR SHALL CONTACT THE DISTRICT AT 383-4755 OR 363-4100 TWO (2) WORKING DAYS IN ADVANCE OF SECTIONING ANY SANTARY SEMER WORK. THE CONTRACTOR SHALL THISBAR HER KEEP THE INSPECTOR FOR THE DISTRICT INFORMED OF HIS SCHEDULE FOR SANTFARY SEMER WORK.

ALL SANITARY SEWER WORK CONSTRUCTED WITHOUT INSPECTION BY THE DISTRICT SHALL BE REMOVED AND RECONSTRUCTED WITH INSPECTION.

THE CONTRACTOR SHALL OBTAIN AND ALL PERMITS REQUIRED BY THE COUNTY OR CITY BEFORE BEGINNING ANY SANITARY SEWER WORK.

Upon the completion of construction a complete set of reproducible "as-constructed" plans shall be provided to the district.

SANITARY SEWER SERVICE SHALL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR SHALL USE WHATEVER MEANS ARE NECESSARY (E.G. PUMPS, ETC.) TO MAINTAIN THIS SERVICE DURING CONSTRUCTION.

#### PURPOSE:

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER CHALTY CONTROL BOARDS. SIELD MANUAL FOR PERSION AND WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL. AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD

#### EROSION CONTROL NOTES:

- IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- 2. THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
- 3. OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNDOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- 6. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
- EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
- 10. IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- 12. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- 13. MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SUFFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- 14. EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH
- 15. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER 1ST THROUGH APRIL 30TH, WHICHEVER IS GREATER.
- 16. PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
- 17. THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN
- 18. THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 19. THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION, METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN BIGHT-OF-WAY THE TOWN RIGHT-OF-WAY.
- 20. SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT-OF-WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
- 21. THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL
- 22. STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPAULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
- 23. EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAYOR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
- 24. TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND

#### EROSION CONTROL NOTES CONTINUED:

- 24. FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN FOLES, GLES, SUEVENTS AND OTHER TUSTOR AND ARE NOT TO CONTAMINATE THE SOIL AND SUFFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER, SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM,
- 25. DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE
- 26. SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES, FOLLOWING AND DURING ALL RAIN EVENTS,TO PUBLIC OWNED FACILITIES.

#### **EROSION CONTROL MEASURES:**


- 1. THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- 2. SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- 3. CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- 4. ALL EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE—STEP APPLICATION OF 1) SEED, MULCH, CONTROL BLANKEIS, OR A HIREE-SIEP APPLICATION OF 1) SEED, MOLCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYPROSEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL. AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER DISCREPAINTS.
- 5. INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- 6. THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- 7. THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
- 8. STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURES SPECIFICATIONS FOR PLACEMENT AND

#### REFERENCES:


- CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- 2. CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

#### PERIODIC MAINTENANCE:

- 1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
  - A. DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
- B. SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
- C. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
- D. SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH
- E. SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- F. RILLS AND GULLIES MUST BE REPAIRED.
- GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- 4. SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- 5. CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION



## EROSION CONTROL LEGEND





GRAVEL BAG

INLET PROTECTION

SILT FENCE



CONCRETE WASHOUT



CONSTRUCTION




TREE PROTECTION



BLANKET / MATTING

NOTE: SEAL ALL OTHER INLETS NOT INTENDED TO ACCEPT STORM WATER AND DIRECT FLOWS TEMPORARILY TO FUNCTIONAL SEDIMENTATION BASIN INLETS. -TYP



CONTROL ROSION

REVISIONS JOB NO: 2170957F 09-19-1

SACF 3017 ROSF (P)

WEST 94545

FIELD ROAD CALIFORNIA

MIDDLEFIELD PARK, CALIF

3252 | MENLO

1" = 10' SCALE: DESIGN BY: JH

HECKED BY: CA HEET NO

OF 13 SHEET

REVISIONS 2170957P

JOB NO: DATE: 09-19-18 NTS SCALE:

CHECKED BY: CA SHEET NO:

**ER-2** 

GRAVEL BAG CONSISTS OF A
—BURLAP SACK FILLED WITH 3/4"
\_CRUSHED, CLEAN DRAIN ROCK STRAW ROLL FILTER FABRIC
PLACED
— BETWEEN
GRATES & INLET
COVER GRAVEL BAGS SHALL SIT ON TOP OF EACH SIDE OF STRAW ROLL AND OVERLAP ON CURB FLOW LINE -

STREET INLET PROTECTION ER-2 NTS

ER-2 NTS

SET POSTS AND EXCAVATE

THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 10' OF THE TEMPORARY CONCRETE WASHOUT FACILITY.

2. STAPLE WIRE FENCE TO THE

NOTE:
PREMANUFACTURED SILT FENCE
PRODUCTS MAY BE USED IN
LIEU OF WIRE FENCE. INSTALL
PER MANUFACTURER'S
RECOMMENDATIONS AND
MAINTAIN KEYING OF FABRIC
PER THIS DETAIL.

SILT FENCE ER-2 NTS

STAPLE DETAIL


PLYWOOD -48"x24" PAINTED WHITE BLACK LETTERS 6" HEIGHT \_1/2" LAG SCREWS WOOD POST 3"X3"X8'

CONCRETE WASHOUT SIGN DETAIL

NOTES: ACTUAL LAYOUT DETERMINED IN FIELD.

ER-2 NTS

(ABOVE GRADE) -TYP PLASTIC LINING PLAN VIEW



CONCRETE WASHOUT

STRAW ROLLS MUST BE PLACED ALONG SLOPE CONTOURS SEDIMEN1


FILTER FABRIC TO COVER INLET

ER-2

NTS

INLET PROTECTION

(E) GRADE



NOTE:

1. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3" TO 5" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.

2. CONTRACTOR IS RESPONSIBLE FOR REGULAR MAINTENANCE AND INSPECTION. THE SILT SHALL BE CLEARED OUT WHEN IT REACHES HALF THE HEIGHT OF THE ROLL.

STRAW ROLLS FLAT LOT

EXISTING TREE PROTECTION DETAIL

5' HIGH STEEL FENCE POSTS
\_BURIED 2' INTO THE GROUND ON 5'
CENTERS WITH 5' HIGH BRIGHT
ORANGE FENCE FABRIC. POST TO
BE AT DRIP LINE OF TREE WHERE
EVER POSSIBLE. NOTE:

REFER TO LANDSCAPE

ARCHITECTURAL PLANS

FOR ADDITIONAL TREE

PROTECTION INFORMATION. NOTE:
LOCAL JURISDICTION MIGHT HAVE
MORE STRINGENT REQUIREMENTS.
CONTRACTOR IS RESPONSIBLE FOR
COORDINATING W/ INSPECTOR TO
ENSURE PROPER PROCEDURES ARE
BEING FOLLOWED.

A 4"X4" TRENCH UP SLOPE ALONG THE LINE OF POSTS. 3. ATTACH THE FILTER FABRIC TO THE WIRE FENCE AND EXTEND IT INTO THE TRENCH. BACKFILL AND COMPACT THE EXCAVATED SOIL. FABRIC AND WIRE INTO THE TRENCH.

PUBLIC\_ RIGHT-OF-WAY

NOTES:

STABILIZED CONSTRUCTION SITE ACCESS SHALL BE CONSTRUCTED OF 3" TO 4" WASHED, FRACTURED

MATERIAL SHALL BE PLACED TO A MINIMUM THICKNESS OF 12". LENGTH OF ENTRANCE SHALL BE A MINIMUM OF 50'.

WIDTH SHALL BE A MIN. OF 15' OR GREATER IF NECESSARY TO COVER ALL VEHICULAR INGRESS AND EGRESS. PROVIDE AMPLE TURNING RADII.

THE ENTRANCE SHALL BE KEPT IN GOOD CONDITION BY OCCASIONAL TOP DRESSING WITH MATERIAL AS SPECIFIED IN ABOVE NOTE.

ACCESSES SHALL BE INSPECTED WEEKLY DURING PERIODS OF HEAVY USAGE, MONTHLY DURING NORMAL USAGE, AND AFTER EACH RAINFALL, WITH MAINTENANCE PROVIDED AS NECESSARY.

PERIODIC TOP DRESSING SHALL BE DONE AS NEEDED.

12" MIN. PROVIDE
APPROPRIATE TRANSITION
BETWEEN STABILIZED
CONSTRUCTION ENTRANCE
AND PUBLIC RIGHT—OF—WAY SECTION GEOTEXTILE LINER BENEATH-AGGREGATE

EXISTING GROUND

PLAN PROVIDE DEPRESSION TO DIRECT RUN OFF AWAY FROM PUBLIC

CONSTRUCTION ENTRANCE

NOTE: IT IS ESSENTIAL THAT THE WIRE/FABRIC BE FULLY EMBEDDED INTO THE GROUND SO RUN-OFF CANNOT FLOW FREELY UNDER FENCE.

ER-2

DESIGN BY: JH

12 OF 13 SHEETS


ER-2 NTS

# **Construction Best Management Practices (BMPs)**

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Clean Water. Healthy Community.

#### Materials & Waste Management



#### Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within
- ☐ Use (but don't overuse) reclaimed water for dust control.

#### Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

#### Waste Management

- ☐ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

#### **Construction Entrances and Perimeter**

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

### Equipment Management & Spill Control



#### Maintenance and Parking

- Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

#### Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly
- Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat
- ☐ Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil, To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

#### Earthmoving



- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

#### **Contaminated Soils**

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration,
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash.

#### Paving/Asphalt Work



- ☐ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement

#### Sawcutting & Asphalt/Concrete Removal


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.

#### Concrete, Grout & Mortar Application




- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

## Landscaping



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

#### Painting & Paint Removal



#### Painting Cleanup and Removal

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.



- ☐ Discharges of groundwater or captured runoff from dewatering operations must possible send dewatering discharge to landscaped area or sanitary sewer. If local wastewater treatment plant.
- from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for



- Never pour paint down a storm drain.

#### Dewatering



- be properly managed and disposed. When discharging to the sanitary sewer call your
- ☐ Divert run-on water from offsite away
- ☐ In areas of known or suspected treatment and proper disposal.

Storm drain polluters may be liable for fines of up to \$10,000 per day!

FIELD ROAD CALIFORNIA

MIDDLEFIELD DARK, CALIF 3252 N MENLO

STORMWATER POLLUTION PREVENTION PLAN


REVISIONS JOB NO: 2170957P DATE: 09-19-18

SW-1 ---OF 13 SHEETS


DESIGN BY: JH CHECKED BY: CA

NTS

SCALE:



#### Avenue





#### Plant Legend

					Water	
	Key	Botanical & Common Names	Qty.	Size	Reg't.	Comments
		Shrubs:				
	51	Berberis t. "Crimson Pygmy" / Dwarf Barberry	6	5 gl.	L	
	52	Nandina d. "Nana" / Dwarf Nandina	4	5 g).	L	
	53	Polystichem munitum / Sword Fern	8	5 gl.	M	
	54	Viburnum t. Spring Bouquet* / Laurustinus	2	5 g).	L	
		Bio-retention:				
	81	Acer circinatum / Vine Maple	3	15 gl.	1	Multi-Stem
	B2	Carpenteria c. "Elizabeth" / Bush Anemone	14	5 g).	1	
	В3	Juncus p. "Elk Blue" / Calif. Gray Rush	18	5 gl.	M	
	64	Mimulus aurantiacus / Monkey Flower	1	5 gt.	T-	
		Groundcovers				
7	6.50	Carex tumulicola / Berkeley Sedge	as req'd,	1 gl.	T	Set @ 12" o.
į		Mahonia repens / Creeping Oregon Grape	W . W	1 gi.	L	Set @ 16" o.


Water conservation classification is based on Water Use Classification of Landscape Species (WUCOLS) prepared by the Water conservation Office of the Department of Water Resources (2000)

#### Notes:

Locations of trees and shrubs shown on Plan are schematic and shall be adjusted in the field to avoid conflicts with utilities, irrigation, footings, etc.



- 3. Quantities in the Plant Legend are for general reference only (Verify count per Plan).
- 4. All planting areas to be top dressed with a 3" layer of medium grind fir bark mulch.



Tree Planting Detail

7/17/2018 MWELO Notes 8/21/2018 Rear Landing

3252 Middlefield Road

Planting Plan

Date 3/7/2018 Scale 1" = 10'- 0" LBW

#### CalGreen Landscape Notes:


Automatic irrigation system controllers for landscaping provided by the builder and installed at the time of final inspection shall comply with the following: CGBSC 4.304.1.

- 1. Controllers shall be weather or soil-moisture based controllers that automatically adjust irrigation in response to changes in plant' needs as weather conditions change.
- Weather based controllers without integral rain sensors or communication systems that account for local rainfall shall have a separate wired or wireless rain sensor which connects or communicates with the controller(s). Soilmoisture based controllers are not required to have rain sensor input.

#### Irrigation Legend

Symbol	Description	GPM	PSI
	Emission Devices.		
3//4/	Rainbird XF-Series Dripline, Lateral Hows 18" o.c., Emitters 12" o.c.	1	35
+	Rainbird 1401 Pressure Compensating Bubbler	.25	35
	Other Equipment:		
	Class 200 PVC Piping, size as Noted		
	Schedule 40 PVC Pressure Mainline Piping, Size as Noted		
6	Rainbird ASVF Remote Control Valve w/ Anti-Siphon, Size as Noted		
0	Rainbird XACZ-075-PRF Control Zone Kit w/ Anti-Siphon & PR Filter		
B	Febco 825Y Reduced Pressure Backflow Preventer, 1" Size		
DO	Line Size Brass Ball Valve		
1	Data Industrial IFS Flow Sensor, Line Size		
B	Rainbird ESP-SMTe Smart Modular Controller w/ Upgrade Kit		

#### Sixth Avenue







#### Irrigation Notes:

- Maximum design flow: 15 gpm
- Maximum design pressure: 65 psi
- All valves shall cycle/soak runtimes to eliminate run-off based on soil types.
- Finish grades shall be set at 2" below adjacent paving to all for mulch placement.
- Compact all trenches to 90% relative compaction.
- All hardscape, utilities and grades to be per Civil Engineer.
- Owner shall provide audit of finished irrigation system by a certified third party, per the provisions of A.B. 1881. Audit to include recommended maximum seasonal run times (July) and quarterly adjustments to irrigation schedule for each valve.
- The irrigation system shall be installed by a Contractor to conform with all applicable State and local codes and ordinances. The Contractor shall obtain and pay for all required permits and fees
- Do not willfully install the irrigation system as shown when it is obvious in the field that unknown obstructions, grade differences, or differences in the dimensions exist that may not have been considered in the design. Such discrepancies should be brought to the attention of the Owner's representative, in the event that notification is not performed, the Contractor shall assume responsibility for any necessary changes.
- The irrigation system design is based on the minimum pressure and the maximum flow demand as stated on the drawings for each point of connection. Verify the static water pressure, service line size and water meter size prior to construction. Any discrepancies between the actual water pressure, service size and meter size with that indicated on the drawings shall be immediately reported to the Owner's representative as well as the Landscape Architect prior to beginning
- All piping and control wires under paying or walls shall shall be installed in separate PVC sleeves. Mainline sleeves shall be a minimum of 2" diameter. Control wire sleeves shall be of sufficient. size (minimum 1" size) for the required number of wires under the paving.
- 12. All excavations are to be backfilled to 85% compaction (95% compaction under paving) unless
- The location and type of electrical power source shall be reviewed in the field with the Owner's representative and compared with the electrical drawings. Any discrepancies shall be reported to both the Owner's representative and the Landscape Architect.
- Exact routing of irrigation wiring is not shown and shall be determined in the field by the
- All wire splices shall be made within valve boxes. Splices shall be made with copper crimp-type 15. connectors and installed within "3M" #DBY sealing pack, or approved equal.
- Contractor shall submit all material specifications and samples to the Landscape Architect for
- Flush and adjust all distribution heads, drippers and nozzles before use. No overspray onto walks or pavement will be permitted.
- 18. Irrigation equipment not otherwise detailed or specified shall be installed according to the ufacturer's recommendations and specifications.
- Contractor to provide irrigation system audit to be conducted prior to the Owner's acceptance 19 by a certified party per the provisions of State Assembly bill 1881.
- trigation drip and lateral lines shall be looped where possible to insure even pressure

#### Additional Notes:

- 1. This irrigation system utilizes a weather based irrigation controller.
- 2. Pressure regulators are to be installed to ensure dynamic pressure of the system is within the manufacturer's recommended pressure range.
- 3. A manual shut-off valve will be installed at the point of connection of the water supply.
- 4. Areas less than 10 feet in width utilize sub-surface drip irrigation.
- 5. This is a non-residential project with less than 1,000 square feet of landscape area,
- 6. "At the time of final inspection, the permit applicant must provide the owner of the property with a certificate of completion, certificate of installation, irrigation schedule of landscape and irrigation maintenance."
- 7. "Unless contradicted by a soils test, compost at a rate of 4 cubic yards per 1,000 square feet of permeable area shall be incorporated to a depth of six inches into the soil."

7/17/2018 MWELO Note 8/21/2018 Rear Landing

Linn B. Winterbotha

3252 Middlefield

Road

Irrigation Plan

3/7/2018 Scale 1" = 10'-0"

LBW



Schedule Symbol	Label	Quantity	Manufacturer	Catalog Number	Description	Lamp	Filename	Lomens Per	Light Loss Factor	Wattage
	E1	10	Lithonia Lighting	DSXPG LED 20C 530 40K TSW MVOLT	DSXPG PARKING GARAGE FIXTURE WITH 2 LIGHT ENGINES, 530mA DRIVER, 4000K LEDs, T5W OPTIC.	LED	DSXPG_LED_20C_530_40K_T5 W_MVOLT.ies	4288	0.85	37
	E2	4	LIGMAN	MT-31426-VW-W40	Matrix 4 square wall down light	LED	E2 -MT-31426-VW-W40.les	1119	0.85	14.3

Statistics									
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min			
Garage	+	6.2 fc	8.8 fc	1.4 fc	6.3:1	4.4:1			
North Entrance Lower	+	4.6 fc	10.7 fc	0.7 fc	15.3:1	6.6:1			
North Entrance Upper	+	5.5 fc	10.4 fc	1.3 fc	8.0:1	4.2:1			
North Path	+	1.8 fc	6.5 fc	1.0 fc	6.5:1	1.8:1			
North Stair Entrance	+	8.8 fc	11.0 fc	7.3 fc	1.5:1	1.2:1			
Site Exterior	+	1.2 fc	5.6 fc	0.0 fc	N/A	N/A			
West Entrance	+	6.8 fc	10.8 fc	3.2 fc	3.4:1	2.1:1			



Ceiling Height: Varies Luminaire Mounting Height: As Noted Reflectances: 50% for Ceiling, 50% for Wall, 20% for Floor Calculation Point Height: 0' AFF

Luminaire illuminance values provided in this report, whether for normal, critical, or emergency applications, are for product application assistance only. These values were developed in collaboration with, and are subject to approval by, the design professional of record (architect/engineer/LC), and are NOT intended for construction. Because these values are approximate and based on limited application information provided to 16500, Inc. at the time of calculation, 16500, Inc. does not warrant the installed performance of the luminaire(s) will match that shown in this report. Please verify all data and conditions to assure the accuracy of the report. 16500 shall neither be responsible nor liable for design, approval, or results of emergency lighting under any circumstances.

3252 Middlefield Site Lighting Summary