# IMPROVEMENT PLANS

SINGLE FAMILY HOME REMODEL/ ADDITION 216 DEVONSHIRE BLVD., SAN CARLOS, CA 94070



LOCATION MAP



VICINITY MAP

#### SHEET INDEX:

C-2 GRADING AND DRAINAGE PLANS

C-3 UTILITY PLAN

EROSION CONTROL PLAN BEST MANAGEMENT PRACTICES

REFERENCED ASSUMED BENCHMARK: TOP OF SANITARY SEWER MANHOLE LOCATED AT DAVONSHIRE BLVD., IN FRONT OF PROPERTY EL: 100.00'

BASIS OF BEARINGS:

THE BEARING S 42'39'37" W BETWEEN FOUND MONUMENT AT THE INTERSECTION OF DEVONSHIRE BLVD. & HIDDEN VALLEY WAY, AND FOUND 344" IRON PIPE AS SET PER CORNER RECORD 1562, SAM MATEO COUNTY RECORDS, WAS USED AS THE BASS OF BEARINGS SHOWN ON THIS MAP.

#### GEOTECHNICAL REVIEW:

GRADING AND DRAINAGE PLANS SHALL BE REVIEWED AND APPROVED BY THE PROJECT GEOTECHNICAL/ SOILS ENGINEER. GEOTECHNICAL/ SOILS ENGINEER TO PROVIDE AND FURNISH LETTER OF APPROVAL TO CITY.

#### NOTICE TO CONTRACTORS

CONTRACTOR TO NOTIFY U.S.A. (UNDERGROUND SERVICE ALERT) AT 800-227-2600 A MINIMUM OF 2 WORKING DAYS BEFORE BEGINNING UNDERGROUND WORK FOR VERIFICATION OF THE LOCATION AND DEPTH OF UNDERGROUND UTILITIES.



# ABBREVIATIONS DESCRIPTION DE LOW COUNTR LOW COUNTR DO GROUND GROUND OF CONTR OF COUNTR AGGREGATE BASE (CLAS ASPHALT CONCRETE AREA DRAIN BACK OF CURB BACK FLOW WATER PREVENTOR VAL' BOTTOM OF WALL BACK OF WALL CURB AND GUTTER GARAGE FINSH FLOOR (BACK) CENTERLINE CENTERLINE CENTERLINE CENTERLINE SWALE DROP INLET DETAIL ELECTRIC EDGE OF PAYEMENT ELEVATION EUCALYPTUS TREE EXISTING FINISHED FLOOR FINISH GRADE FIRE HYDRANT FLOWLINE FFLOF FFLOF FENCE FOR LINE GRADE BREAK GARAGE FINISHED FLOOR (FRONT) GUY WIRE UNDERGROUND SANITARY SEWER

#### LEGEND

	BBOBITE	
EXISTING	PROPOSED	DESCRIPTION
		PROPERTY LINE
——F——	——F——	FILL AREA LIMIT
c	——с——	CUT AREA LIMIT
	102	CONTOUR
W	w	WATER LINE
SD	sp	STORM DRAIN PIPE (SOLID)
ss	ss	SANITARY SEWER PIPE
SUB	SUÐ	SUBDRAIN PIPE (PERFORATED)
OH e,T,TV	OH e,T,TV	OVERHEAD UTILITIES WITH POLE
—— G ——	—— G ——	GAS LINE
— Е —	— Е —	ELECTRIC LINE (UNDERGROUND)
JT	JТ	JOINT TRENCH
⊠ srv	⊠ srv	STREET LIGHT VAULT
O SSCO	• SSCO	SANITARY SEWER CLEANOUT
0	•	SANITARY SEWER MANHOLE
0	•	STORM DRAIN MANHOLE
₩	₩	ELECTROLIER
₩M	⊠ <sup>wм</sup>	WATER METER
		TREE WITH TRUNK
	_ x x	6' WOODEN FENCE
x102.23_	102.23	SPOT ELEVATION
		TREE PROTECTION FENCE

 $\Rightarrow$ 

SWALE. DETENTION PIPE

(E) TREE TO BE REMOVE

DOWN-SPOUT POP-UP EMITTER

#### UTILITY NOTES:

- CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.
- 2. CONNECT GAS AND ELECTRIC LINES PER PG&E STANDARDS.
- 3. CONTRACTOR SHALL COORDINATE ANY DISRUPTIONS TO EXISTING UTILITY SERVICES WITH ADJACENT PROPERTY OWNERS.
- 4. ALL FLECTRIC, TELEPHONE AND GAS EXTENSIONS INCLUDING SERVICE LINES SHALL BE CONSTRUCTED TO THE APPROPRIATE UTILITY COMPANY
  SPECIFICATIONS. ALL UTILITY DISCONNECTIONS SHALL BE COORDINATED
  WITH THE DESIGNATED UTILITY COMPANIES.
- 5. PRIOR TO THE CONSTRUCTION OF OR CONNECTION TO ANY STORM DRAIN, SANITARY SEWER, WATER MAIN OR ANY OF THE DRY UTILITIES, THE CONTRACTOR SHALL EXCAVATE, VERIFY AND CALCULATE ALL POINTS OF CONNECTION AND ALL UTILITY CROSSING AND INFORM THE OWNER/ DEVELOPER OF ANY CONFLICT OR REQUIRED DEVIATIONS FROM THE PLANS

#### DRAINAGE NOTES

- SURFACE WATER SHALL BE DIRECTED AWAY FROM ALL BUILDINGS INTO DRAINAGE SWALES, GUTTERS, STORM DRAIN INLETS AND DRAINAGE SYSTEMS.
- 2 ALL ROOF DOWNSPOLITS SHALL DISCHARGE TO CONCRETE SPLASH PADS DRAINING AWAY FROM THE FOUNDATION, SEE ARCHITECTURAL PLANS FOR ROOF DOWNSPOUT LOCATIONS

1. FARTHWORK QUANTITIES ON THIS TARLE ARE FOR INFORMATION ONLY CONTRACTORS ARE TO PERFORM THEIR OWN QUANTITY TAKE OFFS.

## EARTHWORK TABLE

LOCATION	CUT (CY)	FILL (CY)	IMPORT (CY)	EXPORT (CY)
POOL	33	0		
BACKYARD PATIO	40	0		
BACKYARD LANDSCAPE	20	0		
EX. CRAWL SPACE FILL	0	8		
TOTAL	93	8	0	85

A. A SEWER PERMIT MUST BE OBTAINED FROM THE PUBLIC WORKS DEPARTMENT PRIOR TO THE START OF ANY SEWER CONSTRUCTION WORK. B. NO GRADING IS PERMITTED BETWEEN OCTOBER 1ST AND APRIL 30TH.

DEPARTMENT PRIOR TO THE START OF CONSTRUCTION.

AN ENCROAD-MAINT PERMIT MUST BE GRITANDE FROM THE PUBLIC WORKS
DEPARTMENT PRIOR TO START OF ANY WORK WITHIN THE PUBLIC RIGHT-OF-WAY
OR A PUBLIC UNITIES EASEMENT INCLUDING, BUT NOT LIMITED TO, THE
INSTALLATION OF SEWERS AND OTHER UTILITIES, SIDEWALK, CURB AND GUTTER,
NEWWAY AFRON, WALL EFENCE, OF OTHER CONSTRUCTION, AN ENCROLOMBENT
PERMIT IS ALSO RECORDED FOR THE PLACEMENT OF DERRIS BOXES, STOTIONE
ON TARRESS, OF CONSTRUCTION MATERIALS WITHIN THE PUBLIC RIGHT—OF—WAY.

A GRADING/HAULING PERMIT MUST BE OBTAINED FROM THE PUBLIC WORKS DEPARTMENT PRIOR TO THE START OF CONSTRUCTION.

#### NOTES:

NOTE:

ENGINEERS CIVIL ENGINEERS

John Kubodera 216 Devonshire Blvd San Carlos, CA 94070 (650) 302-0658 kubo99@hulamail.com

COPYRIGHT © 2019 SMP ENGINEERS CIVIL ENGINEERS

PLANS -/ ADDITION

GRADING AND DRAINAGE PL.
VGLE FAMILY HOME REMODEL/ A
216 DEVONSHIRE BLVD.
SAN CARLOS, CA 94070 SINGLE





5/16/2019


V.G. Checked by:


S.R. Job #: 219046

> 1 OF 6 C-1












#### SPECIAL PROVISIONS -2019

- NO PRECEDENT ENTABLISHEE. This Permit is granted with the understanding that this action is not to be considered as establishing any perceden on the question of the expediency of premiting any certain hind of encenachment to be exected within right of way of Charly streets, roads, highways or other
- KEEP PERMIT ON THE SITE. T is Permit or a copy thereof shall be kept at the site of work and q must be shown oney representative of that department or any law enforcement officer on densad.

TerMethod Individual Meeting Average Nethern Test Coffernia

76 minutes 27 28 minutes 31 minutes 29 35 minutes



EARTH SWALE DETAIL

1534 CAROB LANE LOS ALTOS, CA 94024 TEL: (650) 941-8055 FAX: (650) 941-8755 OWNER: John Kubodera 216 Devonshire Blvd San Carlos, CA 94070 (650) 302-0658 kubo99@hulamail.com

SMP

ENGINEERS

CIVIL ENGINEERS

COPYRIGHT © 2019 SMP ENGINEERS CIVIL ENGINEERS

GRADING AND DRAINAGE PLANS SINGLE FAMILY HOME REMODEL/ ADDITION 216 DEVONSHIRE BLVD, SAN CARLOS, CA 94070

Revisions

EXPRES 12-31-2020 No. 052724

5/16/2019 V.G. Checked by:

S.R. Job #: 219046 4 OF 6 C-4

#### PIPES, CONDUITSGAS PUMPS, ETC.

- 20. BACKTILLING. Buckfilling operators shall conform to the following requirements. Across roadway section, cuths, identalize, and other parestrated arose, natural for our as extrate bedrift shall have a surjective facility shall be on a quitaber of not less than 20. The procuepe composition by weight as detertalmentary sieres shall conform to following grading:

21. SURFACE MATERIALS. SCHPACE MATERIALS.

A ACCOUNT BOWN Misseral aggregate material removed shall be placed with a 34° maximum Class 2 Aggregate Base Material, and shall conferen to Section 3 of the Studied Specifications of the Gousty of San Mateo. The proceeding composaishot by weight of aggregates the shall conferen to the following grading when determined by Test Method No California 202 modified by Test Method No California 202 mod gradual processing and the second process of the secon Sieve Size Individual Test Percentage Passing Siever Mexing Average 1" 100 50" 87 - 100 No. 4 30 - 60 100 90 – 100 35 – 55



3" 100 No. 4 35 – 100 No. 30 20 - 100

24. WATER POLLUTION COUTROL

8. GENERAL CLEAT UP. Upon completion of the work, all breath, timber, scraps and material shall be entirely removed from the right of-way and argy axes affected by the work shall be life in a presentable condition, and to the unsidedicing of the Discrete of Public Works, Alterion is also directed to Section 24, "Water Publisher Control," of this document, and the publisher control, and the publisher control, and the publisher control of the document of the publisher control of the publi

Totalistic Centric.\* of this advanted.

STANDARDS OF "ONNTRUCTION." All works shall conform to the Standard Specifications of the Centry of Stan Mates, State of California, which me chemical with the Standard Specifications, May 2006 of the State of California, which we also considered with the Standard Specifications, May 2006 of the State of California, Basiness and Transportation, except on the Standard Specification of the Control State Office of California, except on the California California (California) of the California California (California) of California (California) (Cali

10. SUPERVISION BY DIRECTOR OF PUBLIC WORKS. All the works shall be done arbited to the supervision of and to the satisfaction of the Director of

the institution at the towe repease of the returnine.

I. EXPENS OF INSTITCTION. From which strengtism the presence of an Inspector set Engineer of the Department, the costs associated with salary, rare-ling expectors, toses constrained and extri includents able paid by the Partition. The Partition may be required to deposit with the Department can in an extent determined by the Determined Policy Micross to self-fixed tent sover the articipant count of inspections. Any remaining balance shall be refunded to the Partition ages conception and accuracy of the partition of the Partition of the Conference of the partition of the Partition of the Conference of the partition of the Partition of the Conference of the partition of the Partition of the Conference of the partition of the Partition of the Conference of the partition of the Partition of the Conference of the partition of the Partition of the Partition of the Conference of the partition of t

the Permise upon completion and comprose of the positivate word.

LIMILITY IOR DIAMAGES. The Permise is required to sell initially for ground injury or proposely along the firm are saint and of work became permised to add the region of the "Diamage" in the "Diamage" in the procession of the "Diamage" in the procession of the contract of the contract of the diamage in the contract of the date or are propagation, effect, or thinking in made gained the Contract of the Materia or are propagation, effect, or the sainties from so and date. This is breath that the effective first any proper unders and until the above named Permiser files with the Diamage in the sainties from so and date that the procession of the date of the property dates and seat until the above named Permiser files with the Diamage in the sainties from so add the property Diamage in the areas out of 3.

The Permiser and facing Williamage is the Permiser of the property Diamage in the areas out of 3.

The Permiser and facing Williamage is the Permiser of the Pe

MAKING REPAIRS. If the Director of Public Works shall so elect, repairs paving and other improvements which have been disturbed shall be made by employees of the Department and the expenses therefor shall be been by the

HOUSE DOWNSPOUTS SEE ARCHITECTURAL PLANS - CONCRETE SPLASH BLOCK MIN. 24"\_\_\_\_ NATIVE GRADE OR CERTIFIED COMPACTED SUBGRADE 2X4 RED WOOD HEADER SPLASH BLOCK

21 3/4" X 23 1/4" CONC.

V24 DRAIN BOX W/ 18" X 19 1/2" GRATE TG (SEE PLAN) 6" TO 12" NATIVE BACKFILL OR TOP SOIL . ORIGINAL GROUND ® ® TEE 3/4" DRAIN ROCK PEA SIZE CLEAN (NO FINES) FILTER FABRIC ENCLOSE ALL ROCK SURFACES 6"ø PERFORATED PVC LENGTH PER PLAN


DETENTION BASIN FIFVATION VIEW- NTS

#### Tire Washing

#### Concrete and Mortar

James C. Porter Director of Public Works July 2019

All wastes shall be disposed of properly outside the highway right of-way and, where applicable, in accordance with the Permittee's approved Construction Waste Management



WOOD STAKES OR PLAN VIEW

- EX. DRIVEWAY

NOTES:

1. PLACE FIBER ROLLS AROUND THE INLET CONSISTENT WITH BASIN SEDIMENT BARRIER DETAIL ON THIS SHEET, FIBER ROLLS ARE TUBES MADE FROM STRAW BOUND W/ PLASTIC NETTING. THEY ARE APPROX. 8 DIA. AND 20 — 30 FT. LONG 2. FIBER ROLL INSTALLATION REQUIRES
THE PLACEMENT AND SECURE STAKING O
THE RIBER ROLL IN A TRENCH, 3" DEEP,
DUG ON CONTOUR. RUNOFF MUST NOT
BE ALLOWED TO RUN UNDER OR AROUNI
FIBER ROLL.

FIBER ROLL

3. THE TOP OF THE STRUCTURE (PONDIN
HEIGHT) MUST BE WILL BELOW THE
HEIGHT BOWNER OF SING THE
HEIGHT ENDIFF ROWNER OF SING THE
HILET EXAMINED FOR A TEMPORATION
TO THE DROP NILET OR A TEMPORATION
TO THE DROWNER OF THE
STRUCTURE MAY BE NECESSARY.

STRUCTURE MAY BE NECESSARY.

4. FOSSIL FILERS SHALL BE NOORPORATED IN ALL CATCH BASINS / FED INCORPORATED IN ALL CATCH BASINS / FED INSTALLED PER MANUFACTURER SPECIFICATIONS. FOSSIL FILERS ARE AVAILABLE FROM KETSAR ENTERPRISES NC., 422 LARKFIELD CENTER, SUITE 2 SANTA ROSA, CA 95403, PHONE (800) 573—8819.

(650) 302-0658 kubo99@hulamail.com

OWNER: John Kubodera 216 Devonshire Blvd San Carlos, CA 94070

COPYRIGHT © 2019 SMP ENGINEERS CIVIL ENGINEERS

SMI

ENGINEERS

CIVIL ENGINEERS

1534 CAROB LANE LOS ALTOS, CA 94024 TEL: (650) 941-8055 FAX: (650) 941-8755

PLANS -/ ADDITION BLVD. 94070 G AND DRAINAGE F IILY HOME REMODEL/ 3 DEVONSHIRE BLVD., N CARLOS, CA 94070 FAMILY GRADING SAN

¥

₫

SINGLE

EXPRES 12-31-2020 No. C52724

5/16/2019

1" = 20

V.G.

Checked by:

S.R. Job #: 219046

5 OF 6 C-5

3. Install fiber roll 12\* from limit of grading

Place fiber roll in key trench 3\* deep and place excavated soil on uphill or flow side of the roll.
 On slopes and hilliades, floer rolls shall be abutted at the ends and not overlapped. Place alternate stakes on both sides of the roll, every 6.

STRAW FIBER ROLLS FOSSIL FILTER -SECTION A - A

PROFILE

Maintenance

The entronce shall be maintained in a condition that still prevent tracking in the prevent country and the prevent country measures used to trap sediment.

The prevent country and the prevent country measures used to trap sediment.

The prevent country and the prevent country measures used to trap sediment.

The prevent country and the prevent country

STABILIZED CONSTRUCTION ENTRANCE (TO BE MAINTAINED)

EROSION AND SERIMENT CONTROL NOTES AND MEASURES

1. The facilities shown on this Prior or designed to control Erosion and sediment during the rainty season, October 1st to April 20th. Facilities are to be operable prior to Debber 1 of any year. Creding the processing of the prior of the pri

8. This erosion and sediment control plan may not cover all the situations that may arise during construction due to unanticipated field conditions. Variations and additions may be made to this plan in the field. Notify the city representative of any field changes.

9. This plan is intended to be used for interim erosion and sediment controlly and is not to be used for final elevations or permanent improvements.

11. Reasonable care shall be taken when hauling any earth, sand, gravel, stone, debris, paper or any other substance over any public street, alley or other public place. Should any blow, spill, or track over and upon said public or adjacent private property, immediately remedy shall occur.

SECTION B-B

STORM INLET SEDIMENT TRAP-FIBER ROLLS N.T.S.

PERSPECTIVE

TEMPORARY COVER ON STOCK PILE

N.T.S.

12. Sanitary facilities shall be maintained on the site.

NTS

SILT BAG/ FILTER TO BE REGULARLY MAINTAINED

8

GRAVEL BAGS-STACKED 2 HIGH

FLOW

EXISTING DRAINAGE INLET PROTECTION

0

10. During the rainy season, all paved areas shall be kept clear of earth material and debris. The site shall be maintained so as to minimize sediment laden runoff to any starm drainage systems, including existing drainage swales and water courses.

13. Construction operations shall be carried out in such a manner that erosion and water pollution will be minimized. State and local laws concerning pollution abotement shall be compiled with.

14. Contractors shall provide dust control as required by the appropriate federal, state, and local agency requirements.

13. With the approval of the city inspector, erosion and sediment controls maybe removed after areas above them have been stabilized.

MAINTENANCE NOTES

MANTEMANCE NOTES

A. Repair demogase caused by soil erosion or construction at the end of each working day.

G. Western and the impact of the control of the end of each working day.

G. Western shall be impacted in the control of t

2. All existing drainage inlets on St. George Lone within the limit of the project, shall be protected with sand bogs during construction. See detail. Sand bog inlet protection shall be cleaned out whenever sediment depth is one half the height of one sand bog.

Existing concrete ditch sediment trap shall be cleaned out routinely during construction.

(E) CATCH BASIN-

FLOW

EROSION AND SEDIMENT CONTROL NOTES AND MEASURES

3" TO 5" . AGGREGATE

(E) CURB & GUTTER-

PLAN

city.

5. If hydroseeding is not used or or is not effectively 10/10, then other immediate methods shall be implemented, such as Erosian or Erosian for the mediate methods shall be implemented, such as Erosian in the fertilizer 2) bloom strow 3) tocklifer and mulch.

6. Inlet protection shall be installed at open inlets to prevent additionat from entering the storm drin system, initiat not used in conjunction with erosian control are to be blocked to prevent entry?

7. Lots with busses under construction will not be hydroseeded Erosian protection for each lot with a house under construction shall confirm to the "blocked to prevent entry the confirm to the "blocked to prevent entry" in the confirm to the "blocked to prevent entry" in the confirm to the "blocked to prevent entry the confirmation that the confirmat

Contractor shall be responsible for monitoring erosion and sediment control prior, during, and after storm events.



# **Construction Best Management Practices (BMPs)**

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

Clean Water. Healthy Community.

#### Materials & Waste Management



#### Non-Hazardous Materials

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within
- ☐ Use (but don't overuse) reclaimed water for dust control.

#### Hazardous Materials

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- □ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecas
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes

#### Waste Management

- ☐ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the
- ☐ Clean or replace portable toilets, and inspect them frequently for
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- $\hfill\square$  Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste

#### Construction Entrances and Perimeter

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

#### Equipment Management & **Spill Control**



#### Maintenance and Parking

- Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- $\square$  Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment

#### Spill Prevention and Control

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly
- ☐ Do not hose down surfaces where fluids have spilled Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- ☐ Sweep up spilled dry materials immediately. Do not
- try to wash them away with water, or bury them ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil
- ☐ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

#### **Earthmoving**



- ☐ Schedule grading and excavation work during dry weather
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- □ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets

#### Contaminated Soils

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board
- Unusual soil conditions, discoloration, or odor
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash

#### Paving/Asphalt Work



- ☐ Avoid paving and seal coating inwet weather or when rain is forecast to prevent materials that have not cured from contacting stormwater runoff. Cover storm drain inlets and marholes
- when applying seal coat, tack coat, slurry seal, fog seal, etc. ☐ Collect and recycle or appropriately dispose of excess abrasive gravelor sand.
- Do NOT sweep or wash it into gutters. □ Do not use water to wash down fesh asphalt concrete pavement.

#### Sawcutting & Asphalt/Concrete Removal

- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-:ut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.



Concrete, Grout & Mortar

- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas Let concrete harden and dispose of as garbage
- When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly

# Landscaping



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under
- ☐ Stack bagged material on pallets and
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

#### Painting & Paint Removal



- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of
- ☐ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.

#### Dewatering



- runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for



#### Painting Cleanup and Removal

- drain, or stream
- Never pour paint down a storm drain.
- excess liquids as hazardous waste.
- ☐ Chemical paint stripping residue and chips

- ☐ Discharges of groundwater or captured discharging to the sanitary sewer call your local wastewater treatment plant.
- ☐ Divert run-on water from offsite away from all disturbed areas.
- treatment and proper disposal

Storm drain polluters may be liable for fines of up to \$10,000 per day!



CIVIL ENGINEERS

John Kubodero 216 Devonshire Blvd San Carlos, CA 94070 (650) 302-0658 kubo99@hulamail.com

IG AND DRAINAGE PLANS
IILY HOME REMODEL/ ADDITION
6 DEVONSHIRE BLVD.
IN CARLOS, CA 94070

SINGLE

GRADING



5/16/2019 AS NOTED V.G.

SR

219046 6 OF 6

C-6





# C.3 and C.6 Development Review Checklist

Municipal Regional Stormwater Permit (MRP) Stormwater Controls for Development Projects

Project Informati	on	
	.3 Regulated Projects," data will be reported in the municipality's stormwate	er Annual Report.)
Project Name:	216 DEVONSHIRE	Case Number:
Project Address & Cross St	216 DEVONSHIRE BLVD., SAN CARLOS, CA 94070	
Project APN:	APN: 049-110-160 Project Watershed: PULGAS	CREEK
Applicant Name:	7.11.10.10.110.100	I.A.4 Slope on Site: 3.1
Applicant Phone:	Applicant Email Address:	1.7.4 Clope on cite. 3.1
Development type: (check all that apply)  I.A.1	Single Family Residential: A stand-alone home that is not part  Single Family Residential: Two or more lot residential develop  Multi-Family Residential  Commercial  Industrial, Manufacturing  Mixed-Use  Streets, Roads², etc.  'Redevelopment' as defined by MRP: creating, adding and/or impervious surface on a site where past development has occur impervious surface on a	# of units:  # of units:  # of units:  replacing exterior existing curred. service facilities <sup>3</sup> , (2) retail gasoline
Project Description <sup>4</sup> : (Also note any past or future phases of the project.)	Other, Please specifySINGLE FAMILY HOME REMODEL/ ADDITION	
I.A.2 Total Area of Site:		stockpile area): 0.18 acres.
I.A.5 Certification: I certify that the information pr	ovided on this form is correct and acknowledge that, should the projurface provided in this form, the as-built project may be subject to ac	iect exceed the amount of new
☐ Attach Preliminary Calcula	tions  Attach Final Calculations	an showing areas
Name of person completing th		le: CIVIL ENGINEER
Signature:	Date of the second seco	te: <u>9-26-2019</u>
Phone number: 650-941-805	55 Email address: SRAZAVI@SMPEN	NGINEERS.COM

<sup>&</sup>lt;sup>1</sup> Common Plans of Development (subdivisions or contiguous, commonly owned lots, for the construction of two or more homes developed within 1 year of each other) are not considered single family projects by the MRP.

<sup>&</sup>lt;sup>2</sup> Roadway projects creating 10,000 sq.ft. or more of contiguous impervious surface are subject to C.3 requirements if the roadway is new or being widened with additional traffic lanes.

<sup>&</sup>lt;sup>3</sup> See Standard Industrial Classification (SIC) codes <u>here</u>

<sup>&</sup>lt;sup>4</sup> Project description examples: 5-story office building, industrial warehouse, residential with five 4-story buildings for 200 condominiums, etc.

## I.B Is the project a "C.3 Regulated Project" per MRP Provision C.3.b?

## I.B.1 Enter the amount of impervious surface<sup>5</sup> Retained, Replaced and/or Created by the project:

## Table I.B.1 Impervious<sup>5</sup> and Pervious Surfaces

	I.B.1.a	I.B.1.b	I.B.1.c	I.B.1.d	I.B.1.e
Type of Impervious <sup>5</sup> Surface	Pre-Project Impervious <sup>5</sup> Surface (sq.ft.)	Existing Impervious <sup>5</sup> Surface to be Retained <sup>6</sup> (sq.ft.)	Existing Impervious <sup>5</sup> Surface to be Replaced <sup>6</sup> (sq.ft.)	New Impervious <sup>5</sup> Surface to be Created <sup>6</sup> (sq.ft.)	Post-Project Impervious <sup>5</sup> Surface (sq.ft.) (=b+c+d)
Roof area(s)	2851	2398		Big Assess	2398
Impervious <sup>5</sup> sidewalks, patios, paths, driveways, streets	4045	1917	1019	344	3280
Impervious <sup>5</sup> uncovered parking <sup>7</sup>					0
Totals of Impervious Surfaces:	6896	4315	1019	344	5678
I.B.1.f - Total Impervious <sup>5</sup> Surface Replaced and Create	ed (sum of totals	for columns I.B	.1.c and I.B.1.d)		
Type of Pervious Surface	Pre-Project Pervious Surface (sq.ft.)				Post-project Pervious Surface (sq.ft.)
Landscaping	4299				5517
Pervious Paving				I.B.1.e.1:	
Green Roof				Solo Sala Sala Sala Sala Sala Sala Sala	
	Charles and the comment of the party of				
Totals of Pervious Surfaces:	4299				5517

# I.B.2 Please review and attach additional worksheets as required below using the Total Impervious Surface (IS) Replaced and Created in cell I.B.1.f from Table I.B.1 above and other factors:

	Check all that apply:	Check One		Attach
		Yes	No	Workshee
I.B.2.a	Does this project involve any earthwork? If YES, then Check Yes, and Complete Worksheet A. If NO, then go to I.B.2.b	Ø		Α
1.B.2.b	Is I.B.1.f greater than or equal to 2,500 sq.ft?  If YES, then the Project is subject to Provision C.3.i complete Worksheets B, C & go to I.B.2.c.  If NO, then Stop here - go to I.A.5 and complete Certification or ask municipal staff for Small Project Checklist.		Ø	B, C
I.B.2.c	Is the total Existing IS to be Replaced (column I.B.1.c) 50 percent or more of the total Pre-Project IS (column I.B.1.a)? If YES, site design, source control and treatment requirements apply to the whole site. Continue to I.B.2.d If NO, these requirements apply only to the impervious surface created and/or replaced. Continue to I.B.2.d			
I.B.2.d	Is this project a Special Land Use Category (I.A.1) and is I.B.1.f greater than or equal to 5,000 sq.ft? If YES, project is a Regulated Project. Fill out Worksheet D. Go to I.B.2.f. If NO, go to I.B.2.e			D
I.B.2.e	Is I.B.1.f greater than or equal to 10,000 sq.ft?  If YES, project is a C.3 Regulated Project - complete Worksheet D. Then continue to I.B.2.f.  If NO, then skip to I.B.2.g.			D
I.B.2.f	Is I.B.1.f greater than or equal to 43,560 sq.ft?  If YES, project may be subject to Hydromodification Management requirements - complete Worksheet E then continue to I.B.2.g.  If NO, then go to I.B.2.g.			E
I.B.2.g	Is I.A.3 greater than or equal to 1 acre? If YES, check box, obtain coverage under the CA Const. General Permit & submit Notice of Intent to municipality - go to I.B.2.h. If NO, then go to I.B.2.h. For more information see: www.swrcb.ca.gov/water_issues/programs/stormwater/construction.shtml			
I.B.2.h	Is this a Special Project or does it have the potential to be a Special Project? If YES, complete Worksheet F - then continue to I.B.2.i. If NO, go to I.B.2.i.			F
I.B.2.i	Is project a High Priority Site? (Determined by the Municipality. High Priority Sites can include those located in or within 100 feet of a sensitive habitat, an Area of Special Biological Significance, a body of water, or starting 7/1/16 on sites disturbing >=5,000 ft² with slopes >=15% (see I.A.4) (or per municipal criteria/map) and are subject to monthly inspections from Oct 1 to April 30.) If YES, complete section G-2 on Worksheet G - then continue to I.B.2.j.  If NO, then go to I.B.2.j			G
I.B. <mark>2</mark> .j	For Municipal Staff Use Only: Are you using Alternative Certification for the project review?  If YES, then fill out section G-1 on Worksheet G. Fill out other sections of Worksheet G as appropriate.  See cell I.B.1.e.1 above - Is the project installing 3,000 square feet or more of pervious paving?  If YES, then fill out section G-3 on Worksheet G. Add to Municipal Inspection Lists (C.3.h)			G

<sup>&</sup>lt;sup>5</sup> Per the MRP, pavement that meets the following definition of pervious pavement is NOT an impervious surface. Pervious pavement is defined as pavement that stores and infiltrates rainfall at a rate equal to immediately surrounding unpaved, landscaped areas, or that stores and infiltrates the rainfall runoff volume described in Provision C.3.

<sup>7</sup> Uncovered parking includes the top level of a parking structure.

<sup>&</sup>lt;sup>6</sup> "Retained" means to leave existing impervious surfaces in place, unchanged; "Replaced" means to install new impervious surface where existing impervious surface is removed anywhere on the same property; and "Created" means the amount of new impervious surface being proposed which exceeds the total existing amount of impervious surface at the property.



# Hydrology calculation FOR DEVLOPEMENT AT

## 216 DEVONSHIRE BLVD., SAN CARLOS, CA 94070

**May 2019** 

BY SMP ENGINEERS 1534 CAROB LANE LOS ALTOS, CA 94024



STORM DRAIN CALCULATION NEW SINGLE FAMILY HOUSE 216 DEVONSHIRE BLVD., SAN CARLOS, CA 94070

#### **ASSUMPTIONS:**

RATIONAL METHOD HAS BEEN USED. PER SAN MATO COUNTY DRAINAGE MANUAL.

SINCE SITE IS NOT BOUNDING AN EXISTING DRAINAGE COURSE LOCATED ON AND ADJACENT TO THE PROPERTY,

CALCULATION IS DONE FOR A 10 YEAR STORM.

DURATION OF RAIN TO BE MINIMUM CONCENTRATION TIME (10 MINUTES), PRE OR POST DEVELOPMENT,

WHICHEVER IS LONGER, WHEN FLOW REACHES THE PEAK.

DETENTION BASINS TO BE SIZED TO HOLD ADDITIONAL WATER RUN-OFF IN SITE.

#### **PER-DEVELOPMENT WATERSHED TABLE:**

DESCRIPTION:	AREA (SQFT)	AREA (ACRES)	MATERIAL	С	C x AREA
EX. HOUSE	2,851	0.065	ROOF	0.9	2566
EX. FRONT PORCH & WALKWAY	167	0.004	CONC.	0.9	150
EX. DRIVEWAY	1,801	0.041	AC	0.9	1621
EX. BACKYARD PATIO	2,077	0.048	CONC.	0.9	1869
TOTAL OF IMPERVIOUS AREA:	6,896	0.158	IMPERVIOUS		
LANDSCAPE / GROUND	4,299	0.099	L/S, GROUND	0.1	430
TOTAL OF PERVIOUS AREAS	4,299	0.099	PERVIOUS		
TOTAL SITE AREA	11,195	0.257			6,636

WEIGHTED AVERAGE  $C=\Sigma(CXA)/\Sigma A=$ 

0.593

RUNOFF COEFFICIENT

#### Concentration time (Tc) in minutes

C =	0.593 UNITLESS	
L =	170 FEET	ALONG BACKYARD & SIDE YARD
HIGH POINT ELEVATION =	107 FEET	WESTERLY PROPERTY CORNER
LOW POINT ELEVATION =	101.5 FEET	EASTERLY PROPERTY CORNER
ELEVATION DROP (H) =	5.5 FEET	
SLOPE (S)= 100 X H / L=	3.2 %	
Tc1=[1.8 (1.1-C)√L]/(S <sup>1/3</sup> )=	8.0 minutes	
Tc (MINIMUM) =	10.0 minutes	PER SAN MATO COUNTY DRAINAGE MANUAL,
SO USE Tc=	10.0 minutes	

### Rainfall Intensity (I) 10 YEAR STORM

 $I_{10 \text{ yr}, 10 \text{ MINUTES}} = 2.45 \text{ inches/hr}$ 

Per SAN MATEO COUNTY RAINFALL RUNOFF DATA, TABLE

## **INTENSITY FACTOR:**

F= 0.8 UNITLESS

Per SAN MATEO COUNTY RAINFALL RUNOFF DATA MAP FOR SAN CARLOS

### Flow calculation, PRE DEVELOPMENT

 I =
 2.45 inches/hr

 C =
 0.593

 A =
 0.257 acres

 F=
 0.80

 Q = I.C.A.F. =
 0.299 CFS

PRE DEVELOPMENT STORM RUN-OFF VOLUME, Tc (PRE) DURATION, RECLINE LIMB FACTOR= 1.0

V (PRE-DEVELOPMENT)=Q X Tc (PRE) X 60 (SEC/MIN) = 179 CF

(Rational method)

## **POST-DEVELOPMENT WATERSHED TABLE:**

DESCRIPTION:	AREA (SQFT)	AREA (ACRES)	MATERIAL	С	C x AREA
HOUSE	2,399	0.055	ROOFING	0.9	2,159
FRONT PORCH	167	0.004	CONC.	0.9	150
EX. DRIVEWAY	1,750	0.040	AC	0.9	1,575
PATIO AND WALKWAY	1,362	0.031	PAVER STONE	0.9	1,226
CREDIT FOR HARDSCAPE IN BACKYARD	1,900	0.044	PAVER STONE/ CONC	0.9	1,710
TOTAL OF IMPERVIOUS AREA:	7,578	0.174	IMPERVIOUS		
LANDSCAPE / GROUND	3,617	0.083	LANDSCAPE, GROUND	0.1	362
TOTAL OF PERVIOUS AREAS	3,617	0.083	PERVIOUS		
TOTAL SITE AREA	11,195	0.257			7,182

0.642

(Rational method)

OK

WEIGHTED AVERAGE  $C=\Sigma(CXA)/\Sigma A=0.642$  RUNOFF COEFFICIENT

#### Concentration time (Tc) in minutes

C -	0.042
ONGEST TRAVEL PATH OF WATER REMAIN UNCHANGED	
L=	170 FEET
HIGH POINT ELEVATION =	107 FEET
LOW POINT ELEVATION =	101.5 FEET
ELEVATION DROP (H) =	5.5 FEET
SLOPE (S)= 100 X H / L=	3.2 %
$Tc1=[1.8 (1.1-C)\sqrt{L}]/(S^{1/3})=$	7.3 minutes
Tc (MINIMUM) =	10.0 minutes
SO USE Tc=	10.0 minutes

## Rainfall Intensity (I) 10 YEAR STORM

I 10 YR, 10 MINUTES = 2.45 inches/hr

Per SAN MATEO COUNTY RAINFALL RUNOFF DATA, TABLE

### **INTENSITY FACTOR:**

F= 0.8 UNITLESS

Per SAN MATEO COUNTY RAINFALL RUNOFF DATA MAP FOR SAN CARLOS

## Flow calculation, POST DEVELOPMENT

 I =
 2.45 inches/hr

 C =
 0.642

 A =
 0.257 acres

 F=
 0.80

 Q = I.C.A.F. =
 0.323 CFS

#### POST DEVELOPMENT STORM RUN-OFF VOLUME,

Tc DURATION, RECLINE LIMB FACTOR= 1.0

V (POST-DEVELOPMENT)=Q X Tc (PRE) X 60 = 194 CF

DIFFERENCE OF RUN-OFF TO BE STORED IN SITE

V= V (POST) - V (PRE)= 15 CF

**USE DETENTION BASIN WITH DRAIN ROCK 30% VOID SPACE** 

V <sub>(REQ.)</sub>=V / 0.35= 42 CF

**ESTIMATE DEPTH AND AREA OF DETENTION BASIN** 

DEPTH (D )= 2 FT  $A_{(REQ.)} = V_{(REQ.)} / (D) =$  21.0 SQFT

**ESTIMATE QUANTITY AND SIZE OF EACH DETENTION BASIN** 

 NUMBER OF DETENTION BASINS (N) =
 1

 LENGTH (L) =
 8 FT

 WIDTH (W) =
 3 FT

 A (DESIGN) = N X L X W =
 24.0 SQFT

 SHOULD BE MORE THAN A (REQ.) =
 21.0 SQFT

SO USE 1 DETENTION BASIN, 8 FT LONG, 3 FT WIDE  $\,$  AND 2 FT DEEP.

V  $_{(DESIGN)}$  = N X L X W X D = 48.0 CF SHOULD BE MORE THAN V  $_{(REQ.)}$  42.1 CF OK