
GENERAL NOTES

CONTRACTOR SHALL ADHERE TO ALL CODES, RULES, AND REGULATIONS GOVERNING CONSTRUCTION, BUILDING ACCESS AND THE USE OF FACILITIES AS SET BY LOCAL BUILDING DEPARTMENT AGENCY AND THE BUILDING OWNERS. TITLE 24 C.A.C ESPECIALLY THOSE ABSTRACTS DEALING WITH ENERGY AND HANDICAPPED ACCESS REQUIREMENTS. ANYTHING SHOWN ON THESE DRAWINGS, NOT IN ACCORDANCE WITH THESE RULES AND REGULATIONS, SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGNER BEFORE PROCEEDING WITH ANY WORK.

- DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONAL INFORMATION.
- THE CONTRACTOR AND SUBCONTRACTORS SHALL VERIFY ALL CONDITIONS AND DIMENSIONS IN THE FIELD. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE DESIGNER OF ANY CONFLICTS HEREIN, EITHER APPARENT OR OBVIOUS PRIOR TO START OF WORK ON THAT ITEM OR BEAR THE RESPONSIBILITY OF CORRECTING SUCH WORK AS DIRECTED BY THE ARCHITECT.
- ALL WORK SHALL BE DONE IN A FIRST CLASS WORKMANLIKE MANNER BY MECHANICS SKILLED IN THEIR RESPECTIVE TRADES.
- THE CONTRACTOR SHALL REVIEW PLANS AND THE AREA OF CONSTRUCTION CAREFULLY TO INSURE FULL UNDERSTANDING OF EXACT SCOPE OF WORK. THE ARCHITECT WILL BE AVAILABLE TO REVIEW ALL WORK ON SITE AND RESOLVE ANY UNCLEAR ITEMS
- THE CONTRACTOR SHALL CONTACT THE BUILDING MANAGEMENT TO BE ADVISED OF THE RULES OF THE BUILDING WITH RESPECT TO CONSTRUCTION, WHEN AND HOW DELIVERIES AND/OR REMOVALS CAN BE DONE ON REGULAR OR OVERTIME AND IN GENERAL, ANY BUILDING REQUIREMENTS WHICH WILL AFFECT THEIR WORK.
- THE CONTRACTOR SHALL SUBMIT TO THE ARCHITECT ALL FABRICATION SHOP DWGS. AND FIXTURE CUTS FOR APPROVAL AFTER HAVING CHECKED AND APPROVED THEM FIRST, WHERE APPLICABLE
- THE CONTRACTOR SHALL FURNISH A SYSTEM OF TEMPORARY LIGHTS AND WATER THROUGHOUT THE SPACE UNDER CONSTRUCTION, IF REQUIRED.
- THE CONTRACTOR SHALL REMOVE FROM THE BUILDING ALL RUBBISH AND WASTE MATERIALS, FOR HIS OWN SUBCONTRACTING. IF REQUIRED.
- 10. NO WORK DEPENDING ON PARTITION LOCATIONS SHALL BE DONE UNTIL THE CONTRACTOR HAS MARKED PARTITION LOCATIONS ON THE FLOOR SLAB IN THE FIELD AND THE ARCHITECT HAS APPROVED THEM.
- 11. THE CONTRACTOR SHALL LEAVE THE PREMISES IN A CLEAN AND ORDERLY MANNER.
- 12. THE CONTRACTOR'S PRICE IS TO BE COMPLETE IN ALL WAYS INCLUDING TAXES, OVER-TIME, SHIPPING, ETC.
- 13. ALL MATERIALS AND INSTALLATIONS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S LATEST PRINTED SPECIFICATIONS AND WITH CODE REQUIREMENTS.
- 14. THE WORK INCLUDED UNDER THIS CONTRACT SHALL BE DONE IN ACCORDANCE WITH AIA GENERAL CONDITIONS DOCUMENT A-201, 1991 EDITION.
- . CONTRACTORS, SUBCONTRACTORS AND SUPPLIERS SHALL GUARANTEE THAT THE WORK IS FREE FROM ANY DEFECTS IN WORKMANSHIP AND MATERIALS FOR A PERIOD OF ONE YEAR FROM DATE OF COMPLETION AND BE RESPONSIBLE FOR REPAIR OR REPLACEMENT AT NO ADDITIONAL CHARGE.
- 6. CONTRACTORS TO CARRY EMPLOYER'S LIABILITY INSURANCE OF NOT LESS THAN \$1,000,000 PER OCCURRENCE, AND COMPREHENSIVE GENERAL LIABILITY OF AT LEAST \$2,000,000 COMBINED SINGLE LIMIT FOR BODILY INJURY, DEATH, OR PROPERTY DAMAGE THE POLICIES TO ALSO COVER LANDLORD AND TENANT AS ADDITIONAL INSURED.


SYMBOLS



SITE PLAN 1/8"=1'-0"	Constructions and specifications as specifications as specifications as specifications as specifications as marked by the protection of th
ASPHALT BERM	ONU ONU ONU ONU INC. ONU ONU ONU San FRANCISCO ONU ONU ONU CAN FRANCISCO ONU ONU ONU TEL (415) 512-7566 Subelia San FRANCISCO CA 94107 TEL (415) 512-7566 Subelia Subelia ONU ONU TEL (415) 512-7566 Subelia San FRANCISCO CA 94107 Tel (415) 512-7566 Subelia Subelia ONU ONU TEL (415) 512-7566 Subelia ONU Tel (415) 512-7566 Subelia Subelia ONU Tel (415) 512-7566 Subelia Subelia Subelia Tel (415) 512-7566 Subelia Subelia OULD Tel (415) 700 FRICERATIONS, AS Subelia Subelia
BITHE BITHE	ON ON ON ON ON ON ON ON ON ON
BULLE STREE	ONU ONU ONU SAN FRANCISCO CA 94107 TEL (415) 512-7566 Subeil@shataraarch.com ONU TEL (415) 512-7566 Subeil@shataraarch.com DRAWINGS AND SPECIFICATIONS, AS INTRRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. ONU THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS
Og TREE	CA 94107 TEL (415) 512-7566 suheil@shataraarch.com DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. THESE DOC IN IP PART, FOR ANY PROJECTS
Og TREE	ON Sub- CN 24"TREE CN CON
	24"TREE 24"TREE Suheil@shataraarch.com DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT.
	OF INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS
	ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS
	IN WHOLE OR IN PART, FOR ANY PROJECTS
	PRIOR SPECIFIC WRITTEN AUTHORIZATION
	OF SHATARA ARCHITECTURE INC
	43'- I' AT SETBACK 20'-0' RESIDENTIAL REMODEL
PROPOSED HORIZONTAL ADDITION	ADDRESS ADDRESS 185 CERVANTES RD.
(P) SKYLIGHT	APN APN REDWOOD CITY, CA
	APN: 051-016-010
+ + + + + + + + + + + + + + + + + + +	
(E) CARPORT	22"TREE
	Note PROJECT DIRECTORY OWNER
	ARCHITECT SHATARA ARCHITECTURE INC.
20' 21'-10 3/4" The second sec	890 7TH STREET SAN FRANCISCO, CA 94107
	TEL: 415-512-7566 CONTACT: SUHEIL SHATARA
U OS O DU O DU O DU O DU O DU O DU O DU O DU	
22"TREE	24"TREE DBI STAMP
DRAWING INDEX SCOPE OF WORK PLANNING	NFORMATION BUILDING INFORMATION
A0.0 COVER SHEET A0.0 LOVER SHEET STORY, SINGLE FAMILY DWELLING, MODIFY (E) A0.0 LOVER SHEET STORY, SINGLE FAMILY DWELLING, MODIFY (E) A0.0 LOVER SHEET STORY, SINGLE FAMILY DWELLING, MODIFY (E)	BUILDING DESCRIPTION: 1 BUILDINGS IN LOT. EXISTING: 1 STORIES TYPE V – B
A0.0COVER SHEETSTORY, SINGLE FAMILY DWELLING MODIFY (E)HEIGHT LIMIT: 28-XA0.0.1BEST MANAGEMENT PRACTICEC1DRAINAGE PLANWALLS. MODIFY ROOF LINE & HEIGHT AT THEHEIGHT LIMIT: 28-XA0.1AREA CALCS.C3EROSION & SEDIMENT PLAN & NOTESREMODELED AREA.EXISTING NUMBER OF U	PROPOSED:
A0.2 SITE PHOTOS L1-L3 LANDSCAPING PLAN	
A1.0.1 PROPOSED SITE PLAN	(E) # OF DWELLING UNITS: 1 - NO CHANGE ISSUED DATE NO.
A1.1 EXISTING/DEMO FLOOR PLANS Lot size (Noclositie). A1.2 EXISTING/DEMO FLOOR PLANS AND SECTIONS Lot size (survey) : A1.7 EXISTING FLOOR PLANS EXISTING FLOOR PLANS	10,935 SQ FT YEAR BUILT: 1949 BUILDING AREA: 2,262 SQ FT
AT.3 EXISTING ELEVATIONS ALLOWED LOT COVERAG	
A3.1 PROPOSED ELEVATIONS – 2019 CALIFORNIA ELECTRIC CODE ALLOWED F.A.R.: 2,880.	REV. 11-26-2019
A3.2 PROPOSED RCP - 2019 CALIFORNIA PLUMBING CODE EXISTING LOT COVERAGE A3.3 PROPOSED RCP - 2019 GREEN BUILDING CODE EXISTING F.A.R.: 1,706.93	: 1,665.03 SQ. FT.
A4.1 LEACH FIELD - 2019 CALIFORNIA FIRE CODE PROPOSED LOT COVERA - 2019 CALIFORNIA ENERGY CODE PROPOSED LOT COVERA PROPOSED LOT COVERA	
– 2019 SAN FRANCISCO BUILDING CODE PROPOSED F.A.R.: 1,990	0.75 SQ. FT. +400 GARAGE ALLOW.
ABBREVIATIONS VICINITY MAP	
& AND DBL. DOUBLE F.O.S. FACE OF STUD N.I.C. NOT IN CONTRACT SPEC. SPECIFICATION	
@ AT DEPT. DEPARTMENT FPRF. FIREPROOF NO./# NUMBER SQ. SQUARE (E) EXISTING DIA. DIAMETER FT. FOOT OR FEET NOM. NOMINAL S.ST. STAINLESS STEEL ADJ. ADJUSTABLE DIM. DIMENSION FTG. FOOTING N.T.S. NOT TO SCALE STL. STEL	
ALUM. ALUMINUM DN. DOWN FURR. FURRING O.C. ON CENTER STOR. STORAGE APPROX. APPROXIMATE DR. DOOR GA. GAUGE OPNG. OPENING STRL. STRUCTURAL	
ARCH. ARCHITECTURAL DS. DOWNSPOUT GALV. GALVANIZED OPP. OPPOSITE SUSP. SUSPENDED ASPH. ASPHALT D.S.P DRY STANDPIPE G.B. GRAB BAR P.L. PROPERTY LINE SYM. SYMMETRICAL	Cervantes Rd Sector Sec
BD. BOARD DWG. DRAWING GYP. GYPSUM PL. PLATE T.C. TOP OF CURB BITUM. BITUMINOUS E. EAST H.B. HOSE BIB PLYWD. PLYWOOD TEL. TELEPHONE BLDG. BUILDING EA. EACH HDWD. HARDWOOD PT. POINT TER. TERRAZZO BLK. BLOCK FL. FLEVATION HORIZ, HORIZONTAL PTD. PAINTED T.&G. TONGUE AND	Cervantes Ra
ALUM.ALUMINUMDN.DOWNFURR.FURRINGO.C.ON CENTERSTOR.STORAGEAPPROX.APPROXIMATEDR.DOORGA.GAUGEOPNG.OPENINGSTRL.STRUCTURALARCH.ARCHITECTURALDS.DOWNSPOUTGALV.GALVANIZEDOPP.OPPOSITESUSP.SUSPENDEDASPH.ASPHALTD.S.PDRY STANDPIPEG.B.GRABP.L.PROPERTY LINESYM.SYMMETRICALBD.BOARDDWG.DRAWINGGYP.GYPSUMPL.PLATET.C.TOP OF CURB	

$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	& AND DBL. DOUBLE F.O.S. FACE OF STUD N.I.C. NOT IN CONTRACT SPEC. SPECIFICATION @ AT DEPT. DEPARTMENT FPRF. FIREPROOF NO./# NUMBER SQ. SQUARE (E) EXISTING DIA. DIAMETER FT. FOOT OR FEET NOM. NOMINAL S.ST. STAINLESS STEEL ADJ. ADJUSTABLE DIM. DIMETER FT. FOOT OR FEET NOM. NOMINAL S.ST. STAINLESS STEEL ALUM. ALUMINUM DN. DOWN FURR. FURRING O.C. ON CENTER STOR. STORAGE APPROX. APPROXIMATE DR. DOOR GA. GAUGE OPNG. OPENING STRL. STRL. STRL STRLOTURAL ARCH. ARCHITECTURAL DS. DOWNSPOUT GALV. GALVANIZED OPP. OPPOSITE SUSP. SUSPENDED ASPH. ASPHALT D.S.P DRY STANDPIPE G.B. GRAB BAR P.L. PROPERTY LINE SYM. SYMMETRICAL BD. <t< th=""><th>Image: State of the s</th></t<>	Image: State of the s
SHEET NUMBER UP LEFT A3 DOWN RIGHT INTERIOR ELEVATION SHEET NUMBER DRAWING NUMBER DRAWING NUMBER DOWN OFFICE ROOM IDENTIFICATION ROOM NAME ROOM NUMBER 1 DOOR NUMBER 1 MATCH LINE SHADED PORTION IS SIDE CONSIDERED DATUM POINT COLUMN GRID TOP OF WALL INTERIOR ELEVATION SHEET NUMBER DATUM POINT COLUMN GRID TOP OF WALL	BM.BEAMELEV.ELEVATORHGT.HEIGHTQ.T.QUARRY TILETHK.THICKBOT.BOTTOMENCL.ENCL.ENCLOSUREINSULATIONR.RISERT.P.TOP OFCAB.CABINETEQ.EQUALINT.INTERIORRAD.RADIUSPAVEMENTC.B.CATCH BASINEQPT.EQUIPMENTJAN.JANITORR.D.ROOF DRAINT.W.TOP OF WALLCEM.CEMENT(E)EXISTINGJ.T.JOINTREF.REFERENCETYP.TYPICALCLG.CELINGEXPO.EXPOSEDLAV.LAVATORYREF.REFIGERATORUNF.UNFINISHEDCLG.CLOSETEXP.EXPANSIONLT.LIGHTRGTR.REGISTERU.O.N.UNFEDCLO.CLOSETEXT.EXTERIORMAX.MAXIMUMREINF.REINFORCEDNOTEDCLR.CLEARF.A.FIRE ALARMMECH.MECHANICALREQ'D.REQUIREDVERT.VESTCONC.CONCRETEFDN.FOUNDATIONMTL.METALR.O.ROUGH OPENINGW.WESTCONSTR.CONSTRUCTIONFLE.FIRE EXTINGUISHERMFR.MANUFACTURERR.W.L.RAIN WATER LEADERW/WITHCONSTR.CONSTRUCTIONFL.FLOORMISC.MISC.MISCLIAREOUSSCHEDULEWODWODCONT.CONTINUOUSFL.FLOORMISC.MISCLIAREOUSSCHEDULEW/WITH <t< th=""><th></th></t<>	





A0.0




SAN MATEO COUNTYWIDE Water Pollution **Prevention Program**

Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project. Please note: the wet season begins on October 1 and continues through April 30.

Clean Water. Healthy Community.

Materials & Waste Management



Non-Hazardous Materials

- Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within $14 \, \mathrm{days}.$
- Use (but don't overuse) reclaimed water for dust control.

Hazardous Materials

- Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- □ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- □ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- □ Arrange for appropriate disposal of all hazardous wastes.

Waste Management

- Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- □ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

Construction Entrances and Perimeter

- □ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

Equipment Management & Spill Control



Maintenance and Parking

- Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- □ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- □ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- □ If vehicle or equipment cleaning must be done onsite. clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, steam cleaning equipment, etc.

Spill Prevention and Control

- □ Keep spill cleanup materials (rags, absorbents, etc.) available at the construction site at all times.
- □ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- Clean up spills or leaks immediately and dispose of cleanup materials properly.
- Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).



Earthwork & Contaminated Soils

Erosion Control

- □ Schedule grading and excavation work for dry weather only.
- □ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- □ Seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.


Sediment Control

- □ Protect storm drain inlets, gutters, ditches, and drainage courses with appropriate BMPs, such as gravel bags, fiber rolls, berms, etc.
- □ Prevent sediment from migrating offsite by installing and maintaining sediment sediment basins.
- □ Keep excavated soil on the site where it will not collect into the street.
- Transfer excavated materials to dump trucks on the site, not in the street.
- □ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.

- Buried barrels, debris, or trash.


Paving/Asphalt Work

Concrete, Grout & Mortar Application




- □ Store concrete, grout and mortar under storm drain.
- □ Wash out concrete equipment/trucks offsite or in a contained area, so there is no discharge into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- □ Collect the wash water from washing for appropriate disposal offsite.

Dewatering



- □ Effectively manage all run-on, all runoff within the site, and all runoff that discharges from the site. Divert run-on areas or otherwise ensure compliance.
- □ When dewatering, notify and obtain approval from the local municipality or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- □ In areas of known contamination, testing is required prior to reuse or discharge of how to interpret results. Contaminated groundwater must be treated or hauled off-site for proper disposal.


Storm drain polluters may be liable for fines of up to \$10,000 per day!



- controls, such as fiber rolls, silt fences, or

- □ Contaminated Soils

- Abandoned underground tanks.
- Abandoned wells



- Avoid paving and seal coating in wet weather, or when rain is forecast before fresh pavement will have time to cure.
- Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- Do not use water to wash down fresh asphalt concrete pavement.

Sawcutting & Asphalt/Concrete Removal

- Completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- □ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- □ If sawcut slurry enters a catch basin, clean it up immediately.

cover, on pallets and away from drainage areas. These materials must never reach a


exposed aggregate concrete and remove it

water from offsite away from all disturbed before discharging water to a street gutter

groundwater. Consult with the Engineer to determine whether testing is required and



Painting & Paint Removal



Painting cleanup

- □ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or surface waters.
- □ For water-based paints, paint out brushes to the extent possible. Rinse to the sanitary sewer once you have gained permission from the local wastewater treatment authority. Never pour paint down a drain.
- □ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of residue and unusable thinner/solvents as hazardous waste.

Paint removal

- Chemical paint stripping residue and chips and dust from marine paints or paints containing lead or tributyltin must be disposed of as hazardous waste.
- □ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.

Landscape Materials



- Contain stockpiled landscaping materials by storing them under tarps when they are not actively being used.
- □ Stack erodible landscape material on pallets. Cover or store these materials when they are not actively being used or applied.
- Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.

SHATARA ARCHITECTURE INC.

> 890 7TH ST. SAN FRANCISCO CA 94107

TEL (415) 512-7566 suheil@shataraarch.com

DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT.

THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS OR PURPOSES WHATSOEVER, WITHOUT THE PRIOR SPECIFIC WRITTEN AUTHORIZATION OF SHATARA ARCHITECTURE INC

RESIDENTIAL REMODEL

185 CERVANTES RD. REDWOOD CITY, CA

APN: 051-016-010

PROJECT DIRECTORY OWNER


ARCHITECT

SHATARA ARCHITECTURE INC. 890 7TH STREET

SAN FRANCISCO, CA 94107 TEL: 415-512-7566 CONTACT: SUHEIL SHATARA


DBI STAMP

ISSUED	DATE	NO.
BUILDING	07-17-2	019
BUILDING	07-31-2	019
BUILDING	10-01-2	019
REV.	11-26-2	019
BUILDING	01-13-2	020
REV.	01-27-20)20
PLANNING	04-15-2	.020



SHEET DESCRIPTION BEST MANAGEMENT PRACTICE

A0.0.1



(5) AREA CALCS.

PROPOSED ADDITION : 634.60 SQ. FT. X \$ 300 = \$190,380

ALLOWED ADDITION : 50% OF EXISTING BUILDING COST 1,358.94 SQ. FT. X \$ 300 = \$407,682 X50% = \$ 210,801 + 348 SQ. FT X \$40 = \$13,920

+ \$20,000 RENOVATING EXISTING AREA = \$210,380 LESS THAN 50%

LOT SIZE: 10,935 SQ. FT.



ALLOWED FAR : 0.30 (10,935- 10,000) + 2,600 SQ. FT. = 2,880.50 SQ. FT. EXISTING FAR : BUILDING AREA+CARPORT = 1,706.93 SQ. FT. PROPOSED FAR : 1,993.75 SQ. FT. + 400 SQ. FT. GARAGE ALLOWANCE

ALLOWED LOT COVERAGE : 25% (0.25 X 10,935 SQ. FT.) = 2,733.75 SQ. FT. EXISTING LOT COVERAGE : BUILDING + DECK = 1,665.03 SQ. FT. PROPOSED LOT : 2,163.25 SQ. FT. < (25% OF LOT AREA)

LOT SIZE: 10,935 SQ. FT.

SHATARA ARCHITECTURE

890 7TH ST. SAN FRANCISCO CA 94107

INC.

TEL (415) 512-7566 suheil@shataraarch.com

DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF

THE ARCHITECT. THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS OR PURPOSES WHATSOEVER, WITHOUT THE PRIOR SPECIFIC WRITTEN AUTHORIZATION OF SHATARA ARCHITECTURE INC

PROJECT **RESIDENTIAL REMODEL**

ADDRESS **185 CERVANTES RD.** REDWOOD CITY, CA

APN: 051-016-010


PROJECT DIRECTORY OWNER

ARCHITECT SHATARA ARCHITECTURE INC.

890 7TH STREET SAN FRANCISCO, CA 94107 TEL: 415-512-7566 CONTACT: SUHEIL SHATARA

DBI STAMP

ISSUED	DATE	NO.
BUILDING	07-17-2	019
BUILDING	07-31-2	019
BUILDING	10-01-2	019
REV.	11-26-2	019
BUILDING	01-13-2	020
REV.	01-27-20)20
PLANNING	04-15-2	020



SQUARE FOOTAGES -**AREA CALCS.**

A0.2


SHEET DESCRIPTION































SHATARA ARCHITECTURE INC.

> 890 7TH ST. SAN FRANCISCO CA 94107

TEL (415) 512-7566 suheil@shataraarch.com

DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT.

THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS OR PURPOSES WHATSOEVER, WITHOUT THE PRIOR SPECIFIC WRITTEN AUTHORIZATION OF SHATARA ARCHITECTURE INC

PROJECT **RESIDENTIAL REMODEL**

ADDRESS 185 CERVANTES RD. REDWOOD CITY, CA

APN: 051-016-010


PROJECT DIRECTORY OWNER

ARCHITECT SHATARA ARCHITECTURE INC.


890 7TH STREET SAN FRANCISCO, CA 94107 TEL: 415-512-7566 CONTACT: SUHEIL SHATARA


DBI STAMP


ISSUED	DATE	NO.
BUILDING	07-17-2	019
BUILDING	07-31-2	019
BUILDING	10-01-2	019
REV.	11-26-2	019
BUILDING	01-13-2	020
REV.	01-27-20	020
PLANNING	04-15-2	2020




A0.3

















1 EXISTING SECTION SCALE : 1/4"=1'-0"








11-26-2019


REV.

















(N) ALUMINUM


TYP.

FRAMED WINDOWS

(N) SLIDING DOOR —


(N) WOOD SIDING ┌───TYP.


3 PROPOSED WEST ELEVATION SCALE : 1/4"=1'-0"




SHATARA

ARCHITECTURE








ELECTRICAL & MECHANICAL SYMBOLS & NOTES

ELECTRICAL & MECHANICAL	🔿 LIGHT FIXTURE – PENDANT
LEGEND	- LIGHT FIXTURE – CEILING MOUNTED
↔ A HEATING DUCT REGISTER, FLOOR OR WALL MOUNTED	LIGHT FIXTURE – FL OR LED STRIP LIGHTING
- DOWNLIGHT FIXTURE - RECESSED	\$ SWITCH, 48" A.F.F. # = 3 OR 4 WAY D = DIMMER
FIXTURE - F = FLUORESCENT LED = LED LIGHT	OCC = OCCUPANCY SENSOR Y DATA PORT - COAXIAL CAT-6 DOUBLE WIRED
LIGHT FIXTURE – WALL MOUNTED PC PHOTO-CELLS MS MOTION SENSOR 4' FLUORESCENT KITCHEN: 50% HIGH EFFICACY	GFI ↔ DUPLEX ELECT. OUTLET @ # v # v # MP # AMP W.P.: WATER PROTECTED AMP: AMPERE V : VOLTAGE
3' T5 FLUORECESNT SIDE-MOUNTED TO SOFFIT BATH/ TOILET: 100% HIGH EFFICACY	⊙ _{SCD} SMOKE/CARBON MONOXIDE ALARM DETECTOR
S EXHAUST FAN	⊙ _{sd} smoke alarm detector
EXHAUST FAN / FLUOR. LIGHT FIXTURE COMBO	 ← ─ ─ ─ EXHAUST DUCT (TOILET FAN/ FURNACE, WATER HEATER
G GAS SUPPLY (IN ADDITION TO GAS APPLIACES NOTED	<∱ HOT AIR SUPPLY
ON PLANS) LIGHT FIXTURE – PENDANT	— — — ⇐ INTERNAL AIR EXTRACTION





SHATARA ARCHITECTURE INC.

890 7TH ST. SAN FRANCISCO CA 94107

TEL (415) 512-7566 suheil@shataraarch.com

DRAWINGS AND SPECIFICATIONS, AS INSTRUMENTS OF PROFESSIONAL SERVICE, ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT.

THESE DOCUMENTS ARE NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY PROJECTS OR PURPOSES WHATSOEVER, WITHOUT THE PRIOR SPECIFIC WRITTEN AUTHORIZATION OF SHATARA ARCHITECTURE INC

PROJECT **RESIDENTIAL REMODEL**

ADDRESS 185 CERVANTES RD. REDWOOD CITY, CA

APN: 051-016-010

PROJECT DIRECTORY OWNER


ARCHITECT


SHATARA ARCHITECTURE INC. 890 7TH STREET


SAN FRANCISCO, CA 94107 TEL: 415-512-7566 CONTACT: SUHEIL SHATARA


DBI STAMP

ISSUED	DATE	NO.
BUILDING	07-17-2	019
BUILDING	07-31-2	019
BUILDING	10-01-2	019
REV.	11-26-2	019
BUILDING	01-13-2	020
REV.	01-27-20)20
PLANNING	04-15-2	020









1. TREE PROTECTION FENCING SHALL BE INSTALLED PRIOR TO ANY GRADING AND REMAIN ON-SITE THROUGHOUT CONSRUCTION PROCESS.


2. TREE PROTECTION FENCES SHALL BE INSTALLED AS CLOSE TO DRIP LINES AS POSSIBLE.

3. OWNER/BUILDER SHALL MAINTAIN TREE PROTECTION ZONES FREE OF EQUIPMENT AND MATERIALS STORAGE AND SHALL NOT CLEAN ANY EQUIPMENT WITHIN THESE AREAS.

4. ANY LARGE ROOTS THAT NEED TO BE CUT SHALL BE INSPECTED BY A CERTIFIED ARBORIST OR REGISTERED FORESTER PRIOR TO CUTTING, AND MONITORED AND DOCUMENTED.

5. ROOTS TO BE CUT SHALL BE SEVERED WITH A SAW OR TOPPER.

6. PRE-CONSTRUCTION SITE INSPECTION WILL BE REQUIRED PRIOR TO ISSUANCE OF BUILDING PERMIT.




GENERAL EROSION AND SEDIMENT CONTROL NOTES


.FIBER ROLE INSTALL AT LOCATIONS SHOWN, AFIX AS SHOWN IN DETAIL SE-5

- There will be no stockpiling of soil. All excavated soil will be hauled off-site as it is excavated.
- · Perform clearing and earth-moving activities only during dry weather. Measures to ensure adequate erosion and sediment control shall be installed prior to earth-moving activities and construction.
- Erosion control materials to be on-site during off-season.
- Measures to ensure adequate erosion and sediment control are required year-round. Stabilize all denuded areas and maintain erosion control measures continuously between October 1 and April 30.
- Store, handle, and dispose of construction materials and wastes properly, so as to prevent their contact with stormwater.
- · Control and prevent the discharge of all potential pollutants, including pavement cutting wastes, paints, concrete, petroleum products, chemicals, wash water or sediments, and non-stormwater discharges to storm drains and watercourses.
- · Avoid cleaning, fueling, or maintaining vehicles on-site, except in a designated area where wash water is contained and treated.
- · Limit and time applications of pesticides and fertilizers to prevent polluted runoff.
- Limit construction access routes to stabilized, designated access points
- · Avoid tracking dirt or other materials off-site; clean off-site paved areas and sidewalks using dry sweeping methods.
- Train and provide instruction to all employees and subcontractors regarding the Watershed Protection Maintenance Standards and construction Best Management Practices.
- Placement of erosion materials is required on weekends and during rain events.
- The areas delineated on the plans for parking, grubbing, storage etc., shall not be enlarged or "run over."
- Dust control is required year-round.

Turn the ends of the fiber roll up-slope to prevent runoff from going around the roll.


· Erosion control materials shall be stored on-site






I HAVE COMPLIED WITH THE CRITERIA OF THE ORDINANCE AND APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE

	Botanical	Common	Size	Qty	Water Use	Facto
		Trees				
	Citrus limon Var.	Lemon	15	1	М	.46
	Citrus reticulata 'Clemetine'	Mandarin Orange	15	1	М	.46
	Malus domestica Var.	Apple	15	1	М	.46
		Shrubs				
	Echium candicans	Pride of Madeira	5	7	L	.13
	Rhaphiolepis indica	Indian Hawthorn	5	4	L	.13
	Lavandula stoeches	Spanish Lavender	5	6	L	.13
	Carpentaria californica	Bush Anemone	5	1	L	.13
_		1				
		Perrenials				
	Agastache cana 'Sinning'	Sonoran Sunset	5	17	L	.13
	Erigeron karvinskianus	Mexican Daisy	1	20	L	.13
	Phormium tenax 'Atropurpureum'	Bronze New Zealand Flax	5	1	L	.13
	Phormium 'Maori Queen'	Maori Queen New Zealand Flax	5	4	L	.13
	Phormium tenax	New Zealand Flax	5	1	L	.13
	Heuchera (Variety)	Coral Bells (Variety)	1	5	M	.46
		Grasses				
	Bouteloua gracilis	BIUe Gama	5	11	L	.13
	Carex elata 'Bowles Golden'	Bowles golden Sedge	1	10	M	.46
-	Hakonechloa macra Variegata	Varigated Japanese Forest Grass	1	10	M	.46
	0					8.1. J 197
		GROUNDCOVERS				
	Drosanthemun floribundum	Rosea Ice Plant	4"	30	L	.13
_			-	50		1 - 13
	-					





Climate Redwood City -	Californi	а				°C °F
	Jan	Feb	Mar	Apr	May	Jun
Average high in °F:	58	62	65	69	74	79
Average low in °F:	40	43	45	46	50	53
Av. precipitation in inch:	4.02	3.98	3.15	1.14	0.47	0.12
Days with precipitation:		7		-		1
Hours of sunshine:	-	-	-	-	-	97
	Jul	Aug	Sep	Oct	Nov	Dec
Average high in °F:	81	81	80	74	65	58
Average low in °F:	55	56	54	50	44	40
Av. precipitation in inch:	0.04	0.04	0.16	1.06	2.36	3.86
Days with precipitation:	1.50	-	-	-	-	



-

-




NOTE:

Hours of sunshine:

This plan is diagrammatic in nature and is meant as a general guide only. It is not fully detailed and exhaustively specified. It is the responsibility of the installer to become familiar with all site conditions and these drawing and to notify the designer of any discrepancies. The installer and owner have sole responsibility for quality control, construction standards and compliance to all building codes. This plan is part of a set of documents and is meant to be used together as a whole.

.



I HAVE COMPLIED WITH THE CRITERIA OF THE ORDINANCE AND APPLIED THEM FOR THE EFFICIENT USE OF WATER IN THE LANDSCAPE DESIGN PLANS.

IRRIGATION_SCHEDULE

	MANUFACTURER/MODEL	-			QTY	<u>ARC</u>
<u>A-</u>	Hunter MP1000-90				9	ADJ
	MANUFACTURER/MODEL/	DESCRIPTION			QTY	
	Rain Bird XCZ-100-PRF-B Drip Control Kit, 1" Low f filter and 30psi pressure	=low valve, I" p	ressure regulati I" as needed.	ing back flush	3	
Ø	Pipe Transition Point Pipe transition point from	PVC lateral to	drip tubing with	ı rıser ın drıp box.	5	
	Area to Receive Poly Dri Install min (2) drip lini plantemmiter size t Use larger emmiters smaller G.P.M. emmit areas.	es to each to be determ in sun area ar	nd			
	Soaker Tubing Around Tre Encircle all trees w/ 2 @ 24" from center of center of tree	loops of laze	er drip tubing	, 1st loop	3	
	MANUFACTURER/MODEL	/DESCRIPTION			<u>QTY</u>	
SC	Hunter PRO-C-12 Station	1 Controller			I	
WS	WEATHER SENSOR Hun	iter ET System			I	
•	Rain Bird PGA 1" Electric Remote Control V	Valve			I	
BF	Febco 825Y " Reduced Pressure Backfl	ow Preventer, e	existing		I	
ICI	Flow Meter DLJ Multi-Jet Water Mete	er, #DLJ100, 1	11		I	
 F	Existing POC				2	
НВ	Нозе Віб					
	Irrigation Lateral Line: PV	C Class 200 S	DR 21			
	Irrigation Mainline: PVC 5	ochedule 40				
<i>#•#•</i>	Valve Callout ——— Valve Number ——— Valve GPM					
\	Valve Size			<i>.</i>		
	VALVE S	CHEDL	ILE			
NUMBER	MODEL	SIZE	TYPE	Location		
	Rain Bird DVF-075	3/4"	Drip	SW Shrubs	5	
2 3	Raın Bırd DVF-075 Raın Bırd DVF-075	3/4" 3/4"	Drip Drip	Trees SE Shrubs	÷	
4	Rain Bird 100-PRF	, 	Lawn	Lawn		

PRESSURE REGULATING DEVICES ARE REQUIRED IF WATER PRESSURE IS BELOW OR EXCEEDS THE RECOMMENDED PRESSURE OF THE SPECIFIED IRRIGATION DEVICES.

CHECKVALVES OR ANTI-DRAIN VALEVES ARE REQUIRD ON ALL SPRINKLER HEADS WHERE LOW POINT DRAINAGE COULD OCCUR.

A DIAGRAM OF THE IRRIGATION PLAN SHOWING HYDROZONES SHALL BE KEPT WITH THE IRRIGATION CONTROLLER FO SUBSEQUENT MANAGEMENT PURPOSES.

A CERTIFICATE OF COMPLETION SHALL BE FILLED OUT AND CERTIFIED BY EITHER THE DESIGNER OF THE LANDSCAPE PLANS, IRRIGATION PLANS, OR THE LICENSED CONTRACTOR FOR THE PROJECT.

AN IRRIGATION AUDIT REPORT SHALL BE COMPLETED AT THE TIME OF FINAL INSPECTION.

Irrigation

NOTE:

This plan is diagrammatic in nature and is meant as a general guide only. It is not fully detailed and exhaustively specified. It is the responsibility of the installer to become familiar with all site conditions and these drawing and to notify the designer of any discrepancies. The installer and owner have sole responsibility for quality control, construction standards and compliance to all building codes. This plan is part of a set of documents and is meant to be used together as a whole.

DreamScapes		Phone: 925.332-5092 Cell: 925.202.1260 email: jcastro@dreamscapesbydesign.org
Planting Plan For	185 Cervantes Rd.	185 Cervantes Rd. redwood City, CA
	TITLE : gation	
REVIS		
- 7-20		
DRAWN BY:	PAGE	
J. CASTR		
II-2I-I scale: As Shown		iree

