# SONG RESIDENCE ADDITION

# 140 WINDING WAY SAN CARLOS CA 94070

ADDRESS	140 WINDIING WAY SAN CARLOS CA 9
APN	049-14-1420
TYPE OF CONSTRUCTION	V-B
OCCUPANCY	R-3
ZONING	R1/S71/DR
LOT SIZE	4,590
LOT ARVERAGE SLOPE	15%
FIRE SPRINKLER SYSTEM	NO
FLOOD ZONE:	NO
EASEMENT	YES, REAR AND WEST
MAX. ALLOWED FLOOR AREA	2,000 SF
PROPOSED FLOOR AREA	1,989.9 SF
MAX. ALLOWED COVERAGE RATIO	43.51%
PROPOSED FLOOR AREA	
MAX. ALLOWED BUILDING HEIGHT	30'
MAX. ALLOWED BUILDING HEIGHT	28' 5 1/2"
SETBACK	
FRONT	20 FT
REAR	15 FT
WEST	5 FT
EAST	5 FT

# PROJECT SUMMARY

TOTAL FLOOR AREA
LEVEL 1
LEVEL 2
FAR
LOT COVERAGE
LOT COVERAGE %
BUILDING HEIGHT
STORIES
PARKING SPACE
GARAGE SIZE
PORCH SIZE
NUMBER OF BEDROOMS
NUMBER OF BATHROOMS

# EXISTING PROPOSED 880 1,990 0 553 SF 880 1437 SF 19.2% 43.4% 1,890 1,997 41.2% 43.5% 14'10 7/8" 28' 5 1/2" 1 2 1 1 230 230 0 0 2 5

#### DRAWING INDEX

# A0.1 COVER SHEET

**ARCHITECTURAL** 

A1.1 SURVEY PLAN A1.2 SITE PLAN (1/8"= 1')


A1.3 DRAINAGE CACULATION (1/8"= 1')

A2.1 PLAN - EXISTING (1/4"= 1")
A2.2 PLAN L1- PROPOSED (1/4"= 1")
A2.3 PLAN L2- PROPOSED (1/4"= 1")
A2.4 ROOF PLAN - PROPOSED (1/4"= 1")

A4.1 ELEVATIONS - EXISTING (1/4"= 1')
A4.2 ELEVATIONS - PROPOSED (1/4"= 1')
A4.3 ELEVATIONS - PROPOSED (1/4"= 1')

#### VICINITY MAP

SUBJECT PROJECT



aing 4

el. 650.797.3999

quinn.ye.sf @ gmail.com

#### PROJECT SCOPE

THIS PROJECT IS TO:

ADD (N) LIVING SPACE OF 1,110 SF
 ALTERNATE PARTIAL OF A (E) SINGLE FAMILY HOUSE

#### APPLICABLE CODES

2019 CRC, CEBC, CES, CPC, CMC, CFC, CALGREEN, CALIFORNIA ENERGY EFFICIENCY STANDARDS SAN MATEO COUNTY 2020 ZONING REGULATIONS

# **ABBREVIATIONS**

, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	(21) (110110				
A/C	AIR CONDITIONING	FIN	FINISH	PERP	PERPENDICULAR
ADJ	ADJACENT	FLR	FLOOR(ING)	PL	PROPERTY LINE OR PLATE
AFF	ABOVE FINISHED FLOOR	FOF	FACE OF FINISH	PLYWD	PLYWOOD
AL	ALUMINUM	FOS	FACE OF STUDS	ILIVUD	TETWOOD
ANOD	ANODIZED	FR	FIRE RATED	RRC	REINFORCED CONCRETE
APPROX	APPROXIMATE(LY)	FT	FOOT / FEET	RD	ROOF DRAIN
	, ,	FTG	FOOTING	REF	REFERENCE
ARCH	ARCHITECT(URAL)	FIG	FOOTING	RM	ROOM
BD	BOARD	GA	GAUGE	RO	ROUGH OPENING
		GALV	GALVANIZED	NO	NOOGH OF ENING
BLDG	BUILDING	GALV	GLASS	S	SOUTH
BLK	BLOCK	GR GR	GRADE	SD	STORM DRAIN
BOT	BOTTOM	GYP	GYPSUM	SF	SQUARE FOOT
BTU	BRITISH THERMAL UNIT	GYP	GYPSUM	SHT	SHEET (ING)
CEN 4	CENTENIT	НВ	LIOSE DID	SHTHG	SHEATHING
CEM	CEMENT	нв HDWR	HOSE BIB	SIM	SIMILAR
CER	CERAMIC		HARDWARE		
CJ	CONTROL JOINT	HORIZ	HORIZONTAL	SPEC(S)	SPECIFICATION(S)
CLG	CEILING	HW	HOT WATER	SSL	STANDARD
CLR	CLEAR	HT	HEIGHT	STD	STANDARD
CONC	CONCRETE	HP	HORSEPOWER	STL	STEEL
CONT	CONTINUOUS	INICIII	INICHIATION	<del>-</del>	TUEDAAGETAT
CTR	CENTER	INSUL	INSULATION	T	THERMOSTAT
551	5011515	INT	INTERIOR	TEMP TEN	
DBL	DOUBLE	8.4.8.7	5 4 5 X 15 4 1 15 4	TOS TOP (	
DEMO	DEMOLITION	MAX	MAXIMUM	TYP	TYPICAL
DIA	DIAMETER	MECH	MECHANICAL		LINUEGO OTHERWISE NOTER
DIM	DIMENSION	MFR	MANUFACTURER	UON	UNLESS OTHERWISE NOTED
DN	DOWN	MIN	MINIMUM		
DR	DOOR	MISC	MISCELLANEOUS	VERT	VERTICAL
DWG	DRAWING	MTD	MOUNTED	VIF	VERIFY IN FIELD
DS	DOWN SPOUT				
E	EAST	N	NORTH	W/	WITH
(E)	EXISTING	(N)	NEW	W/O	WITHOUT
ELEC	ELECTRICAL	N/A	NOT APPLICABLE	WC	WATER CLOSET
EQ	EQUAL	NTS	NOT TO SCALE	WD	WOOD
EXT	EXTERIOR			WH	WATER HEATER
		OC	ON CENTER	W.O.	WHERE OCCURS
FD	FLOOR DRAIN	OPP OPF	POSITE	WR	WATER RESISTANT
EDM	FOLINDATION			\ A /T	WEIGHT

#### SONG RESIDENCE

Project No:

Date: Scale:

WEIGHT

140 WINDING WAY SAN CARLOS, CA 94070

PLANNNING SUBMITTAL 03-10-2021

# GENERAL NOTES

FOUNDATION

- 1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND SUBCONTRACTORS TO CHECK AND VERIFY ALL DIMENSIONS AND CONDITIONS INDICATED ON THESE DRAWINGS AND MAKE KNOWN ANY DISCREPANCIES PRIOR TO COMMENCING THEIR WORK.
- 2. THESE DRAWINGS AREA INTENDED FOR USE IN A NEGOTIATED CONSTRUCTION CONTRACT AND, THEREFORE, MAY NOT SPECIFICALLY DETAIL OR SPECIFY MATERIAL AND / OR MANUFACTURERS. THE CONTRACTOR SHALL PROVIDE ALL SAMPLES AND OR CUTS AS REQUIRED TO ASSIST OWNER OR HIS AGENT IN MAKING MATERIAL SELECTIONS. FOR THE PURPOSE OF ESTIMATING, THE CONTRACTORS SHALL USE THE MATERIALS SELECTED BY THE OWNER, OR IN ABSENCE OF SAME, HE SHALL PROVIDE AN ALLOWANCE AMOUNT AND SO CONDITION ANY COST ESTIMATE..
- 3. NO GUARANTEE OF QUALITY OF CONSTRUCTION IS IMPLIED OR INTENDED BY THE ARCHITECTURAL DOCUMENTS, AND THE CONTRACTOR
- 4. THE GENERAL CONTRACTOR SHALL HOLD HARMLESS, INDEMNIFY AND DEFEND THE DESIGNER FROM ANY ACTION INITIATED BY THE INITIAL OWNER OR ANY SUBSEQUENT OWNERS FOR CONSTRUCTION DEFICIENCIES, MODIFICATIONS OR SUCH CONDITIONS WHICH MAY BE BEYOND THE CONTROL OF THE DESIGNER.
- 5. ALL WORK SHALL COMPLY WITH APPLICABLE CODES AND TRADE STANDARDS WHICH GOVERN EACH PHASE OF WORK, INCLUDING BUT NOT LIMITED TO: UNIFORM BUILDING CODE (UBC), UNIFORM MECHANICAL CODE (UMC), NATIONAL ELECTRICAL CODE (NEC), NATIONAL PLUMBING CODE (NPC), AND ALL APPLICABLE LOCAL CODES AND LEGISLATION.
- 6. THE CONTRACTOR SHALL REVIEW AND RECORD THE CONDITIONS OF ALL EXISTING SITE IMPROVEMENTS INCLUDING PAVED AREAS. HE SHALL MAKE KNOWN ALL EXISTING DAMAGED OR DISREPAIRED ITEMS AND CONDITIONS THAT MAY WORSEN DUE TO THE CONSTRUCTION. ALL ITEMS IN GOOD CONDITION SHALL BE MAINTAIN IN THEIR PRESENT CONDITION AND ANY REPAIR OR DAMAGE WHICH OCCURS DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 7. CONTRACTOR SHALL THOROUGHLY EXAMINE THE SITE AND SATISFY HIMSELF AS OF THE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED. THE CONTRACTOR SHALL VERIFY AT THE SITE ALL MEASUREMENTS AFFECTING HIS WORK AND SHALL BE RESPONSIBLE FOR THE CORRECTNESS OF SAME. NO EXTRA COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR THE EXPENSES DUE TO HIS NEGLECT TO EXAMINE OR FAILURE TO DISCOVER CONDITIONS WHICH MAY AFFECT HIS WORK.
- 8. ALL NEW INTERIOR PAINT COLOR, FLOOR, WALLS AND CEILING FINISHES SHALL BE SELECTED BY OWNER AT THE TIME WHEN IT IS NECESSARY FOR THE COMPLETION OF THE PROJECT.
- 9. ALL PUBLIC IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE LATEST ADOPTED CITY STANDARDS. THE STORING OF GOODS AND MATERIALS ON SIDEWALK AND/OR STREET WALL NOT BE ALLOWED UNLESS THE CONTRACTOR HAS APPLIED AND SECURED A SPECIAL PERMIT WHICH ALLOW SUCH STORAGE TO BE PLACED.





(E) BACK VIEW


(E) FRONT VIEW

A0.

2021-02


03-10-2020

**COVER PAGE** 




# FLOOR AREA CALCULATION

LADEL	DIM	ENG		ıc		ADEA
LABEL	DIM	ENS	OIOI	<b>N</b> 5		AREA
LEVEL 1:			.,			
Α	10'			16'		174.7 SF
В	5'	6"	X	12'	9"	70.1 SF
С	5'	6"	X	3'	6"	19.3 SF
D	11'	0"	Χ	13'	9"	151.3 SF
Е	10'	0"	Χ	13'	9"	137.5 SF
						552.8 SF
LEVEL 2:						
F	9'	5"	Χ	3'	2"	29.8 SF
G	17'	6"	Χ	9'	2"	160.4 SF
Н	2'	6"	Χ	6'	5"	16.0 SF
1	20'	0"	Χ	11'	8"	233.3 SF
J	15'	9"	Χ	16'	3"	255.9 SF
K	9'	0"	Χ	12'	9"	114.8 SF
L	9'		Χ	3'	0"	27.0 SF
М	12'		Χ	13'	3"	159.0 SF
N	17'	9"	Χ	13'	6"	239.6 SF
0	6'	5"	Χ	4'	7"	29.4 SF
Р	8'	11"	Χ	5'	11"	52.8 SF
Q	11'	4"	Χ	10'	6"	119.0 SF
						1,437.1 SF
TOTAL CON	NDITIO	NEI	) AI	REA		1,989.9 SF
MAX. ALLO						2,000.0 SF
LOT SIZE						4,590.0 SF
F. A. R.						43.4%



AREA PLAN 03



# COVERAGE RATIO CALCULATION

	PROPOSED		EXISTING
MAIN RESIDENCE	1,437	SF	880
GARAGE	230	SF	230
DECK	330	SF	500
SUNROOM	0	SF	160
SHED	0	SF	120
TOTAL	1,997	SF	1,890
LOT SIZE	4,590	SF	4590
COVERAGE RATIO	43.51%		41.18%


# **KEYNOTES**

- 1 (E) CONC. STEPS
- (E) CONC. ROCK RET. WALL
- (E) TEMP. GAZEBO TO REMOVE
- (E) WOOD STAIRS TO REMOVE
- (E) CONC. STEPS
- (E) TREE REMOVED BY PREVIOUS OWNER
- (E) SEWER CLEANOUT
- 40 GALLON DRY WELL, CONTRACTOR TO VERIFY INSTALLATION DETAILS
- 9 Ø4" ABS DRY WELL INLET PIPE


# SITEWORK NOTES

- 1. DISTURBED SURFACE NOT INVOLVED IN THE IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND/OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION;
- 2. ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION
- ON OR ADJACENT TO THE ROADWAY OR ON THE ADJACENT PROPERTIES; 3. RUNOFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS,
- FIBER ROLLS, AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE; 4. DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY
- AND CONTINUOUSLY THROUGHOUT THE LIFE OF THE PROJECT DURING WINTER OPERATIONS. 5. ALL TEMPORARY STOCKPILES SHALL BE COVERED WITH 6MIL PLASTIC SHEETS, SUITABLY
- 6. THE SITE SHALL BE MONITORED BY THE CONTRACTOR/OWNER AFTER RAIN EVENT TO VERIFY EROSION CONTROL MEASURES ARE FUNCTIONING.
- 7. PROTECT (E) CATCH BASIN WITH GRAVEL BAGS
- 8. SURFACE DRAINAGE SHALL BE DIVERTED TO A STORM SEWER CONVEYANCE OR OTHER APPROVED POINT OF COLLECTION THAT DOES NOT CREATE HAZARD. LOTS SHALL BE GRADED TO DRAIN SURFACE WATER AWAY FROM FOUNDATION WALLS. THE GRADE SHALL FALL NOT FEWER THAN 6" WIHTIN THE FIRST 10'. WHERE LOT LINES, WALLS, SLOPES OR OTHER PHYSICAL BARRIERS PROHIBIT 6" OF FALL WITHIN 10', DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM THE STRUCTURE. IMPERVIOUS SURFACE WITHIN 10' OF THE BUILDING FOUNDATION SHALL BE SLOPED NOT LESS THAN 2 PERCENT AWAY FROM THE BUILDING.

cel. 650.797.3999



SITE PLAN & AREA PLAN



# (E)DRAINAGE CACULATION O 1

# **IMPREVIOUS AREA SUMMARY**

#### **EXISTING CONDITION (PRE-PROJECT)**

A TOTAL AREA OF PARCEL

- B EXISTING PREVIOUS AREA
- C EXISTING INPREVIOUS AREA
- D EXISTING % INPREVIOUS

#### PROPOSED CHANGES

- E EXISTING IMPREVIOUS AREA TO BE RETAINED
- F EXISTING IMPREVIOUS AREA TO BE REPLCAED W/ NEW IMPREVIOUS AREA
- G EXISTING PREVIOUS AREA TO BE REPLCAED W/ NEW IMPREVIOUS AREA
- H NEW IMPREVIOUS AREA (CREATED AND/OR REPLACED)
- I EXISTING IMPREVIOUS AREA TO BE REPLACED W/ NEW PREVIOUS AREA
- J NET CHANGE IN IMPREVIOUS AREA

#### PROPOSED CONDITIONS (POST-PROJECT)

- K PROPOSED PREVIOUS AREAL PROPOSED IMPREVIOUS AREA
- M PROPOSED % IMPREVIOUS AREA

A 4,590


B 1,972

C 2,618

C / A X 100 D 57.04%

	Е	2,494	
	F	413	
	G	361	
= F + G	Н	774	
	l	124	
= G - I	J	237	

= B - J	K	1,735
= C + J	L	2,855
= L / A X 100	М	62.20%



#### aine 4

cel. 650.797.3999

quinn.ye.sf @ gmail.com

# (N)DRAINAGE CACULATION Scale: 1/8" = 1'

_	
1	1,972 SQFT (E) PREVIOUS AREA (E.G. LANDSCAPING, PREVIOUS PAVERS, GREEN ROOFS)
2	2,618 SQFT (E) IMPREVIOUS AREA (E.G. ROOFS, SIDEWALKS, PATIOS, PATHS, DRIVEWAYS, DECKS)
3	413 SQFT (E) IMPREVIOUS REPLACED BY (N) IMPREVIOUS
4	361 SQFT (E) PREVIOUS REPLACED BY (N) IMPREVIOUS
5	124 SQFT (E) IMPREVIOUS REPLACED BY (N) PREVIOUS

SONG RESIDENCE

140 WINDING WAY SAN CARLOS, CA 94070


DR SUBMITTAL 03-10-2021


ev. Date Issue

Project No: 2021-02
Date: 03-10-2020
Scale: 1/8"=1'0"
DRAINAGE CACULATION

**11** 

# **GRAPHIC LEGEND**







Aing Ye

cel. 650.797.3999

quinn.ye.sf @ gmail.com

SONG RESIDENCE

140 WINDING WAY SAN CARLOS, CA 94070

PLANNNING SUBMITTAL 03-10-2021

ev. Date Is:

Project No: Date: Scale: 2021-02 03-10-2020 1/4"=1'0"


DEMOLITION PLAN


A2.1

1 WET BAR

\_\_\_\_\_ (E) WALL

(N) WALL PER GENERAL NOTES (N) WINDOW PER GENERAL NOTES





Aing Ye

cel. 650.797.3999

quinn.ye.sf @ gmail.com

SONG RESIDENCE

140 WINDING WAY SAN CARLOS, CA 94070

PLANNNING SUBMITTAL 03-10-2021

Project No: 2021-02 Date: 03-10-2020 Scale: 1/4"=1'0" PROPOSED PLAN

# **GRAPHIC LEGEND**


\_\_\_\_\_ (E) WALL (N) WALL PER GENERAL NOTES

(N) WINDOW PER GENERAL NOTES

# KEYNOTES

1 2'x4' SKYLIGHT, VELUX FIXED SKYLIGHT OR EQUAL

2 AWNING



cel. 650.797.3999

quinn.ye.sf @ gmail.com

SONG RESIDENCE


140 WINDING WAY SAN CARLOS, CA 94070

PLANNNING SUBMITTAL 03-10-2021

Project No: 2021-02 Date: 03-10-2020 Scale: 1/4"=1'0" PROPOSED PLAN

# KEYNOTES

- (E) ROOF TO REMAIN
- (N) ROOF TO MATCH EXISTING
- 3 (N) SKYLIGHT





Aing Ye

cel. 650.797.3999

quinn.ye.sf @ gmail.com

SONG RESIDENCE

140 WINDING WAY SAN CARLOS, CA 94070

PLANNNING SUBMITTAL 03-10-2021

Rev. Date I


Project No: 2021-02

Date: 03-10-2020

Scale: 1/4"=1'0"

PROPOSED ROOF PLAN

FROFOSED ROOF FI





quinn.ye.sf @ gmail.com

EXISITNG ELEVATION - SOUTH 04

14'7"(454.31) (E)ROOF RIDGE


(E) TOP PLATE

(E) TOP PLATE cel. 650.797.3999 LEVEL 2


— (E) SUNROOM TO REMOVE

— (E) SUNROOM TO REMOVE


(E) WOOD STAIRS TO REMOVE——



# PROPOSED SECTION 1 03 Scale: 1/4"=1'-0"



PROPOSED ELEVATION - NORTH 02



— (E) WOOD SIDING TO REMAIN

DINING

— (N) STUCCO TYP.

0'0"(439.63) (E) F.F. LEVEL 2

-10'0"(429.63) (N)F.F. LEVEL 1

(N) ROOF ASPHALT SHINGLE TO MATCH (E)

— (N) STUCCO TYP.

5:12

(E) WOOD SIDING TYP.—

-10'0"(429.63) (N)F.F. LEVEL 1 -12'9"(427.84)

0'0"(439.63) (E) F.F. LEVEL 2

1/4"=1'0" PROPOSED ELEVATION AND SECTION

2021-02

03-10-2020

PLANNNING SUBMITTAL 03-10-2021

Project No:

Date:

Scale:

Aing Ye

cel. 650.797.3999

#### GENERAL NOTES

- ALL MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE GENERAL AND SPECIFIC PROVISIONS, STANDARD DRAWINGS, AND REQUIREMENTS OF COUNTY OF SAN MATEO.
- CONTRACTOR SHALL SECURE A STREET OPENING PERMIT FROM 2. THE COUNTY ENGINEERING DEPARTMENT AND PAY APPROPRIATE FEE PRIOR TO COMMENCEMENT OF WORK. ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE DONE UNDER A SINGLE STREET OPENING PERMIT.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES WITH THE APPROPRIATE UTILITY AGENCIES PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. CONTRACTOR SHALL NOTIFY ALL PUBLIC AND PRIVATE UTILITY OWNERS 48 HOURS PRIOR TO COMMENCEMENT OF WORK ADJACENT TO THE UTILITY CONTACT UNDERGROUND SERVICE ALERT (USA) AT 800/642-2444.
- EXISTING UTILITIES SHOWN ARE BASED UPON RECORD INFORMATION AND ARE APPROXIMATE IN LOCATION AND DEPTH. MAY BE AFFECTED BY NEW FACILITIES IN THIS CONTRACT. VERIFY ACTUAL LOCATION AND DEPTH, AND REPORT POTENTIAL CONFLICTS TO THE ENGINEER PRIOR TO EXCAVATION FOR NEW FACILITIES.
- IT IS THE CONTRACTORS RESPONSIBILITY TO REPLACE ALL STREET MONUMENTS, LOT CORNER PIPES, AND GRADE STAKES DISTURBED DURING THE PROCESS OF CONSTRUCTION AT THE REGULAR ENGINEER'S FEE.
- PROVIDE CONCRETE PROTECTION BETWEEN UNDERGROUND PIPE CROSSINGS WITH 12" OR LESS VERTICAL CLEARANCE.
- ALL SURPLUS AND UNSUITABLE MATERIAL SHALL BE REMOVED FROM PROJECT SITE AND FROM PUBLIC RIGHT-OF-WAY.
- CONTRACTOR SHALL PROVIDE ADEQUATE DUST CONTROL AND KEEP MUD AND DEBRIS OFF THE PUBLIC RIGHT-OF-WAY AT ALL TIMES.
- ALL TRENCHES AND EXCAVATIONS SHALL BE CONSTRUCTED IN STRICT COMPLIANCE WITH THE APPLICABLE SECTIONS OF CALIFORNIA AND FEDERAL O.S.H.A. REQUIREMENTS AND OTHER APPLICABLE SAFETY ORDINANCES. CONTRACTOR SHALL BEAR FULL RESPONSIBILITY FOR TRENCH SHORING DESIGN AND INSTALLATION.
- GRADE BREAKS ON CURBS AND SIDEWALKS ARE TO BE ROUNDED OFF ON FORM WORK AND FINISHED SURFACING.
- CONTRACTOR SHALL PERFORM HIS CONSTRUCTION AND OPERATION IN MANNER WHICH WILL NOT ALLOW HARMFUL POLLUTANTS TO ENTER THE STORM DRAIN SYSTEM. TO ENSURE COMPLIANCE, THE CONTRACTOR SHALL IMPLEMENT THE APPROPRIATE BEST MANAGEMENT PRACTICE (BMP) AS OUTLINED 12. ALL EXISTING FRONTAGE IMPROVEMENTS (CURB, GUTTER, IN THE BROCHURES ENTITLED BEST MANAGEMENT PRACTICES FOR THE CONSTRUCTION INDUSTRY" ISSUED BY THE SAN MATEO COUNTYWIDE STORM WATER POLLUTION PREVENTION PROGRAM, TO SUIT THE CONSTRUCTION SITE AND JOB CONDITION, THE CONTRACTOR SHALL PRESENT HIS PROPOSED BMP AT THE PRECONSTRUCTION MEETING FOR DISCUSSION AND APPROVAL.
- OVERNIGHT PARKING OF CONSTRUCTION EQUIPMENT IN THE STREET RIGHT-OF-WAY SHALL NOT BE PERMITTED, EXCEPT AT LOCATION(S) APPROVED BY THE COUNTY.
- THE CONTRACTOR SHALL OBTAIN AN ENCROACHMENT PERMIT FROM THE COUNTY'S ENGINEERING DIVISION FOR ALL WORK WITHIN THE PUBLIC RIGHT OF WAY
- THE STORM RUNOFF GENERATED BY THE NEW PROJECT SHALL NOT DRAIN ONTO ADJACENT PROPERTIES. THE EXISTING STORM DRAINAGE FROM THE ADJACENT PROPERTIES SHALL NOT BE BLOCKED BY THE NEW DEVELOPMENT.

#### GRADING NOTES

- CONTRACTOR SHALL CONTACT U.S.A. AT LEAST 48 HOURS PRIOR TO EXCAVATING IN ANY AREA WHERE UNDERGROUND FACILITIES ARE LOCATED. PHONE (800)642-2444.
- THE EXISTENCE, LOCATION AND ELEVATION OF ANY UNDERGROUND UTILITIES ARE SHOWN IN A GENERAL WAY ONLY. IT WILL BE THE RESPONSIBILITY AND DUTY OF THE CONTRACTOR TO MAKE FINAL DETERMINATIONS AS TO THE EXISTENCE, LOCATION AND ELEVATION OF ALL UTILITIES.
- 3. THE SITE SHALL BE CLEARED OF ALL EXISTING STRUCTURES, CONCRETE FOOTINGS, PAVEMENT, LANDSCAPING MATERIALS AND UNDERGROUND UTILITIES.
- FINISHED GRADES ALONG THE PERIMETER OF THE FOUNDATION TO BE SLOPED AT A MINIMUM OF 5% FOR FIRST 5 FEET.
- ALL CONCRETE SHALL BE CLASS "A" CONFORMING TO SECTION 90 OF CALTRANS SPECIFICATIONS AND SHALL DEVELOP A COMPRESSIVE STRENGTH OF 3,000 PSI AT 28 DAYS PER CALIFORNIA TEST METHOD
- THE CONTRACTOR SHALL POTHOLE ALL EXISTING UTILITIES THAT 6. ASPHALT CONCRETE PAVEMENT SHALL BE TYPE B, 3/4" MAXIMUM, MEDIUM WITH SLURRY SEAL COAT. ASPHALT CONCRETE SHALL BE PLACED IN ONE OR MORE LIFTS TO THE MINIMUM TOTAL THICKNESS SHOWN ON THE PLANS. THE MAXIMUM THICKNESS OF EACH LIFT SHALL NOT EXCEED THREE (3) INCHES.
  - AGGREGATE BASE SHALL BE PLACED BENEATH ALL SIDEWALK, CURB AND GUTTER, AND ASPHALT CONCRETE PAVEMENT AS SHOWN ON THE PLANS. AGGREGATE BASE SHALL BE CLASS 2, 1-1/2" MAXIMUM COMPACTED TO AT LEAST 95" RELATIVE COMPACTION PER ASTM D1557-91
  - ON-SITE UTILITY TRENCHES SHALL BE BACKFILLED WITH COMPACTED ENGINEERED FILL. THE FILL MATERIAL SHALL BE PLACED IN LIFTS NOT TO EXCEED EIGHT (8) INCHES IN UNCOMPACTED THICKNESS AND SHALL BE MECHANICALLY COMPACTED TO AT LEAST 90% RELATIVE COMPACTION.
  - 9. ALL UTILITIES SHALL BE UNDERGROUND FROM THE PROPERTY LINES IN. LOCATION OF METERS ARE AS NOTED. COORDINATE ALL SUCH WORK WITH THE UTILITY COMPANY HAVING JURISDICTION.
  - STORM DRAIN POLLUTION PREVENTION. PROTECT DOWNSLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH HAY BALES, TEMPORARY DRAINAGE SWALES, SILT FENCES, BERMS OR STORM DRAIN INLET FILTERS COVER STOCK PILES AND EXCAVATED SOIL WITH SECURED TARPS OR PLASTIC SHEETING.
  - CONTACT PUBLIC WORKS TO SCHEDULE AN INSPECTION A MINIMUM OF 24 HOURS IN ADVANCE OF COMMENCEMENT OF PUBLIC IMPROVEMENT WORK TO SCHEDULE A PRE-CONSTRUCTION MEETING AND FOR EACH SUBSEQUENT DAY OF WORK IN THE PUBLIC RIGHT OF WAY.
  - SIDEWALK, VALLEY GUTTER, PARKING STRIP) THAT ARE DAMAGE DURING THE COURSE OF CONSTRUCTION MUST BE REPAIRED TO "AS NEW" CONDITION. COUNTY WILL NOT BEAR THE COSTS OF
  - 13. ALL WORK WITHIN THE PUBLIC RIGHT OF WAY SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF THE COUNTY OF SAN MATEO STANDARD DETAILS. ALL DETAILS APPLICABLE TO THE PARTICULAR CONSTRUCTION ACTIVITY SHALL BE UTILIZED
    - ALL IMPROVEMENTS IN THE PUBLIC RIGHT OF WAY ARE TO BE COMPLETED AND APPROVED BY THE CONSTRUCTION SUPERVISOR PRIOR TO FINAL INSPECTION BY THE BUILDING INSPECTOR.
  - 15. DATE OF SURVEY: XXXX, 2021
  - 16. ALL GRADING DURING THE RAINY SEASON (OCT. 1ST THROUGH APRIL 30TH) REQUIRES AND EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE CITY. STORMWATER POLLUTION PREVENTION MEASURES SHALL BE IMPLEMENTED THROUGHOUT THE YEAR, TO THE SATISFACTION OF THE CONSTRUCTION SUPERVISOR.
  - 17. ALL CHANGES TO THE APPROVED GRADING AND DRAINAGE PLAN REQUIRE A PLAN MODIFICATION APPROVAL BY THE COUNTY IN ADVANCE OF CONSTRUCTION THE CHANGE. THE PROPOSED PLAN CHANGE MUST BE GENERATED FROM THE ENGINEER/ARCHITECT WHO ORIGINALLY PREPARED THE PLAN.
  - 18. ANY DEVIATION FROM THE APPROVED PLAN AND/OR FAILURE TO OBTAIN GRADING AND DRAINAGE INSPECTION MAY AFFECT THE PUBLIC WORKS SIGN-OFF FOR BUILDING FINAL AND/OR OCCUPANCY.

#### LAND SURVEY

SURVEY COMPLETED BY B&H LAND SURVEYING 901 WALTERMIRE STREET, BELMONT, CA 94001 PHONE 650-637-1590

LOT AREA

4520 SQ. FT. +/-

#### BASIS OF ELEVATIONS:

ELEVATIONS ARE BASED UPON AN ASSUMED DATUM.

TBM: NAIL AND SHINER SET AT EDGE OF ROAD POINT NUMBER 111 ELEVATION = 445.93'

# BASIS OF BEARINGS:

THE BEARING N 49°05'40" W ON THE NORTHEASTERLY LINE OF LOT 104, BLOCK 15, AS SHOWN ON 13 MAPS 51, WAS TAKEN AS THE BASIS OF BEARINGS FOR THIS SURVEY.

#### **ABBREVIATIONS**

ASPHALT CONCRETE ASSESSORS PARCEL NUMBER BACK FLOW PREVENTER BUILDING CATCH BASIN CO CLEAN OUT CONCRETE CONTROL POINT DOWN SPOUT DRIVEWAY EXISTING ELECTRICAL METER FACE OF CURB FINISH FLOOR FINISH GRADE FIRE HYDRANT GAS/GROUND GAS METER PIPE INVERT

JOINT POLE


LIGHT WELL

MAN HOLE MONUMENT NEW PROPERTY LINE PARCEL MAP PAVEMENT ROOF DRAIN TOP OF GRATE STORM DRAIN STORM DRAIN MANHOLE SANITARY SEWER SANITARY SEWER CLEANOUT SIDEWALK TEMPORARTY BENCH MARK VALLEY GUTTER WATER WOOD FENCE WDF WATER METER

WATER VALVE

EXISTING

FF=429.63 LEVEL BOTTOM OF SILL TO ADJ. SOIL FINISHED GRADE SEE STRUCTURE PLANS FOR =11= 111= STRUCTURAL DESIGN



SEE STR. & ARCH. PLANS

ON-SITE ONLY

CB (CHRISTY BOX V24)

DRAIN BOX W/

18" X 19.5" GRATE

ELEV.=425.9

000 000 000 

00000000000000

00000000000

13'LONG

LIMITED TO 40% OF TOTAL BED

DRAIN ROCK RETENTION BASIN

SCALE: NOT TO SCALE

3'x

NOTE: WATER RETENTION

CAPACITY OF BED IS

VOLUME.

0 0 0 0 0 0 0 0 0 0

4" SD PVC

INV=424.5

<u>+11==+11=1</u>

=<u></u>±11=

4" PVC SCH. 40

PERFORATED PIPE W/

HOLES FACING DOWN

RETENTION CALCULATIONS

VOLUME OF DRAIN ROCK REQUIRED PER CALCULATIONS

USE 3' X 11' FOOTPRINT WITH 4.5' DEPTH OF ROCK

VOL OF DRAIN ROCK=3'x11'X4.5'DEEP=148.5CF

TOP OF ROCK SEE NOTE BELOW

BOTTOM OF ROCK

V(CF) = 143CF

VOLUME OF DRAIN ROCK

TOTAL VOL. OF VOIDS=59.4 CF

±11==±11= ±11=

-=11= =±11= ±11=

GEO-TEXTILE FABRIC

TO ENCLOSE ALL

DRAIN ROCK

-3/4"-1 1/2" DRAIN ROCK

175CF OF DRAIN ROCK

CONCEPTUAL PERIMETER FOOTING-TYPE 2 CLEARANCE WITH CONCRETE APRON

SCALE: N.T.S

LEGEND PROPOSED DESCRIPTION PROPERTY LINE STORM DRAIN SANITARY SEWER GAS

DOWN SPOUT

CATCH BASIN (CB)

FIBER ROLL RETENTION ROCK FOOTPRINT

TEMPORARY ORANGE TREE PROTECTION FENCING

 $\overline{\triangleleft}$  $\triangleleft$ ADIN   $\bigcirc$ 

4 jn

9

 $\bigcirc$ 

 $\bigcup_{L} \rightarrow 4$ 

 $\triangleleft$ 

 $Z \vdash$ 

WINDII N MA

0,0


DESCRIPTION

Z O

 $\Box$ 

# GEOTECHNICAL REPORT

ALL WORK TO BE COMPLETED IN CONFORMANCE WITH THE GEOTECHNICAL REPORT PREPARED BY ROMIG ENGINEERS PROJECT NO. 5286-1, DECEMBER 2020. PHONE: 650-591-5224



FACTOR ON ALL CUT MATERIAL. ESTIMATE DOES NOT INCLUDE VOLUMES FOR CLEARING AND GRUBBING. ALL TOPSOIL FROM CUT CAN BE USED IN TOP ' OF LANDSCAPE. CONTRACTOR TO MAKE OWN ESTIMATES OF QUANTITIES FOR BIDDING PURPOSES BASED ON ALL PLANS.

# SHEET INDEX

- C1 NOTES & DETAILS
- C2 GRADING AND DRAINAGE PLAN

C3 EROSION CONTROL, STAGING AND

TREE PROTECTION PLAN

C3A EROSION CONTROL NOTES & DETAILS C4 BEST MANAGEMENT PRACTICES PLAN




JOB NO. 21081 SCALE: AS SHOWN YC DRAWN BY: CHECKED BY: SH DATE: 10/18/21

SHEET

DATE

OF 5 SHEETS



CONSULTIN AND  $\triangleleft$  $\stackrel{\cdot}{\mathsf{m}}$ 





940<sup>7</sup> ATED AND Z -AGING EROSION C TREE 40 WINDING V SAN MATEO 40 S/

REVISIONS DATE | DESCRIPTION

JOB NO. 21081

SCALE: AS SHOWN DRAWN BY: YC CHECKED BY: SH

DATE: 10/18/21

SHEET



OF 5 SHEETS

1.Erosion Control Point of Contact. (Please provide an Erosion Control Point of Contact including name, title/qualification, email, and phone number. The EC Point of Contact will be the County's main point of contact if Erosion Control or Tree Protection corrections are required).

Name: \_\_\_\_\_ Title: \_\_\_\_\_ Phone Number: \_\_\_\_\_

2.Perform clearing and earth-moving activities only during dry weather. Measures to ensure adequate erosion and sediment control shall be installed prior to earth—moving activities and construction.

3. Measures to ensure adequate erosion and sediment control are required year—round. Stabilize all denuded areas and maintain erosion control measures continuously between October 1 and April 30.

4.Store, handle, and dispose of construction materials and wastes properly, so as to prevent their contact with stormwater.

5. Control and prevent the discharge of all potential pollutants, including pavement cutting wastes, paints, concrete, petroleum products, chemicals, wash water or sediments, and non-stormwater discharges to storm drains and watercourses.

6.Use sediment controls or filtration to remove sediment when dewatering site and obtain Regional Water Quality Control Board (RWQCB) permit(s) as necessary.

7. Avoid cleaning, fueling, or maintaining vehicles on—site, except in a designated area where wash water is contained and treated.

8.Limit and time applications of pesticides and fertilizers to prevent polluted runoff.

9.Limit construction access routes to stabilized, designated access

10. Avoid tracking dirt or other materials off—site; clean off—site paved areas and sidewalks using dry sweeping methods.

11. Train and provide instruction to all employees and subcontractors regarding the Watershed Protection Maintenance Standards and Construction Best Management Practices.

12.Placement of erosion materials at these locations are required on weekends and during rain events: (List locations)

13. The areas delineated on the plans for parking, grubbing, storage, etc., shall not be enlarged or ?run over.?

14. Construction sites are required to have erosion control materials on—site during the ?off—season.?

15.Dust control is required year-round.

16.Erosion control materials shall be stored on—site.

17.Use of plastic sheeting between October 1 and April 30 is not acceptable, unless for use on stockpiles where the stockpile is also protected with fiber rolls containing the base of the stockpile.

18. Tree protection shall be in place before any demolition, grading, excavating or grubbing is started.

Erosion Control Notes: 1.All erosion control measures shall be onsite and

readily accessible prior to construction.

2. Sweep or scrape up soils tracked onto the road at the end of each day. Do not hose into street, gutter or storm drain.

3.Revegetate disturbed areas. Exposed bare dirt shall be covered with mulch, jut netting or other erosion control blanket.

4.All temporary stockpiles shall be covered with 6 mil. Plastic sheets, suitable anchored.

5.The site shall be monitored by the contractor/owner after rain event to verify erosion control measures are functioning.

NOTE: MAX. DEPTH OF BED IS LIMITED TO 2FT & BED MUST BE LOCATED AT LEAST 10FT AWAY FROM NEAREST PROPERTY LINE & TREE.

EST. DIMENSIONS OF GRAVEL BED: WIDTH = 4FT -

LENGTH = 4FT PER DETAIL BELOW DEPTH = 2 FT -

MAINTENANCE NOTES

1. MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:

A. REPAIR DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION AT THE END OF EACH WORKING DAY.

SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED. SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM

AND REPAIRS MADE AS NEEDED.

SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1 FOOT.


SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.


F. RILLS AND GULLIES MUST BE REPAIRED.

2. SAND BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE SAND BAG.

1" X 2" X 24" WOOD STAKE **—** 0.2405 STRAW ROLL EXISTING GROUND

ON SLOPES






1. PLACE STRAW ROLL IN TRENCH EXCAVATED 3" (0.024') INTO GROUND ALONG CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.. 2. ON SLOPES PLACE ROLL TO FOLLOW THE CONTOUR AS CLOSELY AS POSSIBLE. CURVE ENDS UPHILL AT THE

3. ABUT ADJACENT ROLLS TIGHTLY.

STRAW ROLL OR FIBER ROLL SCALE: NTS



NOT TO SCALE

INLET PROTECTION IN UNPAVED AREAS SCALE: NTS

RAINAGE IND DET ROSION TREE WINDING

Ο

94( \TE

OTECAY, S.

WA OO

40 S/

REVISIONS

DESCRIPTION

 $\cong$ 

DATE

JOB NO. 21081

SCALE: AS SHOWN

 $\bigcirc$ 

 $\geq$ 

CONSUL

 $\mathbb{Z}$ 

 $\triangleleft$ 

 $\triangleleft$  $\stackrel{\cdot}{\Box}$ 

NOTES:
BRING THE DISTURBED AREA TO THE GRADE OF THE DROP INLET AND SMOOTH AND COMPACT IT. APPROXIMATELY STABILIZE ALL BARE AREAS AROUND THE INLET.

CATCH BASIN —

W/ INLET FILTER

SCALE: NTS

PROPERLY DISPOSE OF ACCUMULATED SEDIMENT

INSPECT ALL INLET PROTECTION DEVICES BEFORE AND AFTER RAINFALL EVENTS, AND WEEKLY THROUGHOUT THE RAIN SEASON. DURING EXTENDED RAINFALL EVENTS, INSPECT INLET PROTECTION DEVICES AT LEAST ONCE EVERY 24 HOURS.

REMOVE ALL INLET PROTECTION DEVICES WITHIN THIRTY DAYS AFTER THE SITE IS STABILIZED, OR WHEN INLET PROTECTIONS IS NO LONGER REQUIRED.

CATCH BASIN INLET FILTER

INSTALLATION REMOVE DRAIN GRATE

INSERT CATCH BASIN FILTER INTO BASIN LEAVING 3" FLAP EXPOSED

REPLACE GRATE TO BASIN THEREBY PINCHING FABRIC BETWEEN GRATE AND CATCH BASIN AND HOLDING FILTER IN PLACE

INSPECTION AND MAINTENANCE

INSPECT CATCH BASIN FILTERS WEEKLY AND AFTER EVERY RAIN


EMPTY CATCH BASIN FILTERS WHEN FILTERS APPEAR TO BE HALF FULL

DISPOSE OF TRAPPED SEDIMENT IN ACCORDANCE WITH LOCAL REQUIREMENTS

CLEAN AND REUSE INLET FILTERS OR DISCARD AND REPLACE AS NECESSARY

STORM DRAIN INLET PROTECTION PUBLIC STREET


BASIN



DETAIL TREE PROTECTION WRAP WITH STRAW ROLL

SCALE: NTS






SHEET OF 5 SHEETS Clean Water. Healthy Community.

# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

# **Materials & Waste Management**



#### **Non-Hazardous Materials**

- ☐ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ☐ Use (but don't overuse) reclaimed water for dust control.

#### **Hazardous Materials**

- ☐ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ☐ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ☐ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ☐ Arrange for appropriate disposal of all hazardous wastes.

#### Waste Management

- Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ☐ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ☐ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ☐ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ☐ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

#### **Construction Entrances and Perimeter**

- ☐ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ☐ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

# **Equipment Management & Spill Control**




#### **Maintenance and Parking**

- ☐ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ☐ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ☐ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ☐ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ☐ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

#### **Spill Prevention and Control**

- ☐ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ☐ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ☐ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ☐ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ☐ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ☐ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

#### **Earthmoving**




- ☐ Schedule grading and excavation work during dry weather.
- ☐ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ☐ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ☐ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

#### **Contaminated Soils**

- ☐ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
- Unusual soil conditions, discoloration, or odor.
- Abandoned underground tanks.
- Abandoned wells
- Buried barrels, debris, or trash

Storm drain polluters may be liable for fines of up to \$10,000 per day!

# Paving/Asphalt Work




- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ☐ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ☐ Collect and recycle or appropriately dispose of excess abrasive gravel or sand Do NOT sweep or wash it into gutters.
- ☐ Do not use water to wash down fresh asphalt concrete pavement.

#### **Sawcutting & Asphalt/Concrete Removal**


- ☐ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ☐ Shovel, abosorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ☐ If sawcut slurry enters a catch basin, clean it up immediately.

# Concrete, Grout & Mortar




- ☐ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ☐ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ☐ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

# **Landscaping** <sub>s</sub>



- ☐ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ☐ Stack bagged material on pallets and under cover.
- ☐ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.


# **Painting & Paint Removal**



#### **Painting Cleanup and Removal**

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ☐ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ☐ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ☐ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ☐ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a statecertified contractor.

#### **Dewatering**



- ☐ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant
- ☐ Divert run-on water from offsite away from all disturbed areas.
- ☐ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ☐ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal



GE CE C/ DRAINAC PRACTIC CARLOS, MEI, S, GRADING ST MANAGEI WINDING WAY,

REVISIONS DATE | DESCRIPTION

JOB NO. 21081 SCALE: AS SHOWN DRAWN BY: YC CHECKED BY: SH

SHEET

DATE: 09/18/21

OF 4 SHEETS